



PRINCIPLE OF HOT WATER HEATING ILLUSTRATED BY TRANSVERSE SECTIONAL VIEW SHOWING BOILER, RADIATOR AND EXPANSION TANK.

American Radiator Company.

Cyclopedia
of
Heating, Plumbing and Sanitation

A Complete Reference Work

ON PLUMBING, GAS FITTING, SEWERS AND DRAINS, HEATING AND VENTILATING, STEAM FITTING, CHEMISTRY, BACTERIOLOGY AND SANITATION, HYDRAULICS, WATER SUPPLY, ELECTRIC WIRING, MECHANICAL DRAWING, SHEET METAL WORK, ETC.

Prepared by a Corps of

SANITARY EXPERTS, CONSULTING ENGINEERS, AND SPECIALISTS OF THE HIGHEST PROFESSIONAL STANDING

Illustrated with over One Thousand Engravings

FOUR VOLUMES

CHICAGO
AMERICAN TECHNICAL SOCIETY
1909

COPYRIGHT, 1909

BY

AMERICAN SCHOOL OF CORRESPONDENCE

COPYRIGHT, 1909

BY

AMERICAN TECHNICAL SOCIETY

Entered at Stationers' Hall, London.

All Rights Reserved.

142892
JUN 4 1910
SX
·AM3
2
660407

Authors and Collaborators

CHARLES B. BALL
Civil and Sanitary Engineer
Chief Sanitary Inspector, City of Chicago
American Society of Civil Engineers
President, American Society of Inspectors of Plumbing and Sanitary Engineers

WILLIAM T. McCLEMENT, A. M., D. Sc.
Head, Department of Botany, Queen's University, Kingston, Can.
Formerly Professor of Chemistry, Armour Institute of Technology

WILLIAM G. SNOW, S. B.
Steam Heating Specialist
American Society of Mechanical Engineers

GLENN M. HOBBS, Ph. D.
Secretary, American School of Correspondence
Formerly Instructor in Physics, University of Chicago
Member, American Physical Society

CHARLES L. HUBBARD, S. B., M. E.
Consulting Engineer on Heating, Ventilating, Power, and Lighting

WILLIAM BEALL GRAY
Sanitary and Heating Engineer
Lecturer on Plumbing, Young Men's Institute, Louisville, Ky.
Member, National Association of Master Plumbers
Author of "House Heating," "Joint Wiping," etc.

DARWIN S. HATCH, B. S.
Assistant Editor, Textbook Department, American School of Correspondence

LOUIS DERR, M. A., S. B.
Associate Professor of Physics, Massachusetts Institute of Technology

WILLIAM NEUBECKER
Instructor, Sheet Metal Department, New York Trade School

FREDERICK E. TURNEAURE, C. E., Dr. Eng.
Dean of the College of Engineering, and Professor of Engineering, University of Wisconsin
American Society of Civil Engineers

CHARLES E. KNOX, E. E.
Consulting Electrical Engineer

EDWARD B. WAITE
Head of Instruction Department, American School of Correspondence
American Society of Mechanical Engineers
Western Society of Engineers

MAURICE LeBOSQUET, S. B.
Director, American School of Home Economics
American Chemical Society, British Society of Chemical Industry, etc.

THOMAS E. DIAL, B. S.
Instructor in Civil Engineering, American School of Correspondence
Formerly with Engineering Department, Atchison, Topeka, & Santa Fé Railroad

ANSON MARSTON, C. E.
Dean of the Division of Engineering, and Professor of Civil Engineering, Iowa State College
American Society of Civil Engineers
Western Society of Civil Engineers

ERNEST L. WALLACE, S. B.
Instructor in Electrical Engineering, American School of Correspondence
American Institute of Electrical Engineers

ERVIN KENISON, S. B.
Assistant Professor of Mechanical Drawing and Descriptive Geometry, Massachusetts Institute of Technology

CHARLES L. GRIFFIN, S. B.
Assistant Engineer, The Solvay-Process Co.
American Society of Mechanical Engineers

HARRIS C. TROW, S. B., *Managing Editor*
Editor-in-Chief, Textbook Department, American School of Correspondence
American Institute of Electrical Engineers

Authorities Consulted

THE editors have freely consulted the standard technical literature of America and Europe in the preparation of these volumes. They desire to express their indebtedness, particularly, to the following eminent authorities, whose well-known treatises should be in the library of everyone interested in Sanitary Engineering.

Grateful acknowledgment is here made also for the invaluable co-operation of the foremost Engineering Firms and Manufacturers in making these volumes thoroughly representative of the latest and best practice in every branch of the broad field of Heating, Plumbing, and Sanitation; also for the valuable drawings, data, suggestions, criticisms, and other courtesies.

R. M. STARBUCK

Author of "Modern Plumbing Illustrated," "Questions and Answers on the Practice and Theory of Sanitary Plumbing," "Questions and Answers on the Practice and Theory of Steam and Hot Water Heating," "Hot Water Circulation, Illustrated," etc.

A. PRESCOTT FOLWELL

Editor of *Municipal Journal and Engineer*; Formerly Professor of Municipal Engineering, Lafayette College; Member of American Society of Civil Engineers; Past President, American Society of Municipal Improvement.
Author of "Water Supply Engineering," "Sewerage," etc

MANSFIELD MERRIMAN

Professor of Civil Engineering in Lehigh University.
Author of "Sanitary Engineering," "A Treatise on Hydraulics," etc.

ROLLA C. CARPENTER, C. E., M. M. E.

Professor of Experimental Engineering, Cornell University.
Author of "Heating and Ventilating Buildings."

H. T. SHERRIFF, A. B.

Editor of *Domestic Engineering*; Member American Society Inspectors of Plumbing and Sanitary Engineering.
Joint Author with Chas. B. Ball of "Theory and Practice of Plumbing Design."

H. de B. PARSONS

Consulting Engineer; Member of American Society of Civil Engineers; Member of American Society of Mechanical Engineers.
Author of "The Disposal of Municipal Refuse," etc.

JOSEPH P. FRIZELL

Hydraulic Engineer and Water-Power Expert; American Society of Civil Engineers.
Author of "Water Power, the Development and Application of the Energy of Flowing Water."

CHARLES EDWARD AMORY WINSLOW

Assistant Professor of Sanitary Biology, Massachusetts Institute of Technology.
Joint Author with Samuel Cate Prescott of "Elements of Water Bacteriology."

JOHN W. HART, R. P. C.

Associate of the Sanitary Institute; Instructor and Lecturer on Practical and Technical Plumber's Work at the Goldsmith Institution, The Croyden County Polytechnic.
Author of "External Plumbing Work," "Principles of Hot Water Supply," "Hints to Plumbers," "Sanitary Plumbing and Drainage."

WM. T. SEDGWICK, Ph. D.

Professor of Biology and Lecturer on Sanitary Science and the Public Health in the Massachusetts Institute of Technology, Boston.
Author of "Principles of Sanitary Science and the Public Health."

SAMUEL CATE PRESCOTT

Assistant Professor of Industrial Biology, Massachusetts Institute of Technology.
Joint Author with Charles Edward Amory Winslow of "Elements of Water Bacteriology."

WM. J. BALDWIN

Member, American Society of Civil Engineers; Member, American Society of Mechanical Engineers.
Author of "Heating."

S. STEVENS HELLYER

Author of "The Plumber and Sanitary Houses," "Lectures on the Science and Art of Sanitary Plumbing," "Principles and Practice of Plumbing."

M. N. BAKER, Ph. B., C. E.

Associate Editor of *Engineering News*.
Author of "Municipal Engineering and Sanitation."

M. NISBET-LATTA

Member, American Gas Institute; Member, American Society of Mechanical Engineers.
Author of "Handbook of American Gas-Engineering Practice."

WILLIAM T. MASON

Professor of Chemistry, Rensselaer Polytechnic Institute; American Public Health Association; Sanitary Institute (Great Britain); American Water-Works Association.
Author of "Water Supply."

MAURICE LEBOSQUET, S. B.

Director, American School of Home Economics; Member of Public Health Association.
Author of "Personal Hygiene."

Authorities Consulted—Continued

LEVESON FRANCIS VERNON-HARCOURT, M. A.

Emeritus Professor of Civil Engineering and Surveying, University College; British Member of the International Commissions for Suez Canal Works.
Author of "Sanitary Engineering with Respect to Water Supply and Sewage Disposal," "Rivers and Canals," etc.

GEORGE CHANDLER WHIPPLE

Consulting Professor of Water Analysis, Brooklyn Polytechnic Institute; Member of Society of American Bacteriologists; Member of American Public Health Association; Member of American Water-Works Association; etc.
Author of "The Microscopy of Drinking Water."

FREDERICK E. TURNEAURE, C. E., Dr. Eng.

Dean, College of Engineering, Professor of Engineering, University of Wisconsin.
Joint Author of "Public Water Supplies," "Theory and Practice of Modern Framed Structures," "Principles of Reinforced Concrete Construction."

WM. S. MONROE, M. E.

Member, American Society of Mechanical Engineers; Member, American Society of Heating and Ventilating Engineers; Member, Western Society of Engineers.
Author of "Steam Heating and Ventilation."

F. H. KING

Formerly Professor of Agricultural Physics, University of Wisconsin.
Author of "Ventilation," "Irrigation and Drainage," "The Soil," etc.

H. N. OGDEN, C. E.

Assistant Professor of Civil Engineering, Cornell University.
Author of "Sewer Design," "Sewer Construction."

JAMES H. FUERTES

Member of the American Society of Civil Engineers.
Author of "Water and Public Health," "Water Filtration Work."

CHAS. B. THOMPSON

Author of "House Heating by Steam and Water."

REGINALD E. MIDDLETON

M. Inst. C. E.; M. Inst. Mech. E.; F. S. I.
Author of "Water Supply."

JAMES J. LAWLER

Author of "Modern Plumbing, Steam and Hot-Water Heating," "American Sanitary Plumbing," "Hot Water Heating and Steam Fitting."

ALLEN HAZEN

Member of American Society of Civil Engineers; Boston Society of Civil Engineers; American Water-Works Association; New England Water-Works Association; etc.

Author of "The Filtration of Public Water Supplies."

DR. HARVEY B. BASHORE

Inspector for the Pennsylvania Department of Health.

Author of "Outlines of Practical Sanitation," "Outlines of Rural Hygiene," "The Sanitation of a Country House."

WM. PAUL GERHARD, C. E.

Consulting Engineer for Sanitary Works; Member of American Public Health Association, etc.

Author of "Sanitary Engineering," "A Guide to Sanitary House Inspection."

SAMUEL RIDEAL, D. Sc.

Fellow of University College, London; Fellow of the Institute of Chemistry; Public Analyst for Lewisham District Board of Works; etc.

Author of "Disinfection and Disinfectants," "Water and its Purification," etc.

HALBERT P. GILLETTE

Editor of *Engineering Contracting;* American Society of Civil Engineers; Late Chief Engineer, Washington State Railroad Commission.

Author of "Handbook of Cost Data for Contractors and Engineers."

JOHN W. HARRISON

Member Royal Sanitary Institute; Member Incorporated Association of Municipal and County Engineers; Formerly Inspector of Nuisances, Bradford, England, etc.

Author of "Lessons on Sanitation."

W. GRAFTON

Author of "Handbook of Practical Gas-Fitting."

GEORGE B. CLOW

Author of "Practical Up-To-Date Plumbing."

WM. MAYO VENABLE, M. S.

Member, American Society of Civil Engineers; Associate Member, American Institute of Electrical Engineers.

Author of "Methods and Devices for Bacterial Treatment of Sewage," "Garbage Crematories in America."

ALFRED G. KING

Author of "Steam and Hot Water Heating Charts," "Practical Heating Illustrated," etc.



TRANSVERSE SECTIONAL VIEW OF COLONIAL MODEL HOUSE, SHOWING INSTALLATION OF HEATING PLANT.
Exhibited by the American Radiator Company at the St. Louis World's Fair, in 1904.

Foreword

THE widespread need for a more scientific knowledge of the principles of Sanitation on the part of thousands of practical men of limited education, calls for an authoritative work of general reference embodying the results of modern experience and the latest approved practice. The Cyclopedia of Heating, Plumbing, and Sanitation is designed to fill this acknowledged need.

¶ The Cyclopedia of Heating, Plumbing, and Sanitation is based upon the method which the American School of Correspondence has developed and successfully used for many years in teaching the principles and practice of engineering in its different branches. It is a compilation of representative Instruction Books of the School, and forms a simple, practical, concise, and convenient reference work for the shop, the library, the school, and the home.

¶ The success which the American School of Correspondence has attained as a factor in the machinery of modern technical and scientific education, is in itself the best possible guarantee for the present work. Therefore, while these volumes are a marked innovation in technical literature—representing, as they do, the best ideas and methods of a large number of *different* authors, each an acknowledged authority in his work—they are by no means an experiment, but are in fact based on what has

proved itself to be the most successful method yet devised for the education of the busy workingman. They have been prepared only after the most careful study of modern needs as developed under the conditions of actual practice.

¶ Neither pains nor expense have been spared to make the present work the most comprehensive and authoritative in its field. The aim has been, not merely to create a work which will appeal to the trained expert, but one that will commend itself also to the beginner and the self-taught, practical man by giving him a working knowledge of the principles and methods, not only of his own particular trade, but of all allied branches of it as well. The various sections have been prepared especially for home study, each written by an acknowledged authority on the subject. The arrangement of matter is such as to carry the student forward by easy stages. Series of review questions are inserted in each volume, enabling the reader to test his knowledge and make it a permanent possession. The illustrations have been selected with unusual care to elucidate the text.

¶ Grateful acknowledgment is due the corps of authors and collaborators—men of wide practical experience, and teachers of well-recognized ability—without whose hearty co-operation this work would have been impossible.

Table of Contents

VOLUME II

HEATING AND VENTILATION . . *By Chas. L. Hubbard*† Page *11

Systems of Warming—Stoves—Hot-Air Furnaces—Direct and Indirect Steam Heating—Radiators—Direct and Indirect Hot-Water Heating—Exhaust Steam Heating—Forced Blast—Principles of Ventilation—Quantity of Air Required—Air-Distribution—Heat Loss from Buildings—Direct-Draft and Indirect-Draft Furnaces—Furnace Details (Grates, Firepot, Dome, Radiator, Heating Surface, Efficiency, Heating Capacity)—Location of Furnace—Smoke-Pipes—Flues—Cold-Air Box—Return Duct—Warm-Air Pipes—Registers—Combination Systems—Care and Management of Furnaces—Steam Boilers, Sectional and Tubular—Water-Tube Boilers—Radiators for Direct Steam—Circulation Coils—Systems of Piping (Two-Pipe, One-Pipe Relief, and One-Pipe Circuit)—Air-Valves—Pipe Sizes—Blow-Off Tank—Types of Indirect-Steam Heaters—Hot-Water Piping—Overhead Distribution—Expansion Tank—Combination Systems of Heating—Forced Hot-Water Circulation—Grease Extractor for Exhaust Steam—Back-Pressure Valve—Exhaust Head—Return Pumps and Traps—Damper Regulators—Vacuum Systems (Webster, Paul)—Forced Blast (Exhaust and Plenum Methods)—Fans and Blowers—Factory Heating—Double-Duct System—Electric Heating—Temperature Regulators—Telethermometer—Humidostat—Air-Filters and Washers—Heating and Ventilation of Schools, Hospitals, Churches, Office Buildings, etc.

STEAM AND HOT-WATER FITTING . . *By W. G. Snow* Page 225

Steam Boilers and Connections—Boiler Setting and Foundations—Grate Surface and Heating Capacity—Coal Consumption—Non-Conductive Coverings—Steam Radiators and Coils—Steam Piping—Dry-Return and Wet-Return Systems—Overhead-Feed System—One-Pipe and Two-Pipe Systems—Steam Pressures and Temperatures—Expansion—Radiator Connections—Computing Radiation—Ducts, Flues, and Registers—Exhaust Steam Heating—Modified Systems of Steam Heating (Thermograde, Vapor, Mercury Seal Vacuum)—Standard Pipe—Hangers—Sleeves—Valves—Tools—Hot-Water Heaters—Single-Main System—Two-Pipe Up-Feed System—Overhead-Feed System—Open-Tank *vs.* Pressure System

ELECTRIC WIRING . . . . . *By C. E. Knox* Page 291

Wires Run in Conduit; in Moulding—Knob and Tube Wiring—Wires Exposed on Insulators—Armored Cable—Fibrous Tubing—Two-Wire and Three-Wire Systems—Sizes of Conductors—Formulæ—Planning an Installation—Testing—A. C. Circuits—Wiring an Office Building—Overhead Linework—Lightning Arresters

REVIEW QUESTIONS . . . . . Page 379

INDEX . . . . . Page 387

* For page numbers, see foot of pages.

† For professional standing of authors, see list of Authors and Collaborators at front of volume.



SECTIONAL VIEW OF HOUSE SHOWING THE THREE METHODS OF STEAM AND HOT-WATER HEATING

A. Indirect Radiation; *B*. Semi-Direct Radiation; *C*. Direct Radiation
Pierce, Butler & Pierce Mfg. Co., Syracuse, N. Y.

HEATING AND VENTILATION

PART I

SYSTEMS OF WARMING

Any system of warming must include, *first*, the combustion of fuel, which may take place in a fireplace, stove, or furnace, or a steam, or hot-water boiler; *second*, a system of transmission, by means of which the heat may be carried, with as little loss as possible, to the place where it is to be used for warming; and *third*, a system of diffusion, which will convey the heat to the air in a room, and to its walls, floors, etc., in the most economical way.

Stoves. The simplest and cheapest form of heating is the stove. The heat is diffused by radiation and convection directly to the objects and air in the room, and no special system of transmission is required. The stove is used largely in the country, and is especially adapted to the warming of small dwelling-houses and isolated rooms.

Furnaces. Next in cost of installation and in simplicity of operation, is the hot-air furnace. In this method, the air is drawn over heated surfaces and then transmitted through pipes, while at a high temperature, to the rooms where heat is required. Furnaces are used largely for warming dwelling-houses, also churches, halls, and schoolhouses of small size. They are more costly than stoves, but have certain advantages over that form of heating. They require less care, as several rooms may be warmed from a single furnace; and, being placed in the basement, more space is available in the rooms above, and the dirt and litter connected with the care of a stove are largely done away with. They require less care, as only one fire is necessary to warm all the rooms in a house of ordinary size. One great advantage in the furnace method of warming comes from the constant supply of fresh air which is required to bring the heat into the rooms. While this is greatly to be desired from a sanitary standpoint, it calls for the consumption of a larger amount of fuel than would otherwise be necessary. This is true because heat is required to warm the fresh air from out of doors up to the temperature of the

rooms, in addition to replacing the heat lost by leakage and conduction through walls and windows.

A more even temperature may be maintained with a furnace than by the use of stoves, owing to the greater depth and size of the fire, which allows it to be more easily controlled.

When a building is placed in an exposed location, there is often difficulty in warming rooms on the north and west sides, or on that side toward the prevailing winds. This may be overcome to some extent by a proper location of the furnace and by the use of extra large pipes for conveying the hot air to those rooms requiring special attention.

Direct Steam. Direct steam, so called, is widely used in all classes of buildings, both by itself and in combination with other systems. The first cost of installation is greater than for a furnace; but the amount of fuel required is less, as no outside air supply is necessary. If used for warming hospitals, schoolhouses, or other buildings where a generous supply of fresh air is desired, this method must be supplemented by some form of ventilating system.

One of the principal advantages of direct steam is the ability to heat all rooms alike, regardless of their location or of the action of winds.

When compared with hot-water heating, it has still another desirable feature—which is its freedom from damage by the freezing of water in the radiators when closed, which is likely to happen in unused rooms during very cold weather in the case of the former system.

On the other hand, the sizes of the radiators must be proportioned for warming the rooms in the coldest weather, and unfortunately there is no satisfactory method of regulating the amount of heat in mild weather, except by shutting off or turning on steam in the radiators at more or less frequent intervals as may be required, unless one of the expensive systems of automatic control is employed. In large rooms, a certain amount of regulation can be secured by dividing the radiation into two or more parts, so that different combinations may be used under varying conditions of outside temperature. If two radiators are used, their surface should be proportioned, when convenient, in the ratio of 1 to 2, in which case one-third, two-thirds, or the whole power of the radiation can be used as desired.

Indirect Steam. This system of heating combines some of the advantages of both the furnace and direct steam, but is more costly to install than either of these. The amount of fuel required is about the same as for furnace heating, because in each case the cool fresh air must be warmed up to the temperature of the room, before it can become a medium for conveying heat to offset that lost by leakage and conduction through walls and windows.

A system for indirect steam may be so designed that it will supply a greater quantity of fresh air than the ordinary form of furnace, in which case the cost of fuel will of course be increased in proportion to the volume of air supplied. Instead of placing the radiators in the rooms, a special form of heater is supported near the basement ceiling and encased in either galvanized iron or brick. A cold-air supply duct is connected with the space below the heater, and warm air pipes are taken from the top and connected with registers in the rooms to be heated the same as in the case of furnace heating.

A separate stack or heater may be provided for each register if the rooms are large; but, if small and so located that they may be reached by short runs of horizontal pipe, a single heater may serve for two or more rooms.

The advantage of indirect steam over furnace heating comes from the fact that the stacks may be placed at or near the bases of the flues leading to the different rooms, thus doing away with long, horizontal runs of pipe, and counteracting to a considerable extent the effect of wind pressure upon exposed rooms. Indirect and direct heating are often combined to advantage by using the former for the more important rooms, where ventilation is desired, and the latter for rooms more remote or where heat only is required.

Another advantage is the large ratio between the radiating surface and grate-area, as compared with a furnace; this results in a large volume of air being warmed to a moderate temperature instead of a smaller quantity being heated to a much higher temperature, thus giving a more agreeable quality to the air and rendering it less dry.

Indirect steam is adapted to all the buildings mentioned in connection with furnace heating, and may be used to much better advantage in those of large size. This applies especially to cases where more than one furnace is necessary; for, with steam heat, a single boiler, or a battery of boilers, may be made to supply heat for a build-

ing of any size, or for a group of several buildings, if desired, and is much easier to care for than several furnaces widely scattered.

Direct-Indirect Radiators. These radiators are placed in the room the same as the ordinary direct type. The construction is such that when the sections are in place, small flues are formed between them; and air, being admitted through an opening in the outside wall, passes upward through them and becomes heated before entering the room. A switch damper is placed in the casing at the base of the radiator, so that air may be taken from the room itself instead of from out of doors, if so desired. Radiators of this kind are not used to any great extent, as there is likely to be more or less leakage of cold air into the room around the base. If ventilation is required, it is better to use the regular form of indirect heater with flue and register, if possible. It is sometimes desirable to partially ventilate an isolated room where it would be impossible to run a flue, and in cases of this kind the direct-indirect form is often useful.

Direct Hot Water. Hot water is especially adapted to the warming of dwellings and greenhouses, owing to the ease with which the temperature can be regulated. When steam is used, the radiators are always at practically the same temperature, while with hot water the temperature can be varied at will. A system for hot-water heating costs more to install than one for steam; as the radiators must be larger and the pipes more carefully run. On the other hand, the cost of operating is somewhat less, because the water need be carried only at a temperature sufficiently high to warm the rooms properly in mild weather, while with steam the building is likely to become overheated, and more or less heat wasted through open doors and windows.

A comparison of the relative costs of installing and operating hot-air, steam, and hot-water systems, is given in Table I.

TABLE I

Relative Cost of Heating Systems

	Hot Air	Steam	Hot Water
Relative cost of apparatus	9	13	15
Relative cost, adding repairs and fuel for five years	29½	29⅞	27
Relative cost, adding repairs and fuel for fifteen years	81	63	52½

One disadvantage in the use of hot water is the danger from freezing when radiators are shut off in unused rooms. This makes it necessary in very cold weather to have all parts of the system turned on sufficiently to produce a circulation, even if very slow. This is sometimes accomplished by drilling a very small hole (about $\frac{1}{8}$ inch) in the valve-seat, to that when closed there will still be a very slow circulation through the radiator, thus preventing the temperature of the water from reaching the freezing point.

Indirect Hot Water. This is used under the same conditions as indirect steam, but more especially in the case of dwellings and hospitals. When applied to other and larger buildings, it is customary to force the water through the mains by means of a pump. Larger heating stacks and supply pipes are required than for steam; but the arrangement and size of air-flues and registers are practically the same, although they are sometimes made slightly larger in special cases.

Exhaust Steam. Exhaust steam is used for heating in connection with power plants, as in shops and factories, or in office buildings which have their own lighting plants. There are two methods of using exhaust steam for heating purposes. One is to carry a back pressure of 2 to 5 pounds on the engines, depending upon the length and size of the pipe mains; and the other is to use some form of *vacuum system* attached to the returns or air-valves, which tends to reduce the back pressure rather than to increase it.

Where the first method is used and a back pressure carried, either the boiler pressure or the cut-off of the engines must be increased, to keep the mean effective pressure the same and not reduce the horsepower delivered. In general it is more economical to utilize the exhaust steam for heating. There are instances, however, where the relation between the quantities of steam required for heating and for power are such—especially if the engines are run condensing—that it is better to throw the exhaust away and heat with live steam. Where the vacuum method is used, these difficulties are avoided; and for this reason that method is coming into quite common use. If the condensation from the exhaust steam is returned to the boilers, the oil must first be removed; this is usually accomplished by passing the steam through some form of grease extractor as it leaves the engine. The water of condensation is often passed through a separating tank in addition to this, before it is delivered to the return

pumps. It is better, however, to remove a portion of the oil before the steam enters the heating system; otherwise a coating will be formed upon the inner surfaces of the radiators, which will reduce their efficiency to some extent.

Forced Blast. This method of heating, in different forms, is used for the warming of factories, schools, churches, theaters, halls—in fact, any large building where good ventilation is desired. The air for warming is drawn or forced through a heater of special design, and discharged by a fan or blower into ducts which lead to registers placed in the rooms to be warmed. The heater is usually made up in sections, so that steam may be admitted to or shut off from any section independently of the others, and the temperature of the air regulated in this manner. Sometimes a *by-pass damper* is attached, so that part of the air will pass through the heater and part around or over it; in this way the proportions of cold and heated air may be so adjusted as to give the desired temperature to the air entering the rooms. These forms of regulation are common where a blower is used for warming a single room, as in the case of a church or hall; but where several rooms are warmed, as in a schoolhouse. it is customary to use the main or primary heater at the blower for warming the air to a given temperature (somewhat below that which is actually required), and to supplement this by placing secondary coils or heaters at the bottoms of the flues leading to the different rooms. By means of this arrangement, the temperature of each room can be regulated independently of the others. The so-called *double-duct* system is sometimes employed. In this case, two ducts are carried to each register, one supplying hot air and the other cold or tempered air; and a damper for mixing these in the right proportions is placed in the flue, below the register.

Electric Heating. Unless electricity can be produced at a very low cost, it is not practicable for heating residences or large buildings. The electric heater, however, has quite a wide field of application in heating small offices, bathrooms, electric cars, etc. It is a convenient method of warming isolated rooms on cold mornings, in late spring and early fall, when the regular heating apparatus of the building is not in operation. It has the advantage of being instantly available, and the amount of heat can be regulated at will. Electric heaters are clean, do not vitiate the air, and are easily moved from place to place.

PRINCIPLES OF VENTILATION

Closely connected with the subject of heating is the problem of maintaining air of a certain standard of purity in the various buildings occupied.

The introduction of pure air can be done properly only in connection with some system of heating; and no system of heating is complete without a supply of pure air, depending in amount upon the kind of building and the purpose for which it is used.

Composition of the Atmosphere. Atmospheric air is not a simple substance but a mechanical mixture. Oxygen and nitrogen, the principal constituents, are present in very nearly the proportion of one part of oxygen to four parts of nitrogen by weight. Carbonic acid gas, the product of all combustion, exists in the proportion of 3 to 5 parts in 10,000 in the open country. Water in the form of vapor, varies greatly with the temperature and with the exposure of the air to open bodies of water. In addition to the above, there are generally present, in variable but exceedingly small quantities, ammonia, sulphuretted hydrogen, sulphuric, sulphurous, nitric, and nitrous acids, floating organic and inorganic matter, and local impurities. Air also contains ozone, which is a peculiarly active form of oxygen; and lately another constituent called *argon* has been discovered.

Oxygen is the most important element of the air, so far as both heating and ventilation are concerned. It is the active element in the chemical process of combustion and also in the somewhat similar process which takes place in the respiration of human beings. Taken into the lungs, it acts upon the excess of carbon in the blood, and possibly upon other ingredients, forming chemical compounds which are thrown off in the act of respiration or breathing.

Nitrogen. The principal bulk of the atmosphere is nitrogen, which exists uniformly diffused with oxygen and carbonic acid gas. This element is practically inert in all processes of combustion or respiration. It is not affected in composition, either by passing through a furnace during combustion or through the lungs in the process of respiration. Its action is to render the oxygen less active, and to absorb some part of the heat produced by the process of oxidation.

Carbonic acid gas is of itself only a neutral constituent of the atmosphere, like nitrogen; and—contrary to the general impression—its presence in moderately large quantities (if uncombined with other

substances) is neither disagreeable nor especially harmful. Its presence, however, in air provided for respiration, decreases the readiness with which the carbon of the blood unites with the oxygen of the air; and therefore, when present in sufficient quantity, it may cause indirectly, not only serious, but fatal results. The real harm of a vitiated atmosphere, however, is caused by the other constituent gases and by the minute organisms which are produced in the process of respiration. It is known that these other impurities exist in fixed proportion to the amount of carbonic acid present in an atmosphere vitiated by respiration. Therefore, as the relative proportion of carbonic acid can easily be determined by experiment, the fixing of a standard limit of the amount in which it may be allowed, also limits the amounts of other impurities which are found in combination with it.

When carbonic acid is present in excess of 10 parts in 10,000 parts of air, a feeling of weariness and stuffiness, generally accompanied by a headache, will be experienced; while with even 8 parts in 10,000 parts a room would be considered close. For general considerations of ventilation, the limit should be placed at 6 to 7 parts in 10,000, thus allowing an increase of 2 to 3 parts over that present in outdoor air, which may be considered to contain four parts in 10,000 under ordinary conditions.

Analysis of Air. An accurate qualitative and quantitative analysis of air samples can be made only by an experienced chemist. There are, however, several approximate methods for determining the amount of carbonic acid present, which are sufficiently exact for practical purposes. Among these the following is one of the simplest:

The necessary apparatus consists of six clean, dry, and tightly corked bottles, containing respectively 100, 200, 250, 300, 350, and 400 cubic centimeters, a glass tube containing exactly 15 cubic centimeters to a given mark, and a bottle of perfectly clear, fresh limewater. The bottles should be filled with the air to be examined by means of a hand-ball syringe. Add to the smallest bottle 15 cubic centimeters of the limewater, put in the cork, and shake well. If the limewater has a milky appearance, the amount of carbonic acid will be at least 16 parts in 10,000. If the contents of the bottle remain clear, treat the bottle of 200 cubic centimeters in the same manner; a milky appearance or turbidity in this would indicate 12 parts in 10,000. In a similar manner, turbidity in the 250 cubic centimeter bottle indicates

10 parts in 10,000; in the 300, 8 parts; in the 350, 7 parts; and in the 400, less than 6 parts. The ability to conduct more accurate analyses can be attained only by special study and a knowledge of chemical properties and of methods of investigation.

Another method similar to the above, makes use of a glass cylinder containing a given quantity of limewater and provided with a piston. A sample of the air to be tested is drawn into the cylinder by an upward movement of the piston. The cylinder is then thoroughly shaken, and if the limewater shows a milky appearance, it indicates a certain proportion of carbonic acid in the air. If the limewater remains clear, the air is forced out, and another cylinder full drawn in, the operation being repeated until the limewater becomes milky. The size of the cylinder and the quantity of limewater are so proportioned that a change in color at the first, second, third, etc., cylinder full of air indicates different proportions of carbonic acid. This test is really the same in principle as the one previously described; but the apparatus used is in more convenient form.

Air Required for Ventilation. The amount of air required to maintain any given standard of purity can very easily be determined, provided we know the amount of carbonic acid given off in the process of respiration. It has been found by experiment that the average production of carbonic acid by an adult at rest is about .6 cubic foot per hour. If we assume the proportion of this gas as 4 parts in 10,000 in the external air, and are to allow 6 parts in 10,000 in an occupied room, the gain will be 2 parts in 10,000; or, in other words, there will be $\frac{2}{10{,}000} = .0002$ cubic foot of carbonic acid mixed with each cubic foot of fresh air entering the room. Therefore, if one person gives off .6 cubic foot of carbonic acid per hour, it will require $.6 \div .0002 = 3{,}000$ cubic feet of air per hour per person to keep the air in the room at the standard of purity assumed—that is, 6 parts of carbonic acid in 10,000 of air.

Table II has been computed in this manner, and shows the amount of air which must be introduced for each person in order to maintain various standards of purity.

While this table gives the theoretical quantities of air required for different standards of purity, and may be used as a guide, it will be better in actual practice to use quantities which experience has shown

to give good results in different types of buildings. In auditoriums where the cubic space per individual is large, and in which the atmosphere is thoroughly fresh before the rooms are occupied, and the occupancy is of only two or three hours' duration, the air-supply may be reduced somewhat from the figures given below.

TABLE II

Quantity of Air Required per Person

Standard Parts of Carbonic Acid in 10,000 of Air in Room	Cubic Feet of Air Required per Person	
	Per Minute	Per Hour
5	100	6,000
6	50	3,000
7	33	2,000
8	25	1,500
9	20	1,200
10	16	1,000

Table III represents good modern practice and may be used with satisfactory results:

TABLE III

Air Required for Ventilation of Various Classes of Buildings

Air-Supply per Occupant for	Cubic Feet per Minute	Cubic Feet per Hour
Hospitals	80 to 100	4, 800 to 6, 000
High Schools	50	3, 000
Grammar Schools	40	2, 400
Theaters and Assembly Halls	25	1, 500
Churches	20	1, 200

When possible, the air-supply to any given room should be based upon the number of occupants. It sometimes happens, however, that this information is not available, or the character of the room is such that the number of persons occupying it may vary, as in the case of public waiting rooms, toilet rooms, etc. In instances of this kind, the required air-volume may be based upon the number of changes per hour. In using this method, various considerations must be taken into account, such as the use of the room and its condition as to crowding, character of occupants, etc. In general, the following will be found satisfactory for average conditions:

TABLE IV

Number of Changes of Air Required in Various Rooms

Use of Room	Changes of Air per Hour
Public Waiting Room	4 to 5
Public Toilets	5 " 6
Coat and Locker Rooms	4 " 5
Museums	3 " 4
Offices, Public	4 " 5
Offices, Private	3 " 4
Public Dining Rooms	4 " 5
Living Rooms	3 " 4
Libraries, Public	4 " 5
Libraries, Private	3 " 4

Force for Moving Air. Air is moved for ventilating purposes in two ways: (1) by expansion due to heating; (2) by mechanical means. The effect of heat on the air is to increase its volume and therefore lessen its density or weight, so that it tends to rise and is replaced by the colder air below. The available force for moving air obtained in this way is very small, and is quite likely to be overcome by wind or external causes. It will be found in general that the heat used for producing velocity in this manner, when transformed into work in the steam engine, is greatly in excess of that required to produce the same effect by the use of a fan.



Fig. 1. Common Form of Anemometer, for Measuring Velocity of Air-Currents.

Ventilation by mechanical means is performed either by pressure or by suction. The former is used for delivering fresh air into a building, and the latter for removing the foul air from it. By both processes the air is moved without change in temperature, and the force for moving must be sufficient to overcome the effects of wind or changes in outside temperature. Some form of fan is used for this purpose.

Measurements of Velocity. The velocity of air in ventilating ducts and flues is measured directly by an instrument called an anemometer. A common form of this instrument is shown in Fig. 1. It consists of a series of flat vanes attached to an axis, and a series of dials.

The revolution of the axis causes motion of the hands in proportion to the velocity of the air, and the result can be read directly from the dials for any given period.

For approximate results the anemometer may be slowly moved across the opening in either vertical or horizontal parallel lines, so that the readings will be made up of velocities taken from all parts of the opening. For more accurate work, the opening should be divided into a number of squares by means of small twine, and readings taken at the center of each. The mean of these readings will give the average velocity of the air through the entire opening.

AIR DISTRIBUTION

The location of the air inlet to a room depends upon the size of the room and the purpose for which it is used. In the case of living rooms in dwelling-houses, the registers are placed either in the floor or in the wall near the floor; this brings the warm air in at the coldest part of the room and gives an opportunity for warming or drying the feet if desired. In the case of schoolrooms, where large volumes of warm air at moderate temperatures are required, it is best to discharge it through openings in the wall at a height of 7 or 8 feet from the floor; this gives a more even distribution, as the warmer air tends to rise and hence spreads uniformly under the ceiling; it then gradually displaces other air, and the room becomes filled with pure air without sensible currents or drafts. The cooler air sinks to the bottom of the room, and can be taken off through ventilating registers placed near the floor. The relative positions of the inlet and outlet are often governed to some extent by the building construction; but, if possible, they should both be located in the same side of the room. Figs. 2, 3, and 4 show common arrangements.

The vent outlet should always, if possible, be placed in an inside wall; otherwise it will become chilled and the air-flow through it will become sluggish. In theaters and churches which are closely packed, the air should enter at or near the floor, in finely-divided streams; and the discharge ventilation should be through openings in the ceiling. The reason for this is the large amount of animal heat given off from the bodies of the audience; this causes the air to become still further heated after entering the room, and the tendency is to rise continuously

from floor to ceiling, thus carrying away all impurities from respiration as fast as they are given off.

All audience halls in which the occupants are closely seated should be treated in the same manner, when possible. This, however, cannot always be done, as the seats are often made removable so that the



Fig. 2. Fig. 3. Fig. 4.

Diagrams Showing Relative Positions of Air Inlets and Outlets as Commonly Arranged.

floor can be used for other purposes. In cases of this kind, part of the air may be introduced through floor registers placed along the outer aisles, and the remainder by means of wall inlets the same as for schoolrooms. The discharge ventilation should be partly through registers near the floor, supplemented by ample ceiling vents for use when the hall is crowded or the outside temperature high.

The matter of air-velocities, size of flues, etc., will be taken up under the head of "Indirect Heating."

HEAT LOSS FROM BUILDINGS

A *British Thermal Unit*, or B. T. U., has been defined as the amount of heat required to raise the temperature of one pound of water one degree F. This measure of heat enters into many of the calculations involved in the solving of problems in heating and ventilation, and one should familiarize himself with the exact meaning of the term.

Causes of Heat Loss. The heat loss from a building is due to the following causes: (1) radiation and conduction of heat through walls and windows; (2) leakage of warm air around doors and windows and through the walls themselves; and (3) heat required to warm the air for ventilation.

Loss through Walls and Windows. The loss of heat through the walls of a building depends upon the material used in construction

TABLE V

Heat Losses in B. T. U. per Square Foot of Surface per Hour—Southern Exposure

Material	Difference between Inside and Outside Temperatures									
	10°	20°	30°	40°	50°	60°	70°	80°	90°	100°
8-in. Brick Wall	5	9	13	18	22	27	31	36	40	45
12-in. Brick Wall	4	7	10	13	16	20	23	26	30	33
16-in. Brick Wall	3	5	8	10	13	16	19	22	24	27
20-in. Brick Wall	2.8	4.5	7	9	11	14	16	18	20	23
24-in. Brick Wall	2.5	4	6	8	10	12	14	16	18	20
28-in. Brick Wall	2	3.5	5	7	9	11	13	14	16	18
32-in. Brick Wall	1.5	3	4.5	6	8	10	11	13	15	16
Single Window	12	24	36	49	60	73	85	93	110	122
Double Window	8	16	24	32	40	48	56	62	70	78
Single Skylight	11	21	31	42	52	63	73	84	94	104
Double Skylight	7	14	20	28	35	42	48	56	62	70
1-in. Wooden Door	4	8	12	16	20	24	28	32	36	40
2-in. Wooden Door	3	5	8	11	14	17	20	23	25	28
2-in. Solid Plaster Partition	6	12	18	24	30	36	42	48	54	60
3-in. Solid Plaster Partition	5	10	15	20	25	30	35	40	45	50
Concrete Floor on Brick Arch	2	4	6.5	9	11	13	15	18	20	22
Wood Floor on Brick Arch	1.5	3	4.5	6	7	9	10	12	13	15
Double Wood Floor	1	2	3	4	5	6	7	8	9	10
Walls of Ordinary Wooden Dwellings	3	5	8	10	13	16	19	22	24	27

For *solid stone walls*, multiply the figures for brick of the same thickness by 1.7. Where rooms have a *cold attic above or cellar beneath*, multiply the heat loss through walls and windows by 1.1.

Correction for Leakage. The figures given in the above table apply only to the most thorough construction. For the average well-built house, the results should be increased about 10 per cent; for fairly good construction, 20 per cent; and for poor construction, 30 per cent.

Table V applies only to a southern exposure; for other exposures multiply the heat loss given in Table V by the factors given in Table VI.

of the wall, the thickness, the number of layers, and the difference between the inside and outside temperatures. The exact amount of heat lost in this way is very difficult to determine theoretically, hence we depend principally on the results of experiments.

Loss by Air-Leakage. The leakage of air from a room varies from one to two or more changes of the entire contents per hour, depending upon the construction, opening of doors, etc. It is common practice to allow for one change per hour in well-constructed buildings where two walls of the room have an outside exposure. As the amount of leakage depends upon the extent of exposed wall and window surface, the simplest way of providing for this is to increase

TABLE VI
Factors for Calculating Heat Loss for Other than Southern Exposures

Exposure	Factor
N.	1.32
E.	1.12
S.	1.0
W.	1.20
N. E.	1.22
N. W.	1.26
S. E.	1.06
S. W.	1.10
N., E., S., and W., or total exposure	1.16

the total loss through walls and windows by a factor depending upon the tightness of the building construction. Authorities differ considerably in the factors given for heat losses, and there are various methods for computing the same. The figures given in Table V have been used extensively in actual practice, and have been found to give good results when used with judgment. The table gives the heat losses through different thicknesses of walls, doors, windows, etc., in B. T. U., per square foot of surface per hour, for varying differences in inside and outside temperatures.

In computing the heat loss through walls, only those exposed to the outside air are considered.

In order to make the use of the table clear, we shall give a number of examples illustrating its use:

Example 1. Assuming an inside temperature of 70°, what will be the heat loss from a room having an exposed wall surface of 200 square feet and a glass surface of 50 square feet, when the outside temperature is zero? The wall is of brick, 16 inches in thickness, and has a southern exposure; the windows are single; and the construction is of the best, so that no account need be taken of leakage

We find from Table V, that the factor for a 16-inch brick wall with a difference in temperature of 70° is 19, and that for glass (single window) under the same condition is 85; therefore,

Loss through walls = 200 × 19 = 3,800
Loss through windows = 50 × 85 = 4,250

Total loss per hour = 8,050 B. T. U.

Example 2. A room 15 ft. square and 10 ft. high has two exposed walls, one toward the north, and the other toward the west. There are 4 windows, each 3 feet by 6 feet in size. The two in the north wall are double, while the

other two are single. The walls are of brick, 20 inches in thickness. With an inside temperature of 70°, what will be the heat loss per hour when it is 10° below zero?

Total exposed surface = 15 × 10 × 2 = 300
Glass surface = 3 × 6 × 4 = 72

Net wall surface = 228

Difference between inside and outside temperature 80°.
Factor for 20-inch brick wall is 18.
Factor for single window is 93.
Factor for double window is 62.
The heat losses are as follows:

Wall, 228 × 18 = 4,104
Single windows, 36 × 93 = 3,348
Double windows, 36 × 62 = 2,232

9,684 B. T. U.

As one side is toward the north, and the other toward the west, the actual exposure is N. W. Looking in Table VI, we find the correction factor for this exposure to be 1.26; therefore the total heat loss is

9,684 × 1.26 = 12,201.84 B. T. U.

Example 3. A dwelling-house of fair wooden construction measures 160 ft. around the outside; it has 2 stories, each 8 ft. in height; the windows are single, and the glass surface amounts to one-fifth the total exposure; the attic and cellar are unwarmed. If 8,000 B. T. U. are utilized from each pound of coal burned in the furnace, how many pounds will be required per hour to maintain a temperature of 70° when it is 20° above zero outside?

Total exposure = 160 × 16 = 2,560
Glass surface = 2,560 ÷ 5 = 512

Net wall = 2,048
Temperature difference = 70 − 20 = 50°
Wall 2,048 × 13 = 26,624
Glass 512 × 60 = 30,720

57,344 B. T. U.

As the building is exposed on all sides, the factor for exposure will be the average of those for N., E., S., and W., or

(1.32 + 1.12 + 1.0 + 1.20) ÷ 4 = 1 16

The house has a cold cellar and attic, so we must increase the heat loss



EXCELSIOR PATTERN RADIATOR USED IN THE INDIRECT METHOD OF WARMING
American Radiator Company



METHOD OF INDIRECT WARMING AND VENTILATION, SHOWING ROTARY CIRCULATION OF AIR
American Radiator Company

10 per cent for each of the first two conditions, and 20 per cent for the last. Making these corrections we have:

$$57{,}344 \times 1.16 \times 1.10 \times 1.10 \times 1.20 = 96{,}338 \text{ B. T. U.}$$

If one pound of coal furnishes 8,000 B. T. U., then $96{,}338 \div 8{,}000 =$ 12 pounds of coal per hour required to warm the building to 70° under the conditions stated.

Approximate Method. For dwelling-houses of the average construction, the following simple method for calculating the heat loss may be used. Multiply the total exposed surface by 45, which will give the heat loss in B. T. U. per hour for an inside temperature of 70° in zero weather.

This factor is obtained in the following manner: Assume the glass surface to be one-sixth the total exposure, which is an average proportion. Then each square foot of exposed surface consists one-sixth of glass and five-sixths of wall, and the heat loss for 70° difference in temperature would be as follows:

$$\text{Wall } \frac{5}{6} \times 19 = 15.8$$

$$\text{Glass } \frac{1}{6} \times 85 = \underline{14.1}$$

$$29.9$$

Increasing this 20 per cent for leakage, 16 per cent for exposure, and 10 per cent for cold ceilings, we have:

$$29.9 \times 1.20 \times 1.16 \times 1.10 = 45.$$

The loss through floors is considered as being offset by including the kitchen walls of a dwelling-house, which are warmed by the range, and which would not otherwise be included if computing the size of a furnace or boiler for heating.

If the heat loss is required for outside temperatures other than zero, multiply by 50 for 10 degrees below, and by 40 for 10 degrees above zero.

This method is convenient for approximations in the case of dwelling-houses; but the more exact method should be used for other types of buildings, and in all cases for computing the heating surface for separate rooms. *When calculating the heat loss from isolated rooms, the cold inside walls as well as the outside must be considered.*

The loss through a wall next to a cold attic or other unwarmed space may in general be taken as about two-thirds that of an outside wall.

Heat Loss by Ventilation. One B. T. U. will raise the temperature of 1 cubic foot of air 55 degrees at average temperatures and pressures, or will raise 55 cubic feet 1 degree, so that the heat required for the ventilation of any room can be found by the following formula:

$$\frac{\text{Cu. ft. of air per hour} \times \text{Number of degrees rise}}{55} = \text{B. T. U. required.}$$

To compute the heat loss for any given room which is to be ventilated, first find the loss through walls and windows, and correct for exposure and leakage; then compute the amount required for ventilation as above, and take the sum of the two. An inside temperature of 70° is always assumed unless otherwise stated.

Examples. What quantity of heat will be required to warm 100,000 cubic feet of air to 70° for ventilating purposes when the outside temperature is 10 below zero?

$$100{,}000 \times 80 \div 55 = 145{,}454 \text{ B. T. U.}$$

How many B. T. U. will be required per hour for the ventilation of a church seating 500 people, in zero weather?

Referring to Table III, we find that the total air required per hour is $1{,}200 \times 500 = 600{,}000$ cu. ft.; therefore $600{,}000 \times 70 \div 55 = 763{,}636$ B. T. U.

The factor $\frac{\text{Rise in Temperature}}{55}$ is approximately 1.1 for 60°, 1.3 for 70°, and 1.5 for 80°. Assuming a temperature of 70° for the entering air, we may multiply the air-volume supplied for ventilation by 1.1 for an outside temperature of 10° above 0, by 1.3 for zero, and by 1.5 for 10° below zero—which covers the conditions most commonly met with in practice.

EXAMPLES FOR PRACTICE

1. A room in a grammar school 28 ft. by 32 ft. and 12 feet high is to accommodate 50 pupils. The walls are of brick 16 inches in thickness; and there are 6 single windows in the room, each 3 ft. by 6 ft.; there are warm rooms above and below; the exposure is S. E. How many B. T. U. will be required per hour for warming the room, and how many for ventilation, in zero weather, assuming the building to be of average construction?

ANS. 24,261 + for warming; 152,727 + for ventilation.

2. A stone church seating 400 people has walls 20 inches in thickness. It has a wall exposure of 5,000 square feet, a glass expos-

ure (single windows) of 600 square feet, and a roof exposure of 7,000 square feet; the roof is of 2-inch pine plank, and the factor for heat loss may be taken the same as for a 2-inch wooden door. The floor is of wood on brick arches, and has an area of 4,000 square feet. The building is exposed on all sides, and is of first-class construction. What will be the heat required per hour for both warming and ventilation when the outside temperature is 20° above zero?

ANS. 296,380 for warming; 436,363 + for ventilation.

3. A dwelling-house of average wooden construction measures 200 feet around the outside, and has 3 stories, each 9 feet high. Compute the heat loss by the approximate method when the temperature is 10° below zero.

ANS. 270,000 B. T. U. per hour.

FURNACE HEATING

In construction, a furnace is a large stove with a combustion chamber of ample size over the fire, the whole being inclosed in a casing of sheet iron or brick. The bottom of the casing is provided with a cold-air inlet, and at the top are pipes which connect with registers placed in the various rooms to be heated. Cold, fresh air is brought from out of doors through a pipe or duct called the *cold-air box;* this air enters the space between the casing and the furnace near the bottom, and, in passing over the hot surfaces of the fire-pot and combustion chamber, becomes heated. It then rises through the warm-air pipes at the top of the casing, and is discharged through the registers into the rooms above.

As the warm air is taken from the top of the furnace, cold air flows in through the cold-air box to take its place. The air for heating the rooms does not enter the combustion chamber.

Fig. 5 shows the general arrangement of a furnace with its connecting pipes. The cold-air inlet is seen at the bottom, and the hot-air pipes at the top; these are all provided with dampers for shutting off or regulating the amount of air flowing through them. The feed or fire door is shown at the front, and the ash door beneath it; a *water-pan* is placed inside the casing, and furnishes moisture to the warm air before passing into the rooms; water is either poured into the pan through an opening in the front, provided for this purpose, or is supplied automatically through a pipe.

The fire is regulated by means of a draft slide in the ash door, and a cold-air or regulating damper placed in the smoke-pipe. Clean-out doors are placed at different points in the casing for the removal of



Fig. 5. General Arrangement of Details of a Hot-Air Furnace, with Connecting Pipes.

ashes and soot. Furnaces are made either of cast iron, or of wrought-iron plates riveted together and provided with brick-lined firepots.

Types of Furnaces. Furnaces may be divided into two general

types known as *direct-draft* and *indirect-draft*. Fig. 6 shows a common form of *direct-draft* furnace with a brick setting; the better class have a radiator, generally placed at the top, through which the gases pass before reaching the smoke-pipe. They have but one damper, usually combined with a cold-air check. Many of the cheaper direct-



Fig. 6. A Common Type of Direct-Draft Furnace in Brick Setting. Cast-Iron Radiator at Top.

draft furnaces have no radiator at all, the gases passing directly into the smoke-pipe and carrying away much heat that should be utilized.

The furnace shown in Fig. 6 is made of cast iron and has a large radiator at the top; the smoke connection is shown at the rear.

Fig. 7 represents another form of direct-draft furnace. In this case the radiator is made of sheet-steel plates riveted together, and the outer casing is of heavy galvanized iron instead of brick.

In the ordinary *indirect-draft* type of furnace (see Fig. 8), the gases pass downward through flues to a radiator located near the base,

thence upward through another flue to the smoke-pipe. In addition to the damper in the smoke-pipe, a direct-draft damper is required to give direct connection with the funnel when coal is first put on, to facilitate the escape of gas to the chimney. When the chimney draft



Fig. 7. Direct-Draft Furnace with Galvanized-Iron Casing. Radiator (at top) Made of Riveted Steel Plates.

is weak, trouble from gas is more likely to be experienced with furnaces of this type than with those having a direct draft.

Grates. No part of a furnace is of more importance than the grates. The plain grate rotating about a center pin was for a long time the one most commonly used. These grates were usually provided with a clinker door for removing any refuse too large to pass between the grate bars. The action of such grates tends to leave a

cone of ashes in the center of the fire causing it to burn more freely around the edges. A better form of grate is the revolving triangular pattern, which is now used in many of the leading furnaces. It consists of a series of triangular bars having teeth. The bars are connected by gears, and are turned by means of a detachable lever. If



Fig. 8. Indirect-Draft Type of Furnace. Gases Pass Downward to Radiator at Bottom, Thence Upward to Smoke-Pipe.

properly used, this grate will cut a slice of ashes and clinkers from under the entire fire with little, if any loss of unconsumed coal.

The Firepot. Firepots are generally made of cast iron or of steel plate lined with firebrick. The depth ranges from about 12 to 18 inches. In cast-iron furnaces of the better class, the firepot is made very heavy, to insure durability and to render it less likely to become red-hot. The firepot is sometimes made in two pieces, to reduce the

liability to cracking. The heating surface is sometimes increased by corrugations, pins, or ribs.

A firebrick lining is necessary in a wrought-iron or steel furnace to protect the thin shell from the intense heat of the fire. Since brick-lined firepots are much less effective than cast-iron in transmitting heat, such furnaces depend to a great extent for their efficiency on the heating surface in the dome and radiator; and this, as a rule, is much greater than in those of cast iron.

Cast-iron furnaces have the advantage when coal is first put on (and the drop flues and radiator are cut out by the direct damper) of still giving off heat from the firepot, while in the case of brick linings very little heat is given off in this way, and the rooms are likely to become somewhat cooled before the fresh coal becomes thoroughly ignited.

Combustion Chamber. The body of the furnace above the firepot, commonly called the *dome* or *feed section*, provides a combustion chamber. This chamber should be of sufficient size to permit the gases to become thoroughly mixed with the air passing up through the fire or entering through openings provided for the purpose in the feed door. In a well-designed furnace, this space should be somewhat larger than the firepot.

Radiator. The radiator, so called, with which all furnaces of the better class are provided, acts as a sort of reservoir in which the gases are kept in contact with the air passing over the furnace until they have parted with a considerable portion of their heat. Radiators are built of cast iron, of steel plate, or of a combination of the two. The former is more durable and can be made with fewer joints, but owing to the difficulty of casting radiators of large size, steel plate is commonly used for the sides.

The effectiveness of a radiator depends on its form, its heating surface, and the difference between the temperature of the gases and the surrounding air. Owing to the accumulation of soot, the bottom surface becomes practically worthless after the furnace has been in use a short time; surfaces, to be effective, must therefore be self-cleaning.

If the radiator is placed near the bottom of the furnace the gases are surrounded by air at the lowest temperature, which renders the radiator more effective for a given size than if placed near the top and

surrounded by warm air. On the other hand, the cold air has a tendency to condense the gases, and the acids thus formed are likely to corrode the iron.

Heating Surface. The different heating surfaces may be described as follows: Firepot surface; surfaces acted upon by direct rays of heat from the fire, such as the dome or combustion chamber; gas- or smoke-heated surfaces, such as flues or radiators; and extended surfaces, such as pins or ribs. Surfaces unlike in character and location, vary greatly in heating power, so that, in making comparisons of different furnaces, we must know the kind, form, and location of the heating surfaces, as well as the area.

In some furnaces having an unusually large amount of surface, it will be found on inspection that a large part would soon become practically useless from the accumulation of soot. In others a large portion of the surface is lined with firebrick, or is so situated that the air-currents are not likely to strike it.

The ratio of grate to heating surface varies somewhat according to the size of furnace. It may be taken as 1 to 25 in the smaller sizes, and 1 to 15 in the larger.

Efficiency. One of the first items to be determined in estimating the heating capacity of a furnace, is its efficiency—that is, the proportion of the heat in the coal that may be utilized for warming. The efficiency depends chiefly on the area of the heating surface as compared with the grate, on its character and arrangement, and on the rate of combustion. The usual proportions between grate and heating surface have been stated. The rate of combustion required to maintain a temperature of 70° in the house, depends, of course, on the outside temperature. In very cold weather a rate of 4 to 5 pounds of coal per square foot of grate per hour must be maintained.

One pound of good anthracite coal will give off about 13,000 B. T. U., and a good furnace should utilize 70 per cent of this heat. The efficiency of an ordinary furnace is often much less, sometimes as low as 50 per cent.

In estimating the required size of a first-class furnace with good chimney draft, we may safely count upon a maximum combustion of 5 pounds of coal per square foot of grate per hour, and may assume that 8,000 B. T. U. will be utilized for warming purposes from each

pound burned. This quantity corresponds to an efficiency of 60 per cent.

Heating Capacity. Having determined the heat loss from a building by the methods previously given, it is a simple matter to compute the size of grate necessary to burn a sufficient quantity of coal to furnish the amount of heat required for warming.

In computing the size of furnace, it is customary to consider the whole house as a single room, with four outside walls and a cold attic. The heat losses by conduction and leakage are computed, and increased 10 per cent for the cold attic, and 16 per cent for exposure. The heat delivered to the various rooms may be considered as being made up of two parts—*first*, that required to warm the outside air up to 70° (the temperature of the rooms); and *second*, the quantity which must be added to this to offset the loss by conduction and leakage. Air is usually delivered through the registers at a temperature of 120°, with zero conditions outside, in the best class of residence work; so that $\frac{70}{120}$ of the heat given to the entering air may be considered as making up the first part, mentioned above, leaving $\frac{50}{120}$ available for purely heating purposes. From this it is evident that the heat supplied to the entering air must be equal to $1 \div \frac{50}{120} = 2.4$ times that required to offset the loss by conduction and leakage.

Example. The loss through the walls and windows of a building is found to be 80,000 B. T. U. per hour in zero weather. What will be the size of furnace required to maintain an inside temperature of 70 degrees?

From the above, we have the total heat required, equal to 80,000 $\times$ 2.4 = 192,000 B. T. U. per hour. If we assume that 8,000 B. T. U. are utilized per pound of coal, then 192,000 $\div$ 8,000 = 24 pounds of coal required per hour; and if 5 pounds can be burned on each square foot of grate per hour, then $\frac{24}{5} = 4.8$ square feet required. A grate 30 inches in diameter has an area of 4.9 square feet, and is the size we should use.

When the outside temperature is taken as 10° below zero, multiply by 2.6 instead of 2.4; and multiply by 2.8 for 20° below.

Table VII will be found useful in determining the diameter of firepot required.

TABLE VII

Firepot Dimensions

Average Diameter of Grate, in Inches	Area in Square Feet
18	1.77
20	2.18
22	2.64
24	3.14
26	3.69
28	4.27
30	4.91
32	5.58

EXAMPLES FOR PRACTICE

1. A brick apartment house is 20 feet wide, and has 4 stories, each being 10 feet in height. The house is one of a block, and is exposed only at the front and rear. The walls are 16 inches thick, and the block is so sheltered that no correction need be made for exposure. Single windows make up $\frac{1}{8}$ the total exposed surface. Figure for cold attic but warm basement. What area of grate surface will be required for a furnace to keep the house at a temperature of 70° when it is 10° below zero outside? Ans. 3.5 square feet.

2. A house having a furnace with a firepot 30 inches in diameter, is not sufficiently warmed, and it is decided to add a second furnace to be used in connection with the one already in. The heat loss from the building is found by computation to be 133,600 B. T. U. per hour, in zero weather. What diameter of firepot will be required for the extra furnace? Ans. 24 inches.

Location of Furnace. A furnace should be so placed that the warm-air pipes will be of nearly the same length. The air travels most readily through pipes leading toward the sheltered side of the house and to the upper rooms. Therefore pipes leading toward the north or west, or to rooms on the first floor, should be favored in regard to length and size. The furnace should be placed somewhat to the north or west of the center of the house, or toward the points of compass from which the prevailing winds blow.

Smoke-Pipes. Furnace smoke-pipes range in size from about 6 inches in the smaller sizes to 8 or 9 inches in the larger ones. They are generally made of galvanized iron of No. 24 gauge or heavier. The pipe should be carried to the chimney as directly as possible,

avoiding bends which increase the resistance and diminish the draft. Where a smoke-pipe passes through a partition, it should be protected by a soapstone or double-perforated metal collar having a diameter at least 8 inches greater than that of the pipe. The top of the smoke-pipe should not be placed within 8 inches of unprotected beams, nor less than 6 inches under beams protected by asbestos or plaster with a metal shield beneath. A collar to make tight connection with the chimney should be riveted to the pipe about 5 inches from the end, to prevent the pipe being pushed too far into the flue. Where the pipe is of unusual length, it is well to cover it to prevent loss of heat and the condensation of smoke.

Chimney Flues. Chimney flues, if built of brick, should have walls 8 inches in thickness, unless terra-cotta linings are used, when only 4 inches of brickwork is required. Except in small houses where an 8 by 8-inch flue may be used, the nominal size of the smoke flue should be at least 8 by 12-inches, to allow for contractions or offsets. A clean-out door should be placed at the bottom of the flue, for removing ashes and soot. A square flue cannot be reckoned at its full area, as the corners are of little value. To avoid down drafts, the top of the chimney must be carried above the highest point of the roof unless provided with a suitable hood or top.

Cold-Air Box. The cold-air box should be large enough to supply a volume of air sufficient to fill all the hot-air pipes at the same time. If the supply is too small, the distribution is sure to be unequal, and the cellar will become overheated from lack of air to carry away the heat generated.

If a box is made too small, or is throttled down so that the volume of air entering the furnace is not large enough to fill all the pipes, it will be found that those leading to the less exposed side of the house or to the upper rooms will take the entire supply, and that additional air to supply the deficiency will be drawn down through registers in rooms less favorably situated. It is common practice to make the area of the cold-air box three-fourths the combined area of the hot-air pipes. The inlet should be placed where the prevailing cold winds will blow into it; this is commonly on the north or west side of the house. If it is placed on the side away from the wind, warm air from the furnace is likely to be drawn out through the cold-air box.

Whatever may be the location of the entrance to the cold-air box, changes in the direction of the wind may take place which will bring the inlet on the wrong side of the house. To prevent the possibility of such changes affecting the action of the furnace, the cold-air box is sometimes extended through the house and left open at both ends, with check-dampers arranged to prevent back-drafts. These checks should be placed some distance from the entrance, to prevent their becoming clogged with snow or sleet.

The cold-air box is generally made of matched boards; but galvanized iron is much better; it costs more than wood, but is well worth the extra expense on account of tightness, which keeps the dust and ashes from being drawn into the furnace casing to be discharged through the registers into the rooms above.

The cold-air inlet should be covered with galvanized wire netting with a mesh of at least three-eighths of an inch. The frame to which it is attached should not be smaller than the inside dimensions of the cold-air box. A door to admit air from the cellar to the cold-air box is generally provided. As a rule, air should be taken from this source, only when the house is temporarily unoccupied or during high winds.



Fig 9. Common Method of Connecting Return Duct to Cold-Air Box.

Return Duct. In some cases it is desirable to return air to the furnace from the rooms above, to be reheated. Ducts for this purpose are common in places where the winter temperature is frequently below zero. Return ducts when used, should be in addition to the regular cold-air box. Fig. 9 shows a common method of making the connection between the two. By proper adjustment of the swinging damper, the air can be taken either from out of doors or through the register from the room above. The return register is often placed in the hallway of

a house, so that it will take the cold air which rushes in when the door is opened and also that which may leak in around it while closed. Check-valves or flaps of light gossamer or woolen cloth should be placed between the cold-air box and the registers to prevent back-drafts during winds.

The return duct should not be used too freely at the expense of outdoor air, and its use is not recommended except during the night when air is admitted to the sleeping rooms through open windows.

Warm-Air Pipes. The required size of the warm-air pipe to any given room, depends on the heat loss from the room and on the volume of warm air required to offset this loss. Each cubic foot of air warmed from zero to 120 degrees brings into a room 2.2 B. T. U. We have already seen that in zero weather, with the air entering the registers at 120 degrees, only $\frac{50}{120}$ of the heat contained in the air is available for offsetting the losses by radiation and conduction, so that only $2.2 \times \frac{50}{120} = .9$ B. T. U. in each cubic foot of entering air can be utilized for warming purposes. Therefore, if we divide the computed heat loss in B. T. U. from a room, by .9, it will give the number of cubic feet of air at 120 degrees necessary to warm the room in zero weather.

As the outside temperature becomes colder, the quantity of heat brought in per cubic foot of air increases; but the proportion available for warming purposes becomes less at nearly the same rate, so

TABLE VIII

Warm-Air Pipe Dimensions

Diameter of Pipe, in Inches	Area in Square Inches	Area in Square Feet
6	28	.196
7	38	.267
8	50	.349
9	64	.442
10	79	.545
11	95	.660
12	113	.785
13	133	.922
14	154	1.07
15	177	1.23
16	201	1.40

that for all practical purposes we may use the figure .9 for all usual conditions. In calculating the size of pipe required, we may assume maximum velocities of 260 and 380 feet per minute for rooms on the first and second floors respectively. Knowing the number of cubic feet of air per minute to be delivered, we can divide it by the velocity, which will give us the required area of the pipe in square feet.

Round pipes of tin or galvanized iron are used for this purpose. Table VIII will be found useful in determining the required diameters of pipe in inches.

Example. The heat loss from a room on the second floor is 18,000 B. T. U. per hour. What diameter of warm-air pipe will be required?

18,000 ÷ .9 = 20,000 = cubic feet of air required per hour. 20,000 ÷ 60 = 333 per minute. Assuming a velocity of 380 feet per minute, we have 333 ÷ 380 = .87 square foot, which is the area of pipe required. Referring to Table VIII, we find this comes between a 12-inch and a 13-inch pipe, and the larger size would probably be chosen.

EXAMPLES FOR PRACTICE

1. A first-floor room has a computed loss of 27,000 B. T. U. per hour when it is 10° below zero. The air for warming is to enter through two pipes of equal size, and at a temperature of 120 degrees. What will be the required diameter of the pipes?

ANS. 14 inches.

2. If in the above example the room had been on the second floor, and the air was to be delivered through a single pipe, what diameter would be required?

ANS. 16 inches.

Since long horizontal runs of pipe increase the resistance and loss of heat, they should not in general be over 12 or 14 feet in length. This applies especially to pipes leading to rooms on the first floor, or to those on the cold side of the house. Pipes of excessive length should be increased in size because of the added resistance.

Figs. 10 and 11 show common methods of running the pipes in the basement. The first gives the best results, and should be used where the basement is of sufficient height to allow it. A damper should be placed in each pipe near the furnace, for regulating the flow of air to the different rooms, or for shutting it off entirely when desired.

While round pipe risers give the best results, it is not always possible to provide a sufficient space for them, and flat or oval pipes are substituted. When vertical pipes must be placed in single partitions, much better results will be obtained if the studding can be



Fig. 10.



Fig. 11.

Common Methods of Running Hot-Air Pipes in Basement. Method Shown in Fig. 10 is Preferable where Feasible.

made 5 or 6 inches deep instead of 4 as is usually done. Flues should never in any case be made less than $3\frac{1}{2}$ inches in depth. Each room should be heated by a separate pipe. In some cases, however, it is allowable to run a single riser to heat two unimportant rooms on an upper floor. A clear space of at least $\frac{1}{2}$ inch should be left between the risers and studs, and the latter should be carefully tinned, and the

TABLE IX

Dimensions of Oval Pipes

Dimension of Pipe	Area in Square Inches
6 ovaled to 5 in.	27
7 " " 4 "	31
7 " " $3\frac{1}{2}$ "	29
7 " " 6 "	38
8 " " 5 "	43
9 " " 4 "	45
9 " " 6 "	57
9 " " 5 "	51
10 " " $3\frac{1}{2}$ "	46
11 " " 4 "	58
12 " " $3\frac{1}{2}$ "	55
10 " " 6 "	67
11 " " 5 "	67
14 " " 4 "	76
15 " " $3\frac{1}{2}$ "	73
12 " " 6 "	85
12 " " 5 "	75
19 " " 4 "	96
20 " " $3\frac{1}{2}$ "	100



VIEWS OF THE AMERICAN RADIATOR COMPANY'S STEAM BOILER FOR HARD COAL.

space between them on both sides covered with tin, asbestos, or wire lath.

Table IX gives the capacity of oval pipes. A 6-inch pipe ovaled to 5 means that a 6-inch pipe has been flattened out to a thickness of 5 inches, and column 2 gives the resulting area.

Having determined the size of round pipe required, an equivalent oval pipe can be selected from the table to suit the space available.

Registers. The registers which control the supply of warm air to the rooms, generally have a net area equal to two-thirds of their gross area. The net area should be from 10 to 20 per cent greater than the area of the pipe connected with it. It is common practice to use registers having the short dimensions equal to, and the long dimensions about one-half greater than, the diameter of the pipe. This would give standard sizes for different diameters of pipe, as listed in Table X.

TABLE X

Sizes of Registers for Different Sizes of Pipes

Diameter of Pipe	Size of Register
6 in.	6 × 10 in.
7 "	7 × 10 "
8 "	8 × 12 "
9 "	9 × 14 "
10 "	10 × 15 "
11 "	11 × 16 "
12 "	12 × 17 "
13 "	14 × 20 "
14 "	14 × 22 "
15 "	15 × 22 "
16 "	16 × 24 "

Combination Systems. A combination system for heating by hot air and hot water consists of an ordinary furnace with some form of surface for heating water, placed either in contact with the fire or suspended above it. Fig. 12 shows a common arrangement where part of the heating surface forms a portion of the lining to the firepot and the remainder is above the fire.

Care must be taken to proportion properly the work to be done by the air and the water; else one will operate at the expense of the other. One square foot of heating surface in contact with the fire is capable of supplying from 40 to 50 square feet of radiating surface,

and one square foot suspended over the fire will supply from 15 to 25 square feet of radiation.

The value or efficiency of the heating surface varies so widely in different makes that it is best to state the required conditions to the



Fig. 12. Combination Furnace, for Heating by Both Hot Air and Hot Water.

manufacturers and have them proportion the surfaces as their experience has found best for their particular type of furnace.

Care and Management of Furnaces. The following general rules apply to the management of all hard coal furnaces.

The fire should be thoroughly shaken once or twice daily in cold weather. It is well to keep the firepot heaping full at all times. In

this way a more even temperature may be maintained, less attention is required, and no more coal is burned than when the pot is only partly filled. In mild weather the mistake is frequently made of carrying a thin fire, which requires frequent attention and is likely to die out. Instead, to diminish the temperature in the house, keep the firepot full and allow ashes to accumulate on the grate (not under it) by shaking less frequently or less vigorously. The ashes will hold the heat and render it an easy matter to maintain and control the fire. When feeding coal on a low fire, open the drafts and neither rake nor shake the fire till the fresh coal becomes ignited. The air supply to the fire is of the greatest importance. An insufficient amount results in incomplete combustion and a great loss of heat. To secure proper combustion, the fire should be controlled principally by means of the ash-pit through the ash-pit door or slide.

The smoke-pipe damper should be opened only enough to carry off the gas or smoke and to give the necessary draft. The openings in the feed door act as a check on the fire, and should be kept closed during cold weather, except just after firing, when with a good draft they may be partly opened to increase the air-supply and promote the proper combustion of the gases.

Keep the ash-pit clear to avoid warping or melting the grate. The cold-air box should be kept wide open except during winds or when the fire is low. At such times it may be partly, but never completely closed. Too much stress cannot be laid on the importance of a sufficient air-supply to the furnace. It costs little if any more to maintain a comfortable temperature in the house night and day than to allow the rooms to become so cold during the night that the fire must be forced in the morning to warm them up to a comfortable temperature.

In case the warm air fails at times to reach certain rooms, it may be forced into them by temporarily closing the registers in other rooms. The current once established will generally continue after the other registers have been opened.

It is best to burn as hard coal as the draft will warrant. Egg size is better than larger coal, since for a given weight small lumps expose more surface and ignite more quickly than larger ones. The furnace and smoke-pipe should be thoroughly cleaned once a year.

This should be done just after the fire has been allowed to go out in the spring.

STEAM BOILERS

Types. The boilers used for heating are the same as have already been described for power work. In addition there is the cast-iron sectional boiler, used almost exclusively for dwelling-houses.

Tubular Boilers. Tubular boilers are largely used for heating purposes, and are adapted to all classes of buildings except dwelling-houses and the special cases mentioned later, for which sectional boilers are preferable. A *boiler horse-power* has been defined as the evaporation of 34½ pounds of water from and at a temperature of 212 degrees, and in doing this 33,317 B. T. U. are absorbed, which are again given out when the steam is condensed in the radiators. Hence to find the boiler H. P. required for warming any given building, we have only to compute the heat loss per hour by the methods already given, and divide the result by 33,330. It is more common to divide by the number 33,000, which gives a slightly larger boiler and is on the side of safety.

The commercial horse-power of a well-designed boiler is based upon its heating surface; and for the best economy in heating work, it should be so proportioned as to have about 1 square foot heating of surface for each 2 pounds of water to be evaporated from and at 212 degrees F. This gives $34.5 \div 2 = 17.2$ square feet of heating surface per horse-power, which is generally taken as 15 in practice. Makers of tubular boilers commonly rate them on a basis of 12 square feet of heating surface per horse-power. This is a safe figure under the conditions of power work, where skilled firemen are employed and where more care is taken to keep the heating surfaces free from soot and ashes. For heating plants, however, it is better to rate the boilers upon 15 square feet per horse-power as stated above.

There is some difference of opinion as to the proper method of computing the heating surface of tubular boilers. In general, all surface is taken which is exposed to the hot gases on one side and to the water on the other. A safe rule, and the one by which Table XII is computed, is to take ½ the area of the shell, ⅔ of the rear head, less the tube area, and the interior surface of all the tubes.

The required amount of grate area, and the proper ratio of heat-

ing surface to grate area, vary a good deal, depending on the character of the fuel and on the chimney draft. By assuming the probable rates of combustion and evaporation, we may compute the required grate area for any boiler from the formula:

$$S = \frac{H.P. \times 34.5}{E \times C},$$

in which

S = Total grate area, in square feet;

E = Pounds of water evaporated per pound of coal;

C = Pounds of coal burned per square foot of grate per hour.

Table XI gives the approximate grate area per H. P. for different rates of evaporation and combustion as computed by the above equation.

TABLE XI

Grate Area per Horse-Power for Different Rates of Evaporation and Combustion

Pounds of Steam per Pound of Coal	Pounds of Coal Burned per Square Foot of Grate per Hour		
	8 lbs.	10 lbs.	12 lbs.
	Square Feet of Grate Surface per Horse-Power		
10	.43	.35	.28
9	.48	.38	.32
8	.54	.43	.36
7	.62	.49	.41
6	.72	.58	.48

For example, with an evaporation of 8 pounds of steam per pound of coal, and a combustion of 10 pounds of coal per square foot of grate, .43 of a square foot of grate surface per H. P. would be called for.

The ratio of heating to grate surface in this type of boiler ranges from 30 to 40, and therefore allows under ordinary conditions a combustion of from 8 to 10 pounds of coal per square foot of grate. This is easily obtained with a good chimney draft and careful firing. The larger the boiler, the more important the plant usually, and the greater the care bestowed upon it, so that we may generally count on a higher rate of combustion and a greater efficiency as the size of the boiler increases. Table XII will be found very useful in determining the size of boiler required under different conditions. The grate area is computed for an evaporation of 8 pounds of water per pound

TABLE XII

Diameter of Shell in Inches	Number of Tubes	Diameter of Tubes in Inches	Length of Tubes in Feet	Horse-Power	Size of Grate in Inches	Size of Uptake in Inches	Size of Smoke-pipe in Sq. In.
30	28	2½	6	8.5	24 x 36	10 x 14	140
			7	9.9	24 x 36	10 x 14	140
			8	11.2	24 x 36	10 x 14	140
			9	12.6	24 x 42	10 x 14	140
			10	14.0	24 x 42	10 x 14	140
36	34	2½	8	13.6	30 x 36	10 x 16	160
			9	15.3	30 x 42	10 x 18	180
			10	16.9	30 x 42	10 x 18	180
			11	18.6	30 x 48	10 x 20	200
			12	20.9	30 x 48	10 x 20	200
42	34	3	9	18.5	36 x 42	10 x 20	200
			10	20.5	36 x 42	10 x 20	200
			11	22.5	36 x 48	10 x 25	250
			12	24.5	36 x 48	10 x 25	250
			13	26.5	36 x 48	10 x 28	280
			14	28.5	36 x 54	10 x 28	280
48	44	3	10	30.4	42 x 48	10 x 28	280
			11	33.2	42 x 48	10 x 28	280
			12	35.7	42 x 54	10 x 32	320
			13	38.3	42 x 54	10 x 32	320
			14	40.8	42 x 60	10 x 36	360
			15	43.4	42 x 60	10 x 36	360
			16	45.9	42 x 60	10 x 36	360
54	54	3	11	34.6	48 x 54	10 x 38	380
			12	37.7	48 x 54	10 x 38	380
			13	40.8	48 x 54	10 x 38	380
			14	43.9	48 x 54	10 x 38	380
			15	47.0	48 x 60	10 x 40	400
			16	50.1	48 x 60	10 x 40	400
	46	3½	17	53.0	48 x 60	10 x 40	400
60	72	3	12	48.4	54 x 60	12 x 40	460
			13	52.4	54 x 60	12 x 40	460
			14	56.4	54 x 60	12 x 40	460
			15	60.4	54 x 66	12 x 42	500
			16	64.4	54 x 66	12 x 42	500
	64	3½	17	71.4	54 x 72	12 x 48	550
			18	75.6	54 x 72	12 x 48	550
66	90	3	14	70.1	60 x 66	12 x 48	500
			15	75.0	60 x 72	12 x 52	620
			16	80.0	60 x 72	12 x 52	620
	78	3½	17	86.0	60 x 78	12 x 56	670
			18	91.1	60 x 78	12 x 56	670
			19	96.2	60 x 78	12 x 56	670
	62	4	20	93.1	60 x 78	12 x 56	670
72	114	3	14	87.4	66 x 72	12 x 56	670
			15	93.6	66 x 72	12 x 56	670
			16	99.7	66 x 78	12 x 62	740
	98	3½	17	106.4	66 x 78	12 x 62	740
			18	112.6	66 x 84	12 x 66	790
			19	118.8	66 x 84	12 x 66	790
	72	4	20	107.3	66 x 84	12 x 66	790

of coal, which corresponds to an efficiency of about 60 per cent, and is about the average obtained in practice for heating boilers.

The areas of uptake and smoke-pipe are figured on a basis of 1 square foot to 7 square feet of grate surface, and the results given in round numbers. In the smaller sizes the relative size of smoke-pipe is greater. The rate of combustion runs from 6 pounds in the smaller sizes to 11½ in the larger. Boilers of the proportions given in the table, correspond well with those used in actual practice, and may be relied upon to give good results under all ordinary conditions.

Water-tube boilers are often used for heating purposes, but more especially in connection with power plants. The method of computing the required H. P. is the same as for tubular boilers.

Sectional Boilers. Fig. 13 shows a common form of cast-iron boiler. It is made up of slabs or sections, each one of which is connected by nipples with headers at the sides and top. The top header acts as a steam drum, and the lower ones act as mud drums; they also receive the water of condensation from the radiators. The gases from the fire pass backward and forward through flues and are finally taken off at the rear of the boiler.

Another common form of sectional boiler is shown in Fig. 14. It is made up of sections which increase the length like the one just described. These boilers have no drum connecting with the sections; but instead, each section connects with the adjacent one through openings at the top and bottom, as shown.

The ratio of heating to grate surface in boilers of this type ranges from 15 to 25 in the best makes. They are provided with the usual attachments, such as pressure-gauge, water-glass, gauge-cocks, and safety-valve; a low-pressure damper regulator is furnished for operating the draft doors, thus keeping the steam pressure practically constant. A pressure of from 1 to 5 pounds is usually carried on these boilers, depending upon the outside temperature. The usual setting is simply a covering of some kind of non-conducting material like plastic magnesia or asbestos, although some forms are enclosed in light brickwork.

In computing the required size, we may proceed in the same manner as in the case of a furnace. For the best types of house-heating boilers, we may assume a combustion of 5 pounds of coal per square foot of grate per hour, and an average efficiency of 60 per cent,

which corresponds to 8,000 B. T. U. per pound of coal, available for useful work.

In the case of direct-steam heating, we have only to supply heat to offset that lost by radiation and conduction; so that the grate area may be found by dividing the computed heat loss per hour by 8,000, which gives the number of pounds of coal; and this in turn, divided by 5, will give the area of grate required. The most efficient rate of



Fig. 13. Common Type of Cast-Iron Sectional Boiler. Note Headers at Sides and Top Acting as Drums.

combustion will depend somewhat upon the ratio between the grate and heating surface. It has been found by experience that about $\frac{1}{4}$ of a pound of coal per hour for each square foot of heating surface gives the best results; so that, by knowing the ratio of heating surface to grate area for any make of heater, we can easily compute the most efficient rate of combustion, and from it determine the necessary grate area.

For example, suppose the heat loss from a building to be 480,000 B. T. U. per hour, and that we wish to use a heater in which the ratio of heating surface to grate area is 24. What will be the most efficient rate of combustion and the required grate area? 480,000 ÷ 8,000 = 60 pounds of coal per hour, and 24 ÷ 4 = 6, which is the best rate of combustion to employ; therefore 60 ÷ 6 = 10, the grate area required.



Fig. 14. Another Type of Sectional Boiler. Here there are no drums, the sections being directly connected through openings at top and bottom.
Courtesy of American Radiator Co.

There are many different designs of cast-iron boilers for low-pressure steam and hot-water heating. In general, boilers having a drum connected by nipples with each section give dryer steam and hold a steadier water-line than the second form, especially when forced above their normal capacity. The steam, in passing through the openings between successive sections in order to reach the outlet, is apt to carry with it more or less water, and to choke the openings, thus producing an uneven pressure in different parts of the boiler.

In the case of hot-water boilers this objection disappears.

In order to adapt this type of boiler to steam work, the opening between the sections should be of good size, with an ample steam space above the water-line; and the nozzles for the discharge of steam should be located at frequent intervals.

EXAMPLES FOR PRACTICE

1. The heat loss from a building is 240,000 B. T. U. per hour, and the ratio of heating to grate area in the heater to be used is 20. What will be the required grate area? ANS. 6 sq. ft.

2. The heat loss from a building is 168,000 B. T. U. per hour, and the chimney draft is such that not over 3 pounds of coal per hour can be burned per square foot of grate. What ratio of heating to grate area will be necessary, and what will be the required grate area?

ANS. Ratio, 12. Grate area, 7 sq. ft.

Cast-iron sectional boilers are used for dwelling-houses, small schoolhouses, churches, etc., where low pressures are carried. They are increased in size by adding more slabs or sections. After a certain length is reached, the rear sections become less and less efficient, thus limiting the size and power.

Horse-Power for Ventilation. We already know that one B. T. U. will raise the temperature of 1 cubic foot of air 55 degrees, or it will raise 100 cubic feet $\frac{1}{100}$ of 55 degrees, or $\frac{55}{100}$ of 1 degree; therefore, to raise 100 cubic feet 1 degree, it will take $1 \div \frac{55}{100}$, or $\frac{100}{55}$ B. T. U.; and to raise 100 cubic feet through 100 degrees, it will take $\frac{100}{55} \times 100$ B. T. U. In other words, the B. T. U. required to raise any given volume of air through any number of degrees in temperature, is equal to

$$\frac{\text{Volume of air in cubic ft.} \times \text{Degrees raised}}{55}$$

Example. How many B. T. U. are required to raise 100,000 cubic feet of air 70 degrees?

$$\frac{100{,}000 \times 70}{55} = 127{,}272 +$$

To compute the H. P. required for the ventilation of a building, we multiply the total air-supply, in cubic feet per hour, by the number of degrees through which it is to be raised, and divide the result by 55. This gives the B. T. U. per hour, which, divided by 33,000, will give the H. P. required. In using this rule, always take the air-supply in cubic feet per *hour*.

EXAMPLES FOR PRACTICE

1. The heat loss from a building is 1,650,000 B. T. U. per hour. There is to be an air-supply of 1,500,000 cubic feet per hour, raised through 70 degrees. What is the total boiler H. P. required?

ANS. 108.

2. A high school has 10 classrooms, each occupied by 50 pupils. Air is to be delivered to the rooms at a temperature of 70 degrees. What will be the total H. P. required to heat and ventilate the building when it is 10 degrees below zero, if the heat loss through walls and windows is 1,320,000 B. T. U. per hour? ANS. 106+.

DIRECT-STEAM HEATING

A system of direct-steam heating consists (1) of a furnace and

boiler for the combustion of fuel and the generation of steam; (2) a system of pipes for conveying the steam to the radiators and for returning the water of condensation to the boiler; and (3) radiators or coils placed in the rooms for diffusing the heat.

Various types of boilers are used, depending upon the size and kind of building to be warmed. Some form of cast-iron sectional boiler is commonly used for dwelling-houses, while the tubular or water-tube boiler is more usually employed in larger buildings. Where the boiler is used for heating purposes only, a low steam-pressure of from 2 to 10 pounds is carried, and the condensation flows back by gravity to the boiler, which is placed below the lowest radiator. When, for any reason, a higher pressure is required, the steam for the heating system is made to pass through a reducing valve, and the condensation is returned to the boiler by means of a pump or return trap.



Fig. 15. Common Type of Cast-Iron Sectional Radiator.

Types of Radiating Surface. The radiation used in direct-steam heating is made up of cast-iron radiators of various forms, pipe radiators, and circulation coils.

Cast-Iron Radiators. The general form of a cast-iron sectional radiator is shown in Fig. 15. Radiators of this type are made up of sections, the number depending upon the amount of heating surface required. Fig. 16 shows an intermediate section of a radiator of this type. It is simply a loop with inlet and outlet at the bottom. The end sections are the same, except that they have legs, as shown in Fig. 17. These sections are connected at the bottom by special nipples, so that steam entering at the end fills the bottom of the radiator, and, being lighter than the air, rises through the loops and forces the air downward and toward the farther end, where it is discharged through an air-valve placed about midway of the last section. There are many different designs varying in height and width, to

suit all conditions. The wall pattern shown in Fig. 18 is very convenient when it is desired to place the radiator above the floor, as in bathrooms, etc.; it is also a convenient form to place under the windows of halls and churches to counteract the effect of cold down drafts. It is adapted to nearly every place where the ordinary direct radiator can be used, and may be connected up in different ways to meet the various requirements.



Fig. 16.



Fig. 17.

Intermediate and End Sections of Radiator Shown in Fig. 15. The end sections (at right) have legs.

A low and moderately shallow radiator, with ample space for the circulation of air between the sections, is more efficient than a deep radiator with the sections closely packed together. One- and two-column radiators, so called, are preferable to three- and four-column, when there is sufficient space to use them.



Fig. 18. Cast-Iron Sectional Radiator of Wall Pattern.

The standard height of a radiator is 36 or 38 inches, and, if possible, it is better not to exceed this.

For small radiators, it is better practice to use lower sections and increase the length; this makes the radiator slightly more efficient and gives a much better appearance.

To get the best results from wall radiators, they should be set out at least 1½ inches from the wall to allow a free circulation of air back of them. Patterns having cross-bars should be placed, if possible, with the bars in a vertical position, as their efficiency is impaired somewhat when placed horizontally.

Pipe Radiators. This type of radiator (see Fig. 19) is made up of wrought-iron pipes screwed into a cast-iron base. The pipes are either connected in pairs at the top by return bends, or each separate tube has a thin metal diaphragm passing up the center nearly to the top. It is necessary that a loop be formed, else a "dead end" would occur. This would become filled with air and prevent steam from entering, thus causing portions of the radiator to remain cold.



Fig. 19. Wrought-Iron Pipe Radiator.

Circulation Coils. These are usually made up of 1 or 1¼-inch wrought-iron pipe, and may be hung on the walls of a room by means of hook plates, or suspended overhead on hangers and rolls.

Fig. 20 shows a common form for schoolhouse and similar work; this coil is usually made of 1¼-inch pipe screwed into *headers* or *branch tees* at the ends, and is hung on the wall just below the windows. This is known as a *branch coil.* Fig. 21 shows a *trombone coil,* which is commonly used when the pipes cannot turn a corner, and where the entire coil must be placed upon one side of the room. Fig. 22

is called a *miter coil,* and is used under the same conditions as a trombone coil if there is room for the vertical portion. This form is not so pleasing in appearance as either of the other two, and is found only in factories or shops, where looks are of minor importance.



Fig. 20. Common Form of "Branch" Coil for Circulation of Direct Steam.

Overhead coils are usually of the miter form, laid on the side and suspended about a foot from the ceiling; they are less efficient than when placed nearer the floor, as the warm air stays at the ceiling and the lower part of the room is likely to remain cold. They are used



Fig. 21. "Trombone" Coil. Used where Entire Coil must be Placed on One Side of Room

only when wall coils or radiators would be in the way of fixtures, or when they would come below the water-line of the boiler if placed near the floor.

When steam is first turned on a coil, it usually passes through a

Fig. 22. "Miter" Coil. Adapted, like the "Trombone," Only to a Single Wall. Frequently Used in Factories and Shops.

portion of the pipes first and heats them while the others remain cold and full of air. Therefore the coil must always be made up in such a way that each pipe shall have a certain amount of spring and may expand independently without bringing undue strains upon the others. Circulation coils should incline about 1 inch in 20 feet toward the

return end in order to secure proper drainage and quietness of operation.

Efficiency of Radiators. The efficiency of a radiator—that is, the B. T. U. which it gives off per square foot of surface per hour—depends upon the difference in temperature between the steam in the radiator and the surrounding air, the velocity of the air over the radiator, and the quality of the surface, whether smooth or rough. In ordinary low-pressure heating, the first condition is practically constant; but the second varies somewhat with the pattern of the radiator. An open design which allows the air to circulate freely over the radiating surfaces, is more efficient than a closed pattern, and for this reason a pipe coil is more efficient than a radiator.

In a large number of tests of cast-iron and pipe radiators, working under usual conditions, the heat given off per square foot of surface per hour for each degree difference in temperature between the steam and surrounding air was found to average about 1.7 B. T. U. The temperature of steam at 3 pounds' pressure is 220 degrees, and 220—70 = 150, which may be taken as the average difference between the temperature of the steam and the air of the room, in ordinary low-pressure work. Taking the above results, we have $150 \times 1.7 = 255$ B. T. U. as the efficiency of an average cast-iron or pipe radiator. This, for convenient use, may be taken as 250. A circulation coil made up of pipes from 1 to 2 inches in diameter, will easily give off 300 B. T. U. under the same conditions; and a cast-iron wall radiator with ample space back of it should have an efficiency equal to that of a wall coil. While overhead coils have a higher efficiency than cast-iron radiators, their position near the ceiling reduces their effectiveness, so that in practice the efficiency should not be taken over 250 B. T. U. per hour at the most. Tabulating the above we have:

TABLE XIII

Efficiency of Radiators, Coils, etc.

Type of Radiating Surface	Radiation per Square Foot of Surface per Hour
Cast-Iron Sectional and Pipe Radiators	250 B. T. U.
Wall Radiators	300 "
Ceiling Coils	200 to 250 "
Wall Coils	300 "

If the radiator is for warming a room which is to be kept at a temperature above or below 70 degrees, or if the steam pressure is greater than 3 pounds, the radiating surface may be changed in the same proportion as the difference in temperature between the steam and the air.

For example, if a room is to be kept at a temperature of 60°, the efficiency of the radiator becomes $\frac{150}{140} \times 250 = 268$; that is, the efficiency varies directly as the difference in temperature between the steam and the air of the room. It is not customary to consider this unless the steam pressure should be raised to 10 or 15 pounds or the temperature of the rooms changed 15 or 20 degrees from the normal.

From the above it is easy to compute the size of radiator for any given room. First compute the heat loss per hour by conduction and leakage in the coldest weather; then divide the result by the efficiency of the type of radiator to be used. It is customary to make the radiators of such size that they will warm the rooms to 70 degrees in the coldest weather. As the low-temperature limit varies a good deal in different localities, even in the same State, the lowest temperature for which we wish to provide must be settled upon before any calculations are made. In New England and through the Middle and Western States, it is usual to figure on warming a building to 70 degrees when the outside temperature is from zero to 10 degrees below.

The different makers of radiators publish in their catalogues, tables giving the square feet of heating surface for different styles and heights, and these can be used in determining the number of sections required for all special cases.

If pipe coils are to be used, it becomes necessary to reduce square feet of heating surface to linear feet of pipe; this can be done by means of the factors given below.

Square feet of heating surface $\times$

3	=	linear ft. of	1 -in. pipe
2.3	=	" "	1¼-in. "
2	=	" "	1½-in. "
1.6	=	" "	2 -in. "

The size of radiator is made only sufficient to keep the room warm after it is once heated; and no allowance is made for *warming up*; that is, the heat given off by the radiator is just equal to that lost through walls and windows. This condition is offset in two ways—



TYPICAL HEATING INSTALLATION SHOWING SECTIONAL BOILER AND RADIATOR.

American Radiator Company.

first, when the room is cold, the difference in temperature between the steam and the air of the room is greater, and the radiator is more efficient; and *second*, the radiator is proportioned for the coldest weather, so that for a greater part of the time it is larger than necessary.

EXAMPLES FOR PRACTICE

1. The heat loss from a room is 25,000 B. T. U. per hour in the coldest weather. What size of direct radiator will be required?

ANS. 100 square feet.

2. A schoolroom is to be warmed with circulation coils of 1¼-inch pipe. The heat loss is 30,000 B. T. U. per hour. What length of pipe will be required?

ANS. 230 linear feet.

Location of Radiators. Radiators should, if possible, be placed in the coldest part of the room, as under windows or near outside doors. In living rooms it is often desirable to keep the windows free, in which case the radiators may be placed at one side. Circulation coils are run along the outside walls of a room under the windows. Sometimes the position of the radiators is decided by the necessary location of the pipe risers, so that a certain amount of judgment must be used in each special case as to the best arrangement to suit all requirements.

Systems of Piping. There are three distinct systems of piping, known as the *two-pipe system*, the *one-pipe relief system*, and the *one-pipe circuit system*, with various modifications of each and combinations of the different systems.

Fig. 23 shows the arrangement of piping and radiators in the two-pipe system. The steam main leads from the top of the boiler, and the branches are carried along near the basement ceiling. Risers are taken from the supply branches, and carried up to the radiators on the different floors; and return pipes are brought down to the return mains, which should be placed near the basement floor below the water-line of the boiler. Where the building is more than two stories high, radiators in similar positions on different floors are connected with the same riser, which may run to the highest floor; and a corresponding return drop connecting with each radiator is carried down beside the riser to the basement. A system in which the main horizontal returns are below the water-line of the boiler is said to

have a *wet* or *sealed* return. If the returns are overhead and above the water-line, it is called a *dry* return. Where the steam is exposed to extended surfaces of water, as in overhead returns, where the condensation partially fills the pipes, there is likely to be cracking or *water-hammer*, due to the sudden condensation of the steam as it comes in contact with the cooler water. This is especially noticeable when steam is first turned into cold pipes and radiators, and the condensation is excessive. When dry returns are used, the pipes should be large and have a good pitch toward the boiler.

In the case of sealed returns, the only contact between the steam



Fig. 23. Arrangement of Piping and Radiators in "Two-Pipe" System.

and standing water is in the vertical returns, where the exposed surfaces are very small (being equal to the sectional area of the pipes), and trouble from water-hammer is practically done away with. Dry returns should be given an incline of at least 1 inch in 10 feet, while for wet returns 1 inch in 20 or even 40 feet is ample. The ends of all steam mains and branches should be dripped into the returns. If the return is sealed, the drip may be directly connected as shown in Fig. 24; but if it is dry, the connection should be provided with a siphon loop as indicated in Fig. 25. The loop becomes filled with water, and prevents steam from flowing directly into the return. As the

condensation collects in the loop, it overflows into the return pipe and is carried away. The return pipes in this case are of course filled with steam above the water; but it is steam which has passed through the radiators and their return connections, and is therefore at a slightly lower pressure; so that, if steam were admitted directly from the main, it would tend to hold back the water in more distant returns and cause surging and cracking in the pipes. Sometimes the boiler is at a lower level than the basement in which the returns are run, and it then becomes necessary to establish a *false* water-line. This is done by making connections as shown in Fig. 26.



Fig. 24. Drip from Steam Main Connected Directly to Sealed Return.

It is readily seen that the return water, in order to reach the boiler, must flow through the trap, which raises the water-line or seal to the level shown by the dotted line. The balance pipe is to equalize the pressure above and below the water in the trap, and prevent siphonic action, which would tend to drain the water out of the return mains after a flow was once started.

The balance pipe, when possible, should be 15 or 20 feet in length, with a throttle-valve placed near its connection with the main. This valve should be opened just enough to allow the steam-pressure to act upon the air which occupies the space above the water in the trap; but it should not be opened sufficiently to allow the steam to enter in large volume and drive the air out. The success of this arrangement depends upon keeping a layer or cushion of cool air next to the surface of the water in the trap, and this is easily done by following the method here described.



Fig. 25. Use of Siphon in Connecting Drip from Steam Main to a "Dry" Return.

One-Pipe Relief System. In this system of piping, the radiators have but a single connection, the steam flowing in and the condensation draining out through the same pipe. Fig. 27 shows the method of running the pipes for this system. The steam main, as before, leads from the top of the boiler, and is carried to as high a point as the basement ceiling will allow; it then slopes downward with a grade of about 1 inch in 10 feet, and makes a circuit of the building or a portion of it.

Risers are taken from the top and carried to the radiators above, as in the two-pipe system; but in this case, the condensation flows back through the same pipe, and drains into the return main near the floor through drip connections which are made at frequent intervals. In a two-story building, the bottom of each riser to the second floor is dripped; and in larger buildings, it is customary to drip each riser that has more than one radiator connected with it. If the radiators are large and at a considerable distance from the next riser, it is better to make a drip connection for each radiator. When the return main is overhead, the risers should be dripped through siphon loops; but the ends of the branches should make direct connection with the returns. This is the reverse of the two-pipe system. In this case the lowest pressure is at the ends of the mains, so that steam introduced into the returns at these points will cause no trouble in the pipes connecting between these and the boiler.



Fig. 26. Connections Made to Establish "False" Water-Line when Boiler is below Basement Level.

If no steam is allowed to enter the returns, a vacuum will be formed, and there will be no pressure to force the water back to the

boiler. A check-valve should always be placed in the main return



Fig. 27. Arrangement of Piping and Radiators in "One-Pipe Relief" System.

near the boiler, to prevent the water from flowing out in case of a vacuum being formed suddenly in the pipes.



Fig. 28. Arrangement of Piping and Radiators in "One-Pipe Circuit" System.

There is but little difference in the cost of the two systems, as larger pipes and valves are required for the single-pipe method

With radiators of medium size and properly proportioned connections, the single-pipe system in preferable, there being but one valve to operate and only one-half the number of risers passing through the lower rooms.

One-Pipe Circuit System. In this case, illustrated in Fig. 28, the steam main rises to the highest point of the basement, as before; and then, with a considerable pitch, makes an entire circuit of the building, and again connects with the boiler below the water-line. Single risers are taken from the top; and the condensation drains back through the same pipes, and is carried along with the flow of steam to the extreme end of the main, where it is returned to the boiler. The main is made large, and of the same size throughout its entire length. It must be given a good pitch to insure satisfactory results.



Fig. 29. "One-Pipe Circuit" System. Adapted to a Large Building.

One objection to a single-pipe system is that the steam and return water are flowing in opposite directions, and the risers must be made of extra large size to prevent any interference. This is overcome in large buildings by carrying a single riser to the attic, large enough to supply the entire building; then branching and running "drops" to the basement. In this system the flow of steam is downward, as well as that of water. This method of piping may be used with good results in two-pipe systems as well. Care must always be taken that no pockets or low points occur in any of the lines of pipe; but if for any reason they cannot be avoided, they should be carefully drained.

A modification of this system, adapting it to large buildings, is shown in diagram in Fig. 29. The riser shown in this case is one of

several, the number depending upon the size of the building; and may be supplied at either bottom or top as most desirable. If steam is supplied at the bottom of the riser, as shown in the cut, all of the drip connections with the return drop, except the upper one, should



Fig. 30. "Two-Pipe" Connection of Radiator to Riser and Return.



Fig. 31. "One-Pipe" Connection of Radiator to Basement Main.

be sealed with either a siphon loop or a check-valve, to prevent the steam from short-circuiting and holding back the condensation in the returns above. If an overhead supply is used, the arrangement should be the reverse; that is, all return connections should be sealed except the lowest.

Sometimes a separate drip is carried down from each set of radiators, as shown on the lower story, being connected with the main return below the water-line of the boiler. In case this is done, it is well to provide a check-valve in each drip below the water-line.



Fig. 32. "One-Pipe" Connection of Radiator to Riser.

In buildings of any considerable size, it is well to divide the piping system into sections by means of valves placed in the corresponding supply and return branches. These are for use in case of a break in any part of the system, so that it will be necessary to shut off only a small part of the heating system during repairs. In tall buildings, it is customary to place valves at the top and bottom of each riser, for the same purpose.

Radiator Connections. Figs. 30, 31, and 32 show the common

methods of making connections between supply pipes and radiators. Fig. 30 shows a two-pipe connection with a riser; the return is carried down to the main below. Fig. 31 shows a single-pipe connection with a basement main; and Fig. 32, a single connection with a riser.

Care must always be taken to make the horizontal part of the piping between the radiator and riser as short as possible, and to give it a good pitch toward the riser. There are various ways of making these connections, especially suited to different conditions; but the examples given serve to show the general principle to be followed.

Figs. 20, 21, and 22 show the common methods of making steam and return connections with circulation coils. The position of the air-valve is shown in each case.

Expansion of Pipes. Cold steam pipes expand approximately



Fig. 33. Elevation and Plan of Swivel-Joint to Counteract Effects of Expansion and Contraction in Pipes.

1 inch in each 100 feet in length when low-pressure steam is turned into them; so that, in laying out a system of piping, we must arrange it in such a manner that there will be sufficient "spring" or "give" to the pipes to prevent injurious strains. This is done by means of offsets and bends. In the case of larger pipes this simple method will not be sufficient, and swivel or slip joints must be used to take up the expansion.

The method of making up a swivel-joint is shown in Fig. 33. Any lengthening of the pipe *A* will be taken up by slight turning or swivel movements at the points *B* and *C*. A slip-joint is shown in

Fig. 34. The part *c* slides inside the shell *d*, and is made steam-tight by a stuffing-box, as shown. The pipes are connected at the flanges *A* and *B*.



Fig. 34. "Slip-Joint" Connection to Take Care of Expansion and Contraction of Pipes.

When pipes pass through floors or partitions, the woodwork should be protected by galvanized-iron sleeves having a diameter from $\frac{3}{4}$ to 1 inch greater than the pipe. Fig. 35 shows a form of adjustable floor-sleeve which may be lengthened or shortened to conform to the thickness of floor or partition. If plain sleeves are used, a plate should be placed around



Fig. 35. Adjustable Metal Sleeve for Carrying Pipe through Floor or Partition.



Fig. 36. Floor-Plate Adjusted to Plain Sleeve for Carrying Pipe through Floor or Partition.

the pipe where it passes through the floor or partition. These are

Fig. 37. Angle Valve.

Fig. 38. Offset Valve.

Fig. 39. Corner Valve.

Valves for Radiator Connections.

made in two parts so that they may be put in place after the pipe is hung. A plate of this kind is shown in Fig. 36.

Valves. The different styles commonly used for radiator connections are shown in Figs. 37, 38, and 39, and are known as *angle*, *offset*, and *corner* valves, respectively. The first is used when the radiator is at the top of a riser or when the connections are like those shown in Figs. 30, 31, and 32; the second is used when the connection



Fig. 40. Indicating Effect of Using Globe Valve on Horizontal Steam Supply Pipe or Dry Return.

between the riser and radiator is above the floor; and the third, when the radiator has to be set close in the corner of a room and there is not space for the usual connection.

A *globe* valve should never be used in a horizontal steam supply or dry return. The reason for this is plainly shown in Fig. 40. In order for water to flow through the valve, it must rise to a height shown by the dotted line, which would half fill the pipes, and cause serious trouble from water-hammer. The gate valve shown in Fig. 41 does not have this undesirable feature, as the opening is on a level with the bottom of the pipe.



Fig. 41. Gate Valve.



Fig. 42. Simplest Form of Air-Valve. Operated by Hand.

Air-Valves. Valves of various kinds are used for freeing the radiators from air when steam is turned on. Fig. 42 shows the simplest form, which is operated by hand. Fig. 43 is a type of automatic valve, consisting of a shell, which is attached to the radiator. *B* is a small opening which may be closed by the spindle *C*, which

is provided with a conical end. *D* is a strip composed of a layer of iron or steel and one of brass soldered or brazed together. The action of the valve is as follows: when the radiator is cold and filled with air the valve stands as shown in the cut. When steam is turned on, the air is driven out through the opening *B*. As soon as this is expelled and steam strikes the strip *D*, the two prongs spring apart owing to the unequal expansion of the two metals due to the heat of the steam. This raises the spindle *C*, and closes the opening so that no steam can escape. If air should collect in the valve, and the metal strip become cool, it would contract, and the spindle would drop and allow the air to escape through *B* as before. *E* is an adjusting nut. *F* is a float attached to the spindle, and is supposed, in case of a sudden rush of water with the air, to rise and close the opening; this action, however, is somewhat uncertain, especially if the pressure of water continues for some time.



Fig. 43. Radiator Automatic Air-Valve. Operated by Metal Strip *D*, Consisting of Two Pieces of Metal of Unequal Expansive Power.

There are other types of valves acting on the same principle. The valve shown in Fig. 44 is closed by the expansion of a piece of vulcanite instead of a metal strip, and has no water float.

Fig. 44. Automatic Air-Valve. Closed by Expansion of a Piece of Vulcanite.



Fig. 45. Automatic Air-Valve. Operated by Expansion of Drum *C* Due to Vaporization of Alcohol with which it is Partly Filled.

The valve shown in Fig. 45 acts on a somewhat different principle. The float *C* is made of thin brass, closed at top and bottom, and is partially filled with wood alcohol. When steam strikes the float, the alcohol is vaporized, and creates a pressure sufficient to bulge out the ends slightly, which raises the spindle and closes the opening *B*.

Fig. 46 shows a form of so-called *vacuum valve*. It acts in a similar manner to those already described, but has in addition a ball check which prevents the air from being drawn into the radiator, should the steam go down and a vacuum be formed. If a partial vacuum exists in the boiler and radiators, the boiling point, and consequently the temperature of the steam, are lowered, and less heat is given off by the radiators. This method of operating a heating plant is sometimes advocated for spring and fall, when little heat is required, and when steam under pressure would overheat the rooms.



Fig. 46. Vacuum Valve.

Pipe Sizes. The proportioning of the steam pipes in a heating plant is of the greatest importance, and should be carefully worked out by methods which experience has proved to be correct. There are several ways of doing this; but for ordinary conditions, Tables XIV, XV, and XVI have given excellent results in actual practice. They have been computed from what is known as D'Arcy's formula, with suitable corrections made for actual working conditions. As the computations are somewhat complicated, only the results will be given here, with full directions for their proper use.

Table XIV gives the flow of steam in pounds per minute for pipes of different diameters and with varying drops in pressure between the supply and discharge ends of the pipe. These quantities are for pipes 100 feet in length; for other lengths the results must be corrected by the factors given in Table XVI. As the length of pipe increases, friction becomes greater, and the quantity of steam discharged in a given time is diminished.

Table XIV is computed on the assumption that the drop in

TABLE XIV

Flow of Steam in Pipes of Various Sizes, with Various Drops in Pressure between Supply and Discharge Ends

Calculated for 100-Foot Lengths of Pipe

Diam. of Pipe	Drop in Pressure (Pounds)								
	¼	½	¾	1	1½	2	3	4	5
1	.44	.63	.78	91	1.13	1.31	1.66	1.97	2.26
1¼	.81	1.16	1.43	1.66	2.05	2.39	3.02	3.59	4.12
1½	1.06	1.89	2.34	2.71	3.36	3.92	4.94	5.88	6.75
2	2.93	4.17	5.16	5.99	7.43	8.65	10.9	13.0	14.9
2½	5.29	7.52	9.32	10.8	13.4	15.6	19.7	23.4	26.9
3	8.61	12.3	15.2	17.6	21.8	25.4	32	31.8	43.7
3½	12.9	18.3	22.6	26.3	32.5	37.9	47.8	56.9	65.3
4	18 1	25.7	31.8	36.9	45.8	53.3	67.2	80.1	91.9
5	32.2	45.7	56.6	65.7	81.3	94.7	120	142	163
6	51.7	73.3	90.9	106	131	152	192	229	262
7	76.7	109	135	157	194	226	285	339	390
8	108	154	190	222	274	319	402	478	549
9	147	209	258	299	371	432	545	649	745
10	192	273	339	393	487	567	715	852	977
12	305	434	537	623	771	899	1,130	1,350	1,550
15	535	761	942	1,090	1,350	1,580	1,990	2,370	2,720

pressure between the two ends of the pipe equals the initial pressure. If the drop in pressure is less than the initial pressure, the actual discharge will be slightly greater than the quantities given in the table;

TABLE XV

Factors for Calculating Flow of Steam in Pipes under Initial Pressures above Five Pounds

To be used in connection with Table XIV

Drop in Pressure in Pounds	Initial Pressure (Pounds)					
	10	20	30	40	60	80
¼	1.27	1.49	1.68	1.84	2.13	2.38
½	1.26	1.48	1.66	1.83	2.11	2.36
1	1.24	1.46	1.64	1.80	2.08	2.32
2	1.21	1.41	1.59	1.75	2.02	2.26
3	1.17	1.37	1.55	1.70	1.97	2.20
4	1.14	1.34	1.51	1.66	1.92	2.14
5	1.12	1.31	1.47	1.62	1.87	2.09

but this difference will be small for pressures up to 5 pounds, and may be neglected, as it is on the side of safety. For higher initial pressures, Table XV has been prepared. This is to be used in connection with Table XIV as follows: First find from Table XIV the quantity of steam which will be discharged through the given diameter of pipe

TABLE XVI

Factors for Calculating Flow of Steam in Pipes of Other Lengths than 100 Feet

Feet	Factor	Feet	Factor	Feet	Factor	Feet	Factor
10	3.16	120	.91	275	.60	600	.40
20	2.24	130	.87	300	.57	650	.39
30	1.82	140	.84	325	.55	700	.37
40	1.58	150	.81	350	.53	750	.36
50	1.41	160	.79	375	.51	800	.35
60	1.29	170	.76	400	.50	850	.34
70	1.20	180	.74	425	.48	900	.33
80	1.12	190	.72	450	.47	950	.32
90	1.05	200	.70	475	.46	1,000	.31
100	1.00	225	.66	500	.45		
110	.95	250	.63	550	.42		

with the assumed drop in pressure; then look in Table XV for the factor corresponding with the assumed drop and the higher initial pressure to be used. The quantity given in Table XIV, *multiplied by* this factor, will give the actual capacity of the pipe under the given conditions.

Example—What weight of steam will be discharged through a 3-inch pipe 100 feet long, with an initial pressure of 60 pounds and a drop of 2 pounds?

Looking in Table XIV, we find that a 3-inch pipe will discharge 25.4 pounds of steam per minute with a 2-pound drop. Then looking in Table XV, we find the factor corresponding to 60 pounds initial pressure and a drop of 2 pounds to be 2.02. Then according to the rule given, $25.4 \times 2.02 = 51.3$ pounds, which is the capacity of a 3-inch pipe under the assumed conditions.

Sometimes the problem will be presented in the following way: What size of pipe will be required to deliver 80 pounds of steam a distance of 100 feet with an initial pressure of 40 pounds and a drop of 3 pounds?

We have seen that the higher the initial pressure with a given drop, the greater will be the quantity of steam discharged; therefore a smaller pipe will be required to deliver 80 pounds of steam at 40 pounds than at 3 pounds initial pressure From Table XV, we find that a given pipe will discharge 1.7 times as much steam per minute with a pressure of 40 pounds and a drop of 3 pounds, as it would with a pressure of 3 pounds, dropping to zero. From this it is evident that if we divide 80 by 1.7 and look in Table XIV under "3 pounds

drop" for the result thus obtained, the size of pipe corresponding will be that required. Now, $80 \div 1.7 = 47$. The nearest number in the table marked "3 pounds drop" is 47.8, which corresponds to a 3½-inch pipe, which is the size required.

These conditions will seldom be met with in low-pressure heating, but apply more particularly to combination power and heating plants, and will be taken up more fully under that head. For lengths of pipe other than 100 feet, multiply the quantities given in Table XIV by the factors found in Table XVI.

Example—What weight of steam will be discharged per minute through a 3½-inch pipe 450 feet long, with a pressure of 5 pounds and a drop of ¼ pound?

Table XIV, which may be used for all pressures below 10 pounds, gives for a 3½-inch pipe 100 feet long, a capacity of 18.3 pounds for the above conditions. Looking in Table XVI, we find the correction factor for 450 feet to be .47. Then $18.3 \times .47 = 8.6$ pounds, the quantity of steam which will be discharged if the pipe is 450 feet long.

Examples involving the use of Tables XIV, XV, and XVI in combination, are quite common in practice. The following example will show the method of calculation:

What size of pipe will be required to deliver 90 pounds of steam per minute a distance of 800 feet, with an initial pressure of 80 pounds and a drop of 5 pounds?

Table XVI gives the factor for 800 feet as .35, and Table XV, that for 80 pounds pressure and 5 pounds drop, as 2.09. Then $\frac{90}{.35 \times 2.09} = 123$, which is the equivalent quantity we must look for in Table XIV. We find that a 4-inch pipe will discharge 91.9 pounds, and a 5-inch pipe 163 pounds. A 4½-inch pipe is not commonly carried in stock, and we should probably use a 5-inch in this case, unless it was decided to use a 4-inch and allow a slightly greater drop in pressure. In ordinary heating work, with pressures varying from 2 to 5 pounds, a drop of ¼ pound in 100 feet has been found to give satisfactory results.

In computing the pipe sizes for a heating system by the above methods, it would be a long process to work out the size of each branch separately. Accordingly Table XVII has been prepared for ready use in low-pressure work.

As most direct heating systems, and especially those in schoolhouses, are made up of both radiators and circulation coils, an efficiency of 300 B. T. U. has been taken for direct radiation of whatever variety, no distinction being made between the different kinds. This gives a slightly larger pipe than is necessary for cast-iron radiators; but it is probably offset by bends in the pipes, and in any case gives a slight factor of safety. We find from a steam table that the *latent heat* of steam at 20 pounds above a vacuum (which corresponds to 5 pounds' gauge-pressure) is 954 + B. T. U.—which means that, for every pound of steam condensed in a radiator, 954 B. T. U. are given off for warming the air of the room. If a radiator has an efficiency of 300 B. T. U., then each square foot of surface will condense 300 ÷ 954 = .314 pound of steam per hour; so that we may assume in round numbers a condensation of $\frac{1}{3}$ of a pound of steam per hour for each square foot of direct radiation, when computing the sizes of steam pipes in low-pressure heating. Table XVII has been calculated on this assumption, and gives the square feet of heating surface

TABLE XVII

Heating Surface Supplied by Pipes of Various Sizes

Length of Pipe, 100 Feet

Size of Pipe	Square Feet of Heating Surface	
	¼ Pound Drop	½ Pound Drop
1	80	114
1¼	145	210
1½	190	340
2	525	750
2½	950	1,350
3	1,550	2,210
3½	2,320	3,290
4	3,250	4,620
5	5,800	8,220
6	9,320	13,200
7	13,800	19,620
8	19,440	27,720

which different sizes of pipe will supply, with drops in pressure of ¼ and ½ pounds in each 100 feet of pipe. The former should be used for pressures from 1 to 5 pounds, and the latter may be used for pressures over 5 pounds, under ordinary conditions. The sizes of long mains and special pipes of large size should be proportioned directly from Tables XIV, XV, and XVI.



CONE EXHAUST FAN, INLET SIDE.
American Blower Co.

Where the two-pipe system is used and the radiators have separate supply and return pipes, the risers or vertical pipes may be taken from Table XVII; but if the single-pipe system is used, the risers must be increased in size, as the steam and water are flowing in opposite directions and must have plenty of room to pass each other. It is customary in this case to base the computation on the velocity of the steam in the pipes, rather than on the drop in pressure. Assuming, as before, a condensation of one-third of a pound of steam per hour per square foot of radiation, Tables XVIII and XIX have been prepared for velocities of 10 and 15 feet per second. The sizes given in Table XIX have been found sufficient in most cases; but the larger sizes, based on a flow of 10 feet per second, give greater safety and should be more generally used. The size of the largest riser should usually be limited to $2\frac{1}{2}$ inches in school and dwelling-house work, unless it is a special pipe carried up in a concealed position. If the length of riser is short between the lowest radiator and the main, a higher velocity of 20 feet or more may be allowed through this portion, rather than make the pipe excessively large.

TABLE XVIII **TABLE XIX**

Radiating Surface Supplied by Steam Risers

10 Feet per Second Velocity		15 Feet per Second Velocity	
Size of Pipe	Sq. Feet of Radiation	Size of Pipe	Sq. Feet of Radiation
1 in.	30	1 in.	50
$1\frac{1}{4}$ "	60	$1\frac{1}{4}$ "	90
$1\frac{1}{2}$ "	80	$1\frac{1}{2}$ "	120
2 "	130	2 "	200
$2\frac{1}{2}$ "	190	$2\frac{1}{2}$ "	290
3 "	290	3 "	340
$3\frac{1}{2}$ "	390	$3\frac{1}{2}$ "	590

EXAMPLES FOR PRACTICE

1. How many pounds of steam will be delivered per minute, through a $3\frac{1}{2}$-inch pipe 600 feet long, with an initial pressure of 5 pounds and a drop of $\frac{1}{2}$ pound? Ans. 7.32 pounds.

2. What size pipe will be required to deliver 25.52 pounds of steam per minute with an initial pressure of 3 pounds and a drop of $\frac{1}{4}$ pound, the length of the pipe being 50 feet? Ans. 4-inch.

3. Compute the size of pipe required to supply 10,000 square feet of direct radiation (assume $\frac{1}{3}$ of a pound of steam per square

foot per hour) where the distance to the boiler house is 300 feet, and the pressure carried is 10 pounds, allowing a drop in pressure of 4 pounds. Ans. 5-inch (this is slightly larger than is required, while a 4-inch is much too small).

TABLE XX

Sizes of Returns for Steam Pipes (in Inches)

Diameter of Steam Pipe	Diameter of Dry Return	Diameter of Sealed Return
1	1	$\frac{3}{4}$
$1\frac{1}{4}$	1	1
$1\frac{1}{2}$	$1\frac{1}{4}$	1
2	$1\frac{1}{2}$	$1\frac{1}{4}$
$2\frac{1}{2}$	2	$1\frac{1}{2}$
3	$2\frac{1}{2}$	2
$3\frac{1}{2}$	$2\frac{1}{2}$	2
4	3	$2\frac{1}{2}$
5	3	$2\frac{1}{2}$
6	$3\frac{1}{2}$	3
7	$3\frac{1}{2}$	3
8	4	$3\frac{1}{2}$
9	5	$3\frac{1}{2}$
10	5	4
12	6	5

Returns. The size of return pipes is usually a matter of custom and judgment rather than computation. It is a common rule among steamfitters to make the returns one size smaller than the corresponding steam pipes. This is a good rule for the smaller sizes, but gives a larger return than is necessary for the larger sizes of pipe. Table XX gives different sizes of steam pipes with the corresponding diameters for dry and sealed returns.

TABLE XXI

Pipe Sizes for Radiator Connections

Square Feet of Radiation		Steam	Return
Two-Pipe	10 to 30	$\frac{3}{4}$ inch	$\frac{3}{4}$ inch
	30 to 48	1 "	$\frac{3}{4}$ "
	48 to 96	$1\frac{1}{4}$ "	1 "
	96 to 150	$1\frac{1}{2}$ "	$1\frac{1}{4}$ "
Single-Pipe	10 to 24	1 inch	
	24 to 60	$1\frac{1}{4}$ "	
	60 to 80	$1\frac{1}{2}$ "	
	80 to 130	2 "	

The length of run and number of turns in a return pipe should be noted, and any unusual conditions provided for. Where the condensation is discharged through a trap into a lower pressure, the sizes given may be slightly reduced, especially among the larger sizes, depending upon the differences in pressure.

Radiators are usually tapped for pipe connections as shown in Table XXI, and these sizes may be used for the connections with the mains or risers.



Fig 47. Good Position for Shut-Off Valve.

Boiler Connections. The steam main should be connected to the rear nozzle, if a tubular boiler is used, as the boiling of the water is less violent at this point and dryer steam will be obtained. The shut-off valve should be placed in such a position that pockets for the accumulation of condensation will be avoided. Fig. 47 shows a good position for the valve.

The size of steam connection may be computed by means of the methods already given, if desired. But for convenience the sizes given in Table XXII may be used with satisfactory results for the short runs between the boilers and main header.

TABLE XXII

Pipe Sizes from Boiler to Main Header

Diameter of Boiler	Size of Steam Pipe
36 inches	3 inches
42 "	4 "
48 "	4 "
54 "	5 "
60 "	5 "
66 "	6 "
72 "	6 "

The return connection is made through the blow-off pipe, and should be arranged so that the boiler can be blown off without draining the returns. A check-valve should be placed in the main return, and a plug-cock in the blow-off pipe. Fig. 48 shows in plan a good arrangement for these connections.

The feed connections, with the exception of that part exposed in the smoke-bonnet, are always made of brass in the best class of work. The small section referred to should be of extra heavy wrought



Fig. 48. A Good Arrangement of Return and Blow-Off Connections.

iron. The branch to each boiler should be provided with a gate or globe valve and a check-valve, the former being placed next to the boiler.

Table XXIII gives suitable sizes for return, blow-off, and feed pipes for boilers of different diameters.

TABLE XXIII

Sizes for Return, Blow-Off, and Feed Pipes

Diameter of Boiler	Size of Pipe for Gravity Return	Size of Blow-Off Pipe	Size of Feed Pipe
36 inches	1½ inches	1¼ inches	1 inch
42 "	2 "	1½ "	1 "
48 "	2 "	1½ "	1 "
54 "	2½ "	2 "	1¼ "
60 "	2½ "	2 "	1¼ "
66 "	3 "	2½ "	1½ "
72 "	3 "	2½ "	1½ "

Blow-Off Tank. Where the blow-off pipe connects with a sewer, some means must be provided for cooling the water, or the expansion and contraction caused by the hot water flowing through the drain-pipes will start the joints and cause leaks. For this reason it is customary to pass the water through a blow-off tank. A form of wrought-iron tank is shown in Fig. 49. It consists of a receiver supported on cast-iron cradles. The tank ordinarily stands nearly full of cold water.

The pipe from the boiler enters above the water-line, and the sewer connection leads from near the bottom, as shown. A vapor pipe is carried from the top of the tank above the roof of the building. When water from the boiler is blown into the tank, cold water from

the bottom flows into the sewer, and the steam is carried off through the vapor pipe. The equalizing pipe is to prevent any siphon action which might draw the water out of the tank after a flow is once started. As only a part of the water is blown out of a boiler at one time, the blow-off tank can be of a comparatively small size. A tank 24 by 48 inches should be large enough for boilers up to 48 inches in diameter;



Fig. 49. Connections of Blow-Off Tank.

and one 36 by 72 inches should care for a boiler 72 inches in diameter. If smaller quantities of water are blown off at one time, smaller tanks can be used. The sizes given above are sufficient for batteries of 2 or more boilers, as one boiler can be blown off and the water allowed to cool before a second one is blown off. Cast-iron tanks are often used in place of wrought-iron, and these may be sunk in the ground if desired.



Cast Iron Seamless Tubular Steam Heater.

HEATING AND VENTILATION

PART II

INDIRECT STEAM HEATING

As already stated, in the indirect method of steam heating, a special form of heater is placed beneath the floor, and encased in galvanized iron or in brickwork. A cold-air box is connected with the space beneath the heater; and warm-air pipes at the top are connected with registers in the floors or walls as already described for furnaces. A separate heater may be provided for each register if the rooms are large, or two or more registers may be connected with the same heater if the horizontal runs of pipe are short. Fig. 50 shows a section through a heater arranged for introducing hot air into a room through a floor register; and Fig. 51 shows the same type of heater connected with a wall register. The cold-air box is seen at the bottom of the casing; and the air, in passing through the spaces between the sections of the heater, becomes warmed, and rises to the rooms above.

Different forms of indirect heaters are shown in Figs. 52 and 53. Several sections connected in a single group are called a *stack*. Sometimes the stacks are encased in brickwork built up from the basement floor, instead of in galvanized iron as shown in the cuts. This method of heating provides fresh air for ventilation, and for this reason is especially adapted for schoolhouses, hospitals, churches, etc. As compared with furnace heating, it has the advantage of being less affected by outside wind-pressure, as long runs of horizontal pipe



Fig. 50. Steam Heater Placed under Floor Register —Indirect System.

are avoided and the heaters can be placed near the registers. In a large building where several furnaces would be required, a single boiler can be used, and the number of stacks increased to suit the existing conditions, thus making it necessary to run but a single fire. Another advantage is the large ratio between the heating and grate surface as compared with a furnace; and as a result, a large quantity of air is warmed to a moderate temperature, in place of a smaller quantity heated to a much higher temperature. This gives a more agreeable quality to the air, and renders it less dry. Direct and indirect systems are often combined, thus providing the living rooms with ventilation, while the hallways, corridors, etc., have only direct radiators for warming.



Fig. 51. Steam Heater Connected to Wall Register.—Indirect System.

Types of Heaters. Various forms of indirect radiators are shown in Figs. 52, 53, 54, and 56. A hot-water radiator may be used for steam; but a steam radiator cannot always be used for hot water, as



Fig. 52. One Form of Indirect Steam or Hot-Water Heater.

it must be especially designed to produce a continuous flow of water through it from top to bottom. Figs. 54 and 55 show the outside and the interior construction of a common pattern of indirect radiator

designed especially for steam. The arrows in Fig. 55 indicate the path of the steam through the radiator, which is supplied at the right, while the return connection is at the left. The air-valve in this case should be connected in the end of the last section near the return.



Fig. 53. Another Form of Indirect Steam or Hot-Water Heater.

A very efficient form of radiator, and one that is especially adapted to the warming of large volumes of air, as in schoolhouse work, is shown in Fig. 56, and is known as the *School pin* radiator. This can



Fig. 54. Exterior View of a Common Type of Radiator for Indirect-Steam Heating.

be used for either steam or hot water, as there is a continuous passage downward from the supply connection at the top to the return at the bottom. These sections or slabs are made up in stacks after the



Fig. 55. Interior Mechanism of Radiator Shown in Fig. 54.

manner shown in Fig. 57, which represents an end view of several sections connected together with special nipples.

A very efficient form of indirect heater may be made up of wrought-iron pipe joined together with branch tees and return bends.

A heater like that shown in Fig. 58 is known as a *box coil.* Its efficiency is increased if the pipes are *staggered*—that is, if the pipes in alternate rows are placed over the spaces between those in the row below.

Efficiency of Heaters. The efficiency of an indirect heater



Fig. 56. "School Pin" Radiator, Especially Adapted for Warming Large Volumes of Air by Either Steam or Hot Water.

depends upon its form, the difference in temperature between the steam and the surrounding air, and the velocity with which the air passes over the heater. Under ordinary conditions in dwelling-house work, a good form of indirect radiator will give off about 2 B. T. U. per square foot per hour for each degree difference in temperature between the steam and the entering air. Assuming a steam pressure of 2 pounds and an outside temperature of zero, we should have a difference in temperature of about 220 degrees, which, under the conditions stated, would give an efficiency of $220 \times 2 = 440$ B. T. U. per hour for each square foot of radiation. By making a similar computation for 10 degrees below zero, we find the efficiency to be 460. In the same manner we may calculate the efficiency for varying conditions of steam pressure and outside temperature. In the case of schoolhouses and similar buildings where large volumes of air are warmed to a moderate tem-



Fig. 57. End View of Several "School Pin" Radiator Sections Connected Together.

perature, a somewhat higher efficiency is obtained, owing to the increased velocity of the air over the heaters. Where efficiencies of 440 and 460 are used for dwellings, we may substitute 600 and 620 for schoolhouses. This corresponds approximately to 2.7 B. T. U. per square foot per hour for a difference of 1 degree between the air and steam.

The principles involved in indirect steam heating are similar to those already described in furnace heating. Part of the heat given off by the radiator must be used in warming up the air-supply to the temperature of the room, and part for offsetting the loss by conduction through walls and windows. The method of computing the heating surface required, depends upon the volume of air to be supplied to the room. In the case of a schoolroom or hall, where the air quantity



Fig. 58. "Box Coil," Built Up of Wrought-Iron Pipe, for Indirect-Steam Heating.

is large as compared with the exposed wall and window surface, we should proceed as follows:

First compute the B. T. U. required for loss by conduction through walls and windows; and to this, add the B. T. U. required for the necessary ventilation; and divide the sum by the efficiency of the radiators. An example will make this clear.

Example. How many square feet of indirect radiation will be required to warm and ventilate a schoolroom in zero weather, where the heat loss by conduction through walls and windows is 36,000 B. T. U., and the air-supply is 100,000 cubic feet per hour?

By the methods given under "Heat for Ventilation," we have

$$\frac{100{,}000}{55} \times 70 \times 127{,}272 = \text{B. T. U. required for ventilation.}$$

$$36{,}000 + 127{,}272 = 163{,}272 \text{ B. T. U.} = \text{Total heat required.}$$

This in turn divided by 600 (the efficiency of indirect radiators under these conditions) gives 272 square feet of surface required.

In the case of a dwelling-house the conditions are somewhat changed, for a room having a comparatively large exposure will have perhaps only 2 or 3 occupants, so that, if the small air-quantity necessary in this case were used to convey the required amount of heat to the room, it would have to be raised to an excessively high temperature. It has been found by experience that the radiating surface necessary for indirect heating is about 50 per cent greater than that required for direct heating. So for this work we may compute the surface required for direct radiation, and multiply the result by 1.5.

Buildings like hospitals are in a class between dwellings and schoolhouses. The air-supply is based on the number of occupants, as in schools, but other conditions conform more nearly to dwelling-houses.

To obtain the radiating surface for buildings of this class, we compute the total heat required for warming and ventilation as in the case of schoolhouses, and divide the sum by the efficiencies given for dwellings—that is, 440 for zero weather, and 460 for 10 degrees below.

Example. A hospital ward requires 50,000 cubic feet of air per hour for ventilation; and the heat loss by conduction through walls, etc., is 100,000 B. T. U. per hour. How many square feet of indirect radiation will be required to warm the ward in zero weather?

$50{,}000 \times 70 \div 55 = 63{,}636$ B. T. U. for ventilation; then,

$$\frac{63{,}636 + 100{,}000}{440} = 372 + \text{square feet.}$$

EXAMPLES FOR PRACTICE

1. A schoolroom having 40 pupils is to be warmed and ventilated when it is 10 degrees below zero. If the heat loss by conduction is 30,000 B. T. U. per hour, and the air supply is to be 40 cubic feet per minute per pupil, how many square feet of indirect radiation will be required? ANS. 273.

2. A contagious ward in a hospital has 10 beds, requiring 6,000 cubic feet of air each, per hour. The heat loss by conduction in zero weather is 80,000 B. T. U. How many square feet of indirect radiation will be required? ANS. 355.

3. The heat loss from a sitting room is 11,250 B. T. U. per hour in zero weather. How many square feet of indirect radiation will be required to warm it? ANS. 75.

Stacks and Casings. It has already been stated that a group of sections connected together is called a stack, and examples of these with their casings are shown in Figs. 50 and 51. The casings are usually made of galvanized iron, and are made up in sections by means of small bolts so that they may be taken apart in case it is necessary to make repairs. Large stacks are often enclosed in brick-work, the sides consisting of 8-inch walls, and the top being covered over with a layer of brick and mortar supported on light wrought-iron tee-bars. Blocks of asbestos are sometimes used for covering, instead of brick, the whole being covered over with plastic material of the same kind.

Where a single stack supplies several flues or registers, the connections between these and the warm-air chamber are made in the same manner as already described for furnace heating. When galvanized-iron casings are used, the heater is supported by hangers from the floor above. Fig. 59 shows the method of hanging a heater from a wooden floor. If the floor is of fireproof construction, the hangers may pass up through the brick-work, and the ends be provided with nuts and large washers or plates; or they may be clamped to the iron beams which carry the floor. Where brick casings are used, the heaters are supported upon pieces of pipe or light I-beams built into the walls.



Fig. 59. Method of Hanging a Heater below a Wooden Floor.

The warm-air space above the heater should never be less than 8 inches, while 12 inches is preferable for heaters of large size. The cold-air space may be an inch or two less; but if there is plenty of room, it is good practice to make it the same as the space above.

Dampers. The general arrangement of a galvanized-iron casing and mixing damper is shown in Fig. 60. The cold-air duct is brought along the basement ceiling from the inlet window, and connects with the cold-air chamber beneath the heater. The entering air passes up between the sections, and rises through the register above, as shown by the arrows. When the mixing damper is in its lowest position, all air reaching the register must pass through the heater; but if the

damper is raised to the position shown, part of the air will pass by without going through the heater, and the mixture entering through the register will be at a lower temperature than before. By changing



Fig. 60. General Arrangement of a Galvanized-Iron Casing and Mixing Damper Damper between Heater and Register.

the position of the damper, the proportions of warm and cold air delivered to the room can be varied, thus regulating the temperature without diminishing to any great extent the quantity of air delivered



Fig. 61. Heater and Mixing Damper with Brick Casing. Damper between Heater and Register.

The objection to this form of damper is that there is a tendency for the air to enter the room before it is thoroughly mixed; that is, a stream of warm air will rise through one half of the register while

cold air enters through the other. This is especially true if the connection between the damper and register is short. Fig. 61 shows a similar heater and mixing damper, with brick casing. Cold air is admitted to the large chamber below the heater, and rises through the sections to the register as before. The action of the mixing damper is the same as already described. Several flues or registers may be connected with a stack of this form, each connection having, in addition to its mixing damper, an adjusting damper for regulating the flow of air to the different rooms.

Another way of proportioning the air-flow in cases of this kind is to divide the hot-air chamber above the heater into sections, by means of galvanized-iron partitions, giving to each room its proper share of heating surface. If the cold-air supply is made sufficiently large, this arrangement is preferable to using adjusting dampers as



Fig. 62. Another Arrangement of Mixing Damper and Heater in Galvanized-Iron Casing. Heater between Damper and Register.

described above. The partitions should be carried down the full depth of the heater between the sections, to secure the best results.

The arrangement shown in Fig. 62 is somewhat different, and overcomes the objection noted in connection with Fig. 60, by substituting another. The mixing damper in this case is placed at the other end of the heater. When it is in its highest position, all of the air must pass through the heater before reaching the register; but when partially lowered, a part of the air passes over the heater, and the result is a mixture of cold and warm air, in proportions depending upon the position of the damper. As the layer of warm air in this case is below the cold air, it tends to rise through it, and a more thorough mixture is obtained than is possible with the damper shown in Fig. 60. One quite serious objection, however, to this form of damper, is illustrated in Fig. 63. When the damper is nearly

closed so that the greater part of the air enters above the heater, it has a tendency to fall between the sections, as shown by the arrows, and, becoming heated, rises again, so that it is impossible to deliver air to a room below a certain temperature. This peculiar action increases as the quantity of air admitted below the heater is diminished. When the inlet register is placed in the wall at some distance above the floor, as in schoolhouse work, a thorough mixture of air can be obtained by placing the heater so that the current of warm air will pass up the front of the flue and be discharged into the room through the lower part of the register. This is shown quite clearly in Fig. 64, where the current of warm air is represented by crooked arrows, and the cold air by straight arrows. The two currents pass up the flue separately; but as soon as they are discharged through the register the warm air tends to rise, and the cold air to fall, with the result of a more or less complete mixture, as shown.



Fig. 63. Showing Difficulty of Regulating Temperature with Arrangement in Fig. 62.



Fig. 64. Arrangement of Heater and Damper Causing Warm Air to Enter Room through Lower Part of Register, thus Securing Thorough Mixing



HOT WATER HEATER AND CONNECTIONS.

It is often desirable to warm a room at times when ventilation is not necessary, as in the case of living rooms during the night, or for quick warming in the morning. A register and damper for air rotation should be provided in this case. Fig. 65 shows an arrangement for this purpose. When the damper is in the position shown, air will be taken from the room above and be warmed over and over; but, by raising the damper, the supply will be taken from outside. Special care should be taken to make all mixing dampers tight against air-leakage, else their advantages will be lost. They should work easily and close tightly against flanges covered with felt. They may be operated from the rooms above by means of chains passing over



Fig. 65. Arrangement for Quick Heating without Ventilation. Damper Shuts off Fresh Air, and Air of Room Heated by Rotating Forth and Back through Register and Heater.

guide-pulleys; special attachments should be provided for holding in any desired position.

Warm-Air Flues. The required size of the warm-air flue between the heater and the register, depends first upon the difference in temperature between the air in the flue and that of the room, and second, upon the height of the flue. In dwelling-houses, where the conditions are practically constant, it is customary to allow 2 square inches area for each square foot of radiation when the room is on the first floor, and $1\frac{1}{2}$ square inches for the second and third floors. In the case of hospitals, where a greater volume of air is required, these figures may be increased to 3 square inches for the first floor wards, and 2 square inches for those on the upper floors.

In schoolhouse work, it is more usual to calculate the size of flue from an assumed velocity of air-flow through it. This will vary greatly according to the outside temperature and the prevailing wind conditions. The following figures may be taken as average velocities

obtained in practice, and may be used as a basis for calculating the required flue areas for the different stories of a school building:

1st floor, 280 feet per minute.
2nd " , 340 " " "
3rd " , 400 " " "

These velocities will be increased somewhat in cold and windy weather and will be reduced when the atmosphere is mild and damp.

Having assumed these velocities, and knowing the number of cubic feet of air to be delivered to the room per minute, we have only to divide this quanity by the assumed velocity, to obtain the required flue area in square feet.

Example. A schoolroom on the second floor is to have an air-supply of 2,000 cubic feet per minute. What will be the required flue area?

ANS. $2000 \div 340 = 5.8 +$ sq. feet.

The velocities would be higher in the coldest weather, and dampers should be placed in the flues for throttling the air-supply when necessary.

Cold-Air Ducts. The cold-air ducts supplying heaters should be planned in a manner similar to that described for furnace heating. The air-inlet should be on the north or west side of the building; but this of course is not always possible. The method of having a large trunk line or duct with inlets on two or more sides of the building, should be carried out when possible. A cold-air room with large inlet windows, and ducts connecting with the heaters, makes a good arrangement for schoolhouse work. The inlet windows in this case should be provided with check-valves to prevent any outward flow of air. A detail of this arrangement is shown in Fig. 66.

This consists of a boxing around the window, extending from the floor to the ceiling. The front is sloped as shown, and is closed from the ceiling to a point below the bottom of the window. The remainder is open, and covered with a wire netting of about $\frac{1}{2}$-inch mesh; to this are fastened flaps or checks of gossamer cloth about 6 inches in width. These are hemmed on both edges and a stout wire is run through the upper hem which is fastened to the netting by means of small copper or soft iron wire. The checks allow the air to flow inward but close when there is any tendency for the current to reverse.

The area of the cold-air duct for any heater should be about three-fourths the total area of the warm-air ducts leading from it.

If the duct is of any considerable length or contains sharp bends, it should be made the full size of all the warm-air ducts. Adjusting dampers should be placed in the supply duct to each separate stack. If a trunk with two inlets is used, each inlet should be of sufficient size to furnish the full amount of air required, and should be provided with cloth checks for preventing an outward flow of air, as already described. The inlet windows should be provided with some form of damper or slide, outside of which should be placed a wire grating, backed by a netting of about $\frac{3}{8}$-inch mesh.

Vent Flues. In dwelling-houses, vent flues are often omitted, and the frequent opening of doors and leakage are depended upon to carry away the impure air. A well-designed system of warming should provide some means for discharge ventilation, especially for bathrooms and toilet-rooms, and also for living rooms where lights are burned in the evening. Fireplaces are usually provided in the more important rooms of a well-built house, and these are made to serve as vent flues. In rooms having no fireplaces, special flues of tin or galvanized iron may be carried up in the partitions in the same manner as the warm-air flues. These should be gathered together in the attic, and connected with a brick flue running up beside the boiler or range chimney.



Fig. 66. Air-Inlet Provided with Check-Valves to Prevent Outward Flow of Air.

Very fair results may be obtained by simply letting the flues open into an unfinished attic, and depending upon leakage through the roof to carry away the foul air.

The sizes of flues may be made the reverse of the warm-air flues —that is, 1½ square inches area per square foot of indirect radiation for rooms on the first floor, and 2 square inches for those on the second. This is because the velocity of flow will depend upon the height of flue, and will therefore be greater from the first floor. The flow of air through the vents will be slow at best, unless some means is provided for warming the air in the flue to a temperature above that of the room with which it connects.

The method of carrying up the outboard discharge beside a warm chimney is usually sufficient in dwelling-houses; but when it is desired to move larger quantities of air, a loop of steam pipe should be run inside the flue. This should be connected for drainage and air-venting as shown in Fig. 67. When vents are carried through the roof independently, some form of protecting hood should be provided for keeping out the snow and rain. A simple form is shown in Fig. 68. Flues carried outboard in this way should always be extended well above the ridges of adjacent roofs to prevent down drafts in windy weather.



Fig. 67. Loop of Steam Pipe to be Run Inside Flue. Connected for Drainage and Air-Venting.

For schoolhouse work we may assume average velocities through the vent flues, as follows:

1st floor, 340 feet per minute.
2nd " , 280 " " "
3rd " , 220 " " "

Where flue sizes are based on these velocities, it is well to guard against down drafts by placing an aspirating coil in the flue. A single row of pipes across the flue as shown in Fig. 69, is usually sufficient for this purpose when the flues are large and straight;

otherwise, two rows should be provided. The slant height of the heater should be about twice the depth of the flue, so that the area between the pipes shall equal the free area of the flue.

Large vent flues of this kind should always be provided with dampers for closing at night, and for regulation during strong winds.

Sometimes it is desired to move a given quantity of air through a flue which is already in place. Table XXIV shows what velocities may be obtained through flues of different heights, for varying differences in temperature between the outside air and that in the flue.



Fig. 68. Section Showing Simple Form of Protecting Hood for Vent Carried through Roof.

Example.—It is desired to discharge 1,300 cubic feet of air per minute through a flue having an area of 4 square feet and a height of 30 feet. If the efficiency of an aspirating coil is 400 B. T. U., how many square feet of surface will be required to move this amount of air when the temperature of the room is 70° and the outside temperature is 60°?



Fig. 69. Aspirating Coil Placed in Flue to Prevent Down Drafts.

1,300 ÷ 4 = 325 feet per minute = Velocity through the flue. Looking in Table XXIV, and following along the line opposite a 30-foot flue, we find that to obtain this velocity there must be a difference of 30 degrees between the air in the flue and the external air.

If the outside temperature is 60 degrees, then the air in the flue must be raised to 60 + 30 = 90 degrees. The air of the room being at 70 degrees, a rise of 20 degrees is necessary. So the problem resolves itself into the following: What amount of heating surface having an

TABLE XXIV

Air-Flow through Flues of Various Heights under Varying Conditions of Temperature

(Volumes given in cubic feet per square foot of sectional area of flue)

Height of Flue in Feet	Excess of Temperature of Air in Flue Above that of External Air					
	5°	10°	15°	20°	30°	50°
5	55	76	94	109	134	167
10	77	108	133	153	188	242
15	94	133	162	188	230	297
20	108	153	188	217	265	342
25	121	171	210	242	297	383
30	133	188	230	265	325	419
35	143	203	248	286	351	453
40	153	217	265	306	375	484
45	162	230	282	325	398	514
50	171	242	297	342	419	541
60	188	264	325	373	461	594

efficiency of 400 B. T. U. is necessary to raise 1,300 cubic feet of air per minute through 20 degrees?

1,300 cubic feet per minute = 1,300 × 60 = 78,000 per hour; and making use of our formula for "heat for ventilation," we have

$$\frac{78{,}000 \times 20}{55} = 28{,}363 \text{ B. T. U.};$$

and this divided by 400 = 71 square feet of heating surface required.

EXAMPLES FOR PRACTICE

1. A schoolroom on the third floor has 50 pupils, who are to be furnished with 30 cubic feet of air per minute each. What will be the required areas in square feet of the supply and vent flues?

Ans. Supply, 3.7 +. Vent, 6.8 +.

2. What size of heater will be required in a vent flue 40 feet high and with an area of 5 square feet, to enable it to discharge 1,530 cubic feet per minute, when the outside temperature is 60°? (Assume an efficiency of 400 B. T. U. for the heater.) Ans. 41.7 square feet.

Registers. Registers are made of cast iron and bronze, in a great variety of sizes and patterns. The almost universal finish for cast-iron registers is black "Japan;" but they are also finished in colors and electroplated with copper and nickel. Fig. 70 shows a section through a floor register, in which *A* represents the valves, which may be turned in a vertical or horizontal position, thus opening or closing the register; *B* is the iron border; *C*, the register box of tin or galvanized iron; and *D*, the warm-air pipe. Floor registers are usually set in cast-iron borders, one of which is shown in Fig. 71; while wall registers may be screwed directly to wooden borders or frames to correspond with the finish of the room. Wall registers should be provided with pull-cords for opening and closing from the floor; these are shown in Fig. 72. The plain lattice pattern shown in Fig. 73 is the best for schoolhouse work, as it has a comparatively free opening for air-flow and is pleasing and simple in design. More elaborate patterns are used for fine dwelling-house work. Registers with shut-off valves are used for air-inlets, while the plain register faces without the valves are placed in the vent openings. The vent flues are usually gathered together in the attic, and a single damper may be used to shut off the whole number at once. Flat or round wire gratings of open pattern are often used in place of



Fig. 70. Section through a Floor Register.


Fig. 71. Cast-Iron Border for a Floor Register.

register faces. The grill or solid part of a register face usually takes up about ⅓ of the area; hence in computing the size, we must allow for this by multiplying the required "net area" by 1.5, to obtain the "total" or "over-all" area.

Example. Suppose we have a flue 10 inches in width and wish to use a register having a free area of 200 square inches. What will be the required height of the register?

200 × 1.5 = 300 square inches, which is the total area required; then 300 ÷ 10 = 30, which is the required height, and we should use a 10 by 30-inch register. When a register is spoken of as a 10 by



Fig. 72. Wall Register with Pull Cords for Opening and Closing.



Fig. 73. Plain Lattice Pattern Register. Best for Schoolhouse Work.

30-inch or a 10 by 20-inch, etc., the dimensions of the latticed opening are meant, and not the outside dimensions of the whole register. The free opening should have the same area as the flue with which it connects. In designing new work, one should provide himself with a trade catalogue, and use only standard sizes, as special patterns and sizes are costly. Fig. 74 shows the method of placing gossamer check-valves back of the vent register faces to prevent down drafts, the same as described for fresh-air inlets.

Inlet registers in dwelling-house and similar work are placed either in the floor or in the baseboard; sometimes they are located under the windows, just above the baseboard. The object in view is to place them where the currents of air entering the room will not be objectionable to persons sitting near windows. A long, narrow floor-register placed close to the wall in front of a window, sends up a shallow current of warm air, which is not especially noticeable



Fig. 74. Method of Placing Gossamer Check-Valves back of Vent Register Face to Prevent Down Drafts.

to one sitting near it. Inlet registers are preferably placed near outside walls, especially in large rooms. Vent registers should be placed in inside walls, near the floor.

Pipe Connections. The two-pipe system with dry or sealed returns is used in indirect heating. The conditions to be met are practically the same as in direct heating, the only difference being that the radiators are at the basement ceiling instead of on the floors above. The exact method of making the pipe connections will depend somewhat upon existing conditions; but the general method shown in Fig. 75 may be used as a guide, with modifications to suit

any special case. The ends of all supply mains should be dripped, and the horizontal returns should be sealed if possible.

Pipe Sizes. The tables already given for the proportioning of pipe sizes can be used for indirect systems. The following table has been computed for an efficiency of 640 B. T. U. per square foot of surface per hour, which corresponds to a condensation of $\frac{2}{3}$ of a pound of steam. This is twice that allowed for direct radiation in Table



Fig. 75. General Method of Making Pipe and Radiator Connections, in Basement, in Indirect Heating.

XVII; so that we can consider 1 square foot of indirect surface as equal to 2 of direct in computing pipe sizes.

As the indirect heaters are placed in the basement, care must be taken that the bottom of the radiator does not come too near the water-line of the boiler, or the condensation will not flow back properly; this distance, under ordinary conditions, should not be less than 2 feet. If much less than this, the pipes should be made extra large, so that there may be little or no drop in pressure between the boiler

TABLE XXV

Indirect Radiating Surface Supplied by Pipes of Various Sizes

Size of Pipe	Square Feet of Indirect Radiation which will be Supplied with		
	¼ Pound Drop in 200 Feet	¼ Pound Drop in 100 Feet	½ Pound Drop in 100 Feet
1 in.	28	40	57
1¼ "	51	72	105
1½ "	67	95	170
2 "	185	262	375
2½ "	335	475	675
3 "	540	775	1, 105
3½ "	812	1, 160	1, 645
4 "	1, 140	1, 625	2, 310
5 "	2, 030	2, 900	4, 110
6 "	3, 260	4, 660	6, 600
7 "	4, 830	6, 900	9, 810
8 "	6, 800	9, 720	13, 860

and the heater. A drop in pressure of 1 pound would raise the water-line at the heater 2.4 feet.



Fig. 76. General Form of Direct-Indirect Radiator.



Fig. 77. Section through Radiator Shown in Fig. 76.

Direct-Indirect Radiators. A direct-indirect radiator is similar in form to a direct radiator, and is placed in a room in the same

manner. Fig. 76 shows the general form of this type of radiator; and Fig. 77 shows a section through the same. The shape of the sections is such, that when in place, small flues are formed between them. Air is admitted through an opening in the outside wall; and, in passing upward through these flues, becomes heated before entering the room. A switch-damper is placed in the duct at the base of the radiator, so that the air may be taken from the room itself instead of from out of doors, if so desired. This is shown more particularly in Fig. 76.

Fig. 78 shows the wall box provided with louvre slats and netting, through which the air is drawn. A damper door is placed at either end of the radiator base; and, if desired, when the cold-air supply is shut off by means of the register in the air-duct, the radiator can be converted into the ordinary type by opening both damper doors, thus taking the air from the room instead of from the outside. It is customary to increase the size of a direct-indirect radiator 30 per cent above that called for in the case of direct heating.



Fig. 78. Wall Box with Louvre Slats and Netting, Direct-Indirect System.

CARE AND MANAGEMENT OF STEAM-HEATING BOILERS

Special directions are usually supplied by the maker for each kind of boiler, or for those which are to be managed in any peculiar way. The following general directions apply to all makes, and may be used regardless of the type of boiler employed:

Before starting the fire, see that the boiler contains sufficient water. The water-line should be at about the center of the gauge-glass.

The smoke-pipe and chimney flue should be clean, and the draft good.

Build the fire in the usual way, using a quality of coal which is best adapted to the heater. In operating the fire, keep the firepot

full of coal, and shake down and remove all ashes and cinders as often as the state of the fire requires it.

Hot ashes or cinders must not be allowed to remain in the ashpit under the grate-bars, but must be removed at regular intervals to prevent burning out the grate.

To control the fire, see that the damper regulator is properly attached to the draft doors and the damper; then regulate the draft by weighting the automatic lever as may be required to obtain the necessary steam pressure for warming. Should the water in the boiler escape by means of a broken gauge-glass, or from any other cause, the fire should be dumped, and the boiler allowed to cool before adding cold water.

An empty boiler should never be filled when hot. If the water gets low at any time, but still shows in the gauge-glass, more water should be added by the means provided for this purpose.

The safety-valve should be lifted occasionally to see that it is in working order.

If the boiler is used in connection with a gravity system, it should be cleaned each year by filling with pure water and emptying through the blow-off. If it should become foul or dirty, it can be thoroughly cleansed by adding a few pounds of caustic soda, and allowing it to stand for a day, and then emptying and thoroughly rinsing.

During the summer months, it is recommended that the water be drawn off from the system, and that air-valves and safety-valves be opened to permit the heater to dry out and to remain so. Good results, however, are obtained by filling the heater full of water, driving off the air by boiling slowly, and allowing it to remain in this condition until needed in the fall. The water should then be drawn off and fresh water added.

The heating surface of the boiler should be kept clean and free from ashes and soot by means of a brush made especially for this purpose.

Should any of the rooms fail to heat, examine the steam valves in the radiators. If a two-pipe system, both valves at each radiator must be opened or closed at the same time, as required. See that the air-valves are in working condition.

If the building is to be unoccupied in cold weather, draw all the water out of the system by opening the blow-off pipe at the boiler and all steam valves and air-valves at the radiators.

HOT-WATER HEATERS

Types. Hot-water heaters differ from steam boilers principally in the omission of the reservoir or space for steam above the heating surface. The steam boiler might answer as a heater for hot water; but the large capacity left for the steam would tend to make its operation slow and rather unsatisfactory, although the same type of boiler is sometimes used for both steam and hot water. The passages in a hot-water heater need not extend so directly from bottom to top as in a steam boiler, since the problem of providing for the free liberation of the steam bubbles does not have to be considered. In general, the heat from the furnace should strike the surfaces in such a manner as to increase the natural circulation; this may be accomplished to a certain extent by arranging the heating surface so that a large proportion of the direct heat will be absorbed near the top of the heater. Practically the boilers for low-pressure steam and for hot water differ from each other very little as to the character of the heating surface, so that the methods already given for computing the size of grate surface, horse-power, etc., under the head of "Steam Boilers," can be



Fig. 79. Richardson Sectional Hot-Water Heater.

used with satisfactory results in the case of hot-water heaters.

It is sometimes stated that, owing to the greater difference in temperature between the furnace gases and the water in a hot-water heater, as compared with steam, the heating surface will be more efficient and a smaller heater can be used. While this is true to a certain extent, different authorities agree that this advantage is so small that no account should be taken of it, and the general proportions of the heater should be calculated in the same manner as for steam. Fig. 79 shows a form of hot-water heater made up of slabs or sections similar to the sectional steam boiler shown in Part I. The size can be increased in a similar manner, by adding more sections. In this case, however, the boiler is increased in width instead of in length. This has an advantage in the larger sizes, as a second fire door can be added, and all parts of the grate can be reached as well in the large sizes as in the small.

Fig. 80 shows a different form of sectional boiler, in which the sections are placed one above another. These boilers are circular in form and well adapted to dwelling-houses and similar work.



Fig. 80. "Invincible" Boiler, with Sections Superposed.
Courtesy of American Radiator Co.

Fig. 81 shows another type of cast-iron heater which is not made in sections. The space between the outer and inner shells surrounding the furnace is filled with water, and also the cross-pipes directly over the fire and the drum at the top. The supply to the radiators is taken off from the top of the heater, and the return connects at the lowest point.

The ordinary horizontal and vertical tubular boilers, with various modifications, are used to a considerable extent for hot-water heating,

and are well adapted to this class of work, especially in the case of large buildings.

Automatic regulators are often used for the purpose of maintaining a constant temperature of the water. They are constructed in different ways—some depend upon the expansion of a metal pipe or rod at different temperatures, and others upon the vaporization and consequent pressure of certain volatile liquids. These means are usually employed to open small valves which admit water-pressure under rubber diaphragms; and these in turn are connected by means of chains with the draft doors of the furnace, and so regulate the draft as required to maintain an even temperature of the water in the heater. Fig. 82 shows one of the first kind. *A* is a metal rod placed in the flow pipe from the heater, and is so connected with the valve *B* that when the water reaches a certain temperature the expansion of the rod opens the valve and admits water from the street pressure through the pipes *C* and *D* into the chamber *E*. The bottom of *E* consists of a rubber diaphragm, which is forced down by the water-pressure and carries with it the lever which operates the dampers as shown, and checks the fire. When the temperature of the water drops, the rod contracts and valve *B* closes, shutting off the pressure from the chamber *E*. A spring is provided to throw the lever back to its original position,



Fig. 81. Cast-Iron Heater Not Made in Sections. Water Fills Cross-Pipes and Space between Outer and Inner Shells.



DIRECT-INDIRECT METHOD OF WARMING TAKING A FRESH AIR SUPPLY FROM OUTSIDE AND PASSING IT UPWARD
American Radiator Company

and the water above the diaphragm is forced out through the pet-cock *G*, which is kept slightly open all the time.

DIRECT HOT-WATER HEATING

A hot-water system is similar in construction and operation to one designed for steam, except that *hot water* flows through the pipes and radiators instead.

The circulation through the pipes is produced solely by the difference in weight of the water in the supply and return, due to the difference in temperature. When water is heated it expands, and thus a given volume becomes lighter and tends to rise, and the cooler water flows in to take its place; if the application of heat is kept up, the circulation thus produced is continuous. The velocity of flow depends upon the difference in temperature between the supply and return, and the height of the radiator above the boiler. The horizontal distance of the radiator from the boiler is also an important factor affecting the velocity of flow.



Fig. 82. Hot-Water Heater with Automatic Regulator Operated through Expansion and Contraction of Metal Rod in Flow Pipe.

This action is best shown by means of a diagram, as in Fig. 83. If a glass tube of the form shown in the figure is filled with water and held in a vertical position, no movement of the water will be noticed, because the two columns *A* and *B* are of the same weight, and therefore in equilibrium. Now, if a lamp flame be held near the tube *A*, the small bubbles of steam which are formed will show the water to be in motion, with a current flowing in the direction indicated by the arrows. The reason for this is, that, as the water in *A* is heated,

it expands and becomes lighter for a given volume, and is forced upward by the heavier water in *B* falling to the bottom of the tube. The heated water flows from *A* through the connecting tube at the top, into *B*, where it takes the place of the cooler water which is settling to the bottom. If, now, the lamp be replaced by a furnace, and the columns *A* and *B* be connected at the top by inserting a radiator, the illustration will assume the practical form as utilized in hot-water heating (see Fig. 84).



Fig. 83. Illustrating How the Heating of Water Causes Circulation.

The heat given off by the radiator always insures a difference in temperature between the columns of water in the supply and return pipes, so that as long as heat is supplied by the furnace the flow of water will continue. The greater the difference in temperature of the water in the two pipes, the greater the difference in weight, and consequently the faster the flow. The greater the height of the radiator above the heater, the more rapid will be the circulation, because the total difference in weight between the water in the supply and return risers will vary directly with their height. From the above it is evident that the rapidity of flow depends chiefly upon the *temperature* difference between the supply and return, and upon the *height of the radiator* above the heater. Another factor which must be considered in long runs of horizontal pipe is the *frictional resistance.*



Fig. 84. Illustrating Simple Circulation in a Heating System.

Systems of Circulation. There are two distinct systems of circulation employed—one depending on the difference in temperature of the water in the supply and return pipes, called *gravity circulation*;

and another where a pump is used to force the water through the mains, called *forced circulation*. The former is used for dwellings and other buildings of ordinary size, and the latter for large buildings, and especially where there are long horizontal runs of pipe.

For gravity circulation some form of sectional cast-iron boiler is commonly used, although wrought-iron tubular boilers may be employed if desired. In the case of forced circulation, a heater designed to warm the water by means of live or exhaust steam is often used. A centrifugal or rotary pump is best adapted to this purpose, and may be driven by an electric motor or a steam engine, as most convenient.

Types of Radiating Surface. Cast-iron radiators and circulation coils are used for hot water as well as for steam. Hot-water radiators differ from steam radiators principally in having a horizontal passage at the top as well as at the bottom. This construction is necessary in order to draw off the air which gathers at the top of each loop or section. Otherwise they are the same as steam radiators, and are well adapted for the circulation of steam, and in some respects are superior to the ordinary pattern of steam radiator.



Fig. 85. Showing Construction of Radiator for Hot Water or Steam. Note Horizontal Passage along Top.

The form shown in Fig. 85 is made with an opening at the top for the entrance of water, and at the bottom for its discharge, thus insuring a supply of hot water at the top and of colder water at the bottom.

Some hot-water radiators are made with a cross-partition so arranged that all water entering passes at once to the top, from which it may take any passage toward the outlet. Fig. 86 is the more common form of radiator, and is made with continuous passages at top and bottom, the hot water being supplied at one side and drawn off at the other. The action of gravity is depended upon for making the hot and lighter water pass to the top, and the colder water sink

to the bottom and flow off through the return. Hot-water radiators are usually tapped and plugged so that the pipe connections can be made either at the top or at the bottom. This is shown in Fig. 87.

Wall radiators are adapted to hot-water as well as steam heating.

Efficiency of Radiators. The efficiency of a hot-water radiator depends entirely upon the temperature at which the water is circulated. The best practical results are obtained with the water leaving the boiler at a maximum temperature of about 180 degrees in zero weather and returning at about 160 degrees; this gives an average



Fig. 86. Common Form of Hot-Water Radiator. Circulation Produced Wholly through Action of Gravity, Hot Water Rising to Top.



Fig. 87. End Elevation of Radiator Showing Taps at Top and Bottom for Pipe Connections.

temperature of 170 degrees in the radiators. Variations may be made, however, to suit the existing conditions of outside temperature. We have seen that an average cast-iron radiator gives off about 1.7 B.T.U. per hour per square foot of surface per degree difference in temperature between the radiator and the surrounding air, when working under ordinary conditions; and this holds true whether it is filled with steam or water.

If we assume an average temperature of 170 degrees for the water, then the difference in temperature between the radiator and the air will be 170 — 70 = 100 degrees; and this multiplied by 1.7 =

170, which may be taken as the efficiency of a hot-water radiator under the above average conditions.

This calls for a water radiator about 1.5 times as large as a steam radiator to heat a given room under the same conditions. This is common practice although some engineers multiply by the factor 1.6, which allows for a lower temperature of the water. Water leaving the boiler at 170 degrees should return at about 150; the drop in temperature should not ordinarily exceed 20 degrees.

Systems of Piping. A system of hot-water heating should produce a perfect circulation of water from the heater to the radiating



Fig. 88. System of Piping Usually Employed for Hot-Water Heating.

surface, and thence back to the heater through the returns. The system of piping usually employed for hot-water heating is shown in Fig. 88. In this arrangement the main and branches have an inclination upward from the heater; the returns are parallel to the mains, and have an inclination downward toward the heater, connecting with it at the lowest point. The flow pipes or risers are taken from the tops of the mains, and may supply one or more radiators as required. The return risers or drops are connected with the return mains in a similar manner. In this system great care must be taken to produce a nearly equal resistance to flow in all of the branches, so that each radiator may receive its full supply of water. It will always

be found that the principal current of heated water will take the path of least resistance, and that a small obstruction or irregularity in the piping is sufficient to interfere greatly with the amount of heat received in the different parts of the same system.

Some engineers prefer to carry a single supply main around the building, of sufficient size to supply all the radiators, bringing back a single return of the same size. Practice has shown that in general it is not well to use pipes over 8 or 10 inches in diameter; if larger pipes are required, it is better to run two or more branches.

The boiler, if possible, should be centrally located, and branches carried to different parts of the building. This insures a more even circulation than if all the radiators are supplied from a single long main, in which case the circulation is liable to be sluggish at the farther end.



Fig. 89. System of Hot-Water Piping Especially Adapted to Apartment Buildings where Each Flat Has a Separate Heater.

The arrangement shown in Fig. 89 is similar to the circuit system for steam, except that the radiators have two connections instead of one. This method is especially adapted to apartment houses, where each flat has its separate heater, as it eliminates a separate return main, and thus reduces, by practically one-half, the amount of piping in the basement. The supply risers are taken from the top of the main; while the returns should connect into the side a short distance beyond, and in a direction *away* from the boiler. When this system is used, it is necessary to enlarge the radiators slightly as the distance from the boiler increases.

In flats of eight or ten rooms, the size of the last radiator may be increased from 10 to 15 per cent, and the intermediate ones propor-

tionally, at the same time keeping the main of a large and uniform size for the entire circuit.

Overhead Distribution. This system of piping is shown in Fig. 90. A single riser is carried directly to the expansion tank, from which branches are taken to supply the various drops to which the radiators are connected. An important advantage in connection with this system is that the air rises at once to the expansion tank, and escapes through the vent, so that air-valves are not required on the radiators.



Fig. 90. "Overhead" Distribution System of Hot-Water Piping.

At the same time, it has the disadvantage that the water in the tank is under less pressure than in the heater; hence it will boil at a lower temperature. No trouble will be experienced from this, however, unless the temperature of the water is raised above 212 degrees.

Expansion Tank. Every system for hot-water heating should be connected with an expansion tank placed at a point somewhat above the highest radiator. The tank must in every case be connected to a line of piping which cannot by any possible means be shut off from the boiler. When water is heated, it expands a certain amount,

depending upon the temperature to which it is raised; and a tank or reservoir should always be provided to care for this increase in volume.

Expansion tanks are usually made of heavy galvanized iron of one of the forms shown in Figs. 91 and 92, the latter form being used where the headroom is limited. The connection from the heating system enters the bottom of the tank, and an open vent pipe is taken from the top. An overflow connected with a sink or drain-pipe should be provided. Connections should be made with the water supply both at the boiler and at the expansion tank, the former to be used when first filling the system, as by this means all air is driven from the bottom upward and is discharged through the vent at the expansion tank. Water that is added afterward may be supplied directly to the expansion tank, where the water-line can be noted in the gauge-glass. A ball-cock is sometimes arranged to keep the water-line in the tank at a constant level.



Fig. 91. A Common Form of Galvanized-Iron Expansion Tank.

An *altitude gauge* is often placed in the basement with the colored hand or pointer set to indicate the normal water-line in the expansion tank. When the movable hand falls below the fixed one, more water may be added, as required, through the supply pipe at the boiler. When the tank is placed in an attic or roof space where there is danger of freezing, the expansion pipe may be connected into the side of the



Fig. 92. Form of Expansion Tank Used where Headroom is Limited.

tank, 6 or 8 inches from the bottom, and a circulation pipe taken from the lower part and connected with the return from an upper-floor radiator. This produces a slow circulation through the tank, and keeps the water warm.

The size of the expansion tank depends upon the volume of water contained in the system, and on the temperature to which it is heated. The following rule for computing the capacity of the tank may be used with satisfactory results:

Square feet of radiation, *divided by* 40, equals required capacity of tank in gallons.

Air-Venting. One very important point to be kept in mind in the design of a hot-water system, is the removal of air from the pipes and radiators. When the water in the boiler is heated, the air it contains forms into small bubbles which rise to the highest points of the system.

In the arrangement shown in Fig. 88, the main and branches grade upward from the boiler, so that the air finds its way into the radiators, from which it may be drawn off by means of the air-valves.

A better plan is that shown in Fig. 89. In this case the expansion pipe is taken directly off the top of the main over the boiler, so that the larger part of the air rises directly to the expansion tank and escapes through the vent pipe. The same action takes place in the overhead system shown in Fig. 90, where the top of the main riser is connected with the tank. Every high point in the system and every radiator, except in the downward system with top supply connection, should be provided with an air-valve.

Pipe Connections. There are various methods of connecting the radiators with the mains and risers. Fig. 93 shows a radiator connected with the horizontal flow and return mains, which are located below the floor. The manner of connecting with a vertical riser and return drop is shown in Fig. 94. As the water tends to flow to the highest point, the radiators on the lower floors should be favored by making the connection at the top of the riser and taking the pipe for the upper floors from the side as shown. Fig. 95 illustrates the manner of connecting with a radiator on an upper floor where the supply is connected at the top of the radiator.

The connections shown in Figs. 96 and 97 are used with the overhead system shown in Fig. 90.

Where the connection is of the form shown at the left in Fig. 90, the cooler water from the radiators is discharged into the supply pipe again, so that the water furnished to the radiators on the lower floors is at a lower temperature, and the amount of heating surface must be correspondingly increased to make up for this loss, as already described for the circuit system.



Fig. 93. Radiator Connected with Horizontal Flow and Return Mains Located below Floor.



Fig. 94. Radiator Connected to Vertical Riser and Return Drop.

For example, if in the case of Fig. 90 we assume the water to leave at 180 degrees and return at 160, we shall have a drop in temperature of 10 degrees on each floor; that is, the water will enter the radiator on the second floor at 180 degrees and leave it at 170, and will enter the radiator on the first floor at 170 and leave it at 160.



Fig. 95. Upper-Floor Radiator with Supply Connected at Top.



Fig. 96. Radiator Connections, Overhead Distribution System.

The average temperatures will be 175 and 165, respectively. The efficiency in the first case will be $175 - 70 = 105$; and $105 \times 1.5 = 157$. In the second case, $165 - 70 = 95$; and $95 \times 1.5 = 142$; so that the radiator on the first floor will have to be larger than that on the second floor in the ratio of 157 to 142, in order to do the same work.

This is approximately an increase of 10 per cent for each story downward to offset the cooling effect; but in practice the supply drops are made of such size that only a part of the water is by-passed through the radiators. For this reason an increase of 5 per cent for each story downward is probably sufficient in ordinary cases.

Where the radiators discharge into a separate return as in the case of Fig. 88, or those at the right in Fig. 90, we may assume the temperature of the water to be the same on all floors, and give the radiators an equal efficiency.



Fig. 97. Another Form of Radiator Connection, Overhead Distribution System.

In a dwelling-house of two stories, no difference would be made in the sizes of radiators on the two floors; but in the case of a tall office building, corrections would necessarily be made as above described.

Where circulation coils are used, they should be of a form which will tend to produce a flow of water through them. Figs. 98, 99, and 100 show different ways of making up and connecting these coils. In Figs. 98 and 100, supply pipes may be either drops or risers; and



Fig. 98. Circulation Coil, One Method of Construction. Supply Pipes may be Either Drops or Risers.

in the former case the return in Fig. 100 may be carried back, if desired, into the supply drop, as shown by the dotted lines.

Combination Systems. Sometimes the boiler and piping are arranged for either steam or hot water, since the demand for a higher or lower temperature of the radiators might change.

The object of this arrangement is to secure the advantages of a hot-water system for moderate temperatures, and of steam heating for extremely cold weather.



Fig. 99. Another Method of Building Up a Circulation Coil.

As less radiating surface is required for steam heating, there is an advantage due to the reduction in first cost. This is of considerable importance, as a heating system must be designed of such dimensions as to be capable of warming a building in the coldest weather;



Fig. 100. Circulation Coil with Either Drop or Riser Supply. In former case, return may be carried into Supply Drop as shown by Dotted Lines.

and this involves the expenditure of a considerable amount for radiating surfaces, which are needed only at rare intervals. A combination system of hot-water and steam heating requires, *first*, a heater or boiler

which will answer for either purpose; *second*, a system of piping which will permit the circulation of either steam or hot water; and *third*, the use of radiators which are adapted to both kinds of heating. These requirements will be met by using a steam boiler provided with all the fittings required for steam heating, but so arranged that the damper regulator may be closed by means of valves when the system is to be used for hot-water heating. The addition of an expansion tank is required, which must be so arranged that it can be shut off when the system is used for steam heating. The system of piping shown in Fig. 88 is best adapted for a combination system, although an overhead distribution as shown in Fig. 90 may be used by shutting off the vent and overflow pipes, and placing air-valves on the radiators.

While this system has many advantages in the way of cost over the complete hot-water system, the labor of changing from steam to hot water will in some cases be troublesome; and should the connections to the expansion tank not be opened, serious results would follow.



Fig. 101. Radiator Valve for Hot-Water Work.

Valves and Fittings. Gate-valves should always be used in connection with hot-water piping, although angle-valves may be used at the radiators. There are several patterns of radiator valves made especially for hot-water work; their chief advantage lies in a device for quick closing, usually a quarter-turn or half-turn being sufficient to open or close the valve. Two different designs are shown in Figs. 101 and 102.

It is customary to place a valve in only one connection, as that is sufficient to stop the flow of water through the radiator; a fitting known as a *union elbow* is often employed in place of the second valve. (See Fig. 103.)

Air-Valves. The ordinary pet-cock air-valve is the most reliable for hot-water radiators, although there are several forms of automatic valves which are claimed to give satisfaction. One of these is shown in Fig. 104. This is similar in construction to a steam trap. As air collects in the chamber, and the water-line is lowered, the float drops, and in so doing opens a small valve at the top of the

chamber, which allows the air to escape. As the water flows in to take its place, the float is forced upward and the valve is closed.

All radiators which are supplied by risers from below, should be provided with air-valves placed in the top of the last section at the return end. If they are supplied by drops from an overhead system, the air will be discharged at the expansion tank, and air-valves will not be necessary at the radiators.



Fig. 102. Another Type of Hot-Water Radiator Valve.



Fig. 103. Union Elbow.

Fittings. All fittings, such as elbows, tees, etc., should be of the *long-turn* pattern. If the common form is used, they should be a size larger than the pipe, bushed down to the proper size. The long-turn fittings, however, are preferable, and give a much better appearance. Connections between the radiators and risers may be made with the ordinary short-pattern fittings, as those of the other form are not well adapted to the close connections necessary for this work.



Fig. 104. Automatic Air-Valve for Hot-Water Radiator. Operated by a Float.

Pipe Sizes. The size of pipe required to supply any given radiator depends upon four conditions; *first*, the size of the radiator; *second*, its elevation above the boiler; *third*, the length of pipe required to connect it with the boiler; and *fourth*, the difference in temperature between the supply and the return.

As it would be a long and rather complicated process to work out the required size of each pipe for a heating system, Tables XXVI and XXVII have been prepared, covering the usual conditions to be met with in practice.

TABLE XXVI

Direct Radiating Surface Supplied by Mains of Different Sizes and Lengths of Run

Size of Pipe	Square Feet of Radiating Surface								
	100 ft. Run	200 ft. Run	300 ft. Run	400 ft. Run	500 ft. Run	600 ft Run	700 ft. Run	800 ft. Run	1,000 ft. Run
1 in.	30								
1¼ "	60	50							
1½ "	100	75	50						
2 "	200	150	125	100	75				
2½ "	350	250	200	175	150	125			
3 "	550	400	300	275	250	225	200	175	150
3½ "	850	600	450	400	350	325	300	250	225
4 "	1,200	850	700	600	525	475	450	400	350
5 "		1,400	1,150	1,000	700	850	775	725	650
6 "				1,600	1,400	1,300	1,200	1,150	1,000
7 "							1,706	1,600	1,500

These quantities have been calculated on a basis of 10 feet difference in elevation between the center of the heater and the radiators, and a difference in temperature of 17 degrees between the supply and the return.

TABLE XXVII

Radiating Surface on Different Floors Supplied by Pipes of Different Sizes

Size of Riser	Square Feet of Radiating Surface					
	1st Story	2d Story	3d Story	4th Story	5th Story	6th Story
1 in.	30	55	65	75	85	95
1¼ "	60	90	110	125	140	160
1½ "	100	140	165	185	210	240
2 "	200	275	375	425	500	
2½ "	350	475				
3 "	550					
3½ "	850					

Table XXVI gives the number of square feet of direct radiation which different sizes of mains and branches will supply for varying lengths of run.

Table XXVI may be used for all horizontal mains. For vertical risers or drops, Table XXVII may be used. This has been com-

puted for the same difference in temperature as in the case of Table XXVI (17 degrees), and gives the square feet of surface which different sizes of pipe will supply on the different floors of a building, assuming the height of the stories to be 10 feet. Where a single riser is carried to the top of a building to supply the radiators on the floors below, by drop pipes, we must first get what is called the *average elevation of the system* before taking its size from the table. This may be illustrated by means of a diagram (see Fig. 105).

In *A* we have a riser carried to the third story, and from there a drop brought down to supply a radiator on the first floor. The elevation available for producing a flow in the riser is only 10 feet, the same as though it extended only to the radiator. The water in the two pipes above the radiator is practically at the same temperature, and therefore in equilibrium, and has no effect on the flow of the water in the riser. (Actually there would be some radiation from the pipes, and the return, above the radiator, would be slightly cooler, but for purposes of illustration this may be neglected). If the radiator was on the second floor the elevation of the system would be 20 feet (see *B*); and on the third floor, 30 feet; and so on. The distance which the pipe is carried above the first radiator which it supplies has but little effect in producing a flow, especially if covered, as it should be in practice. Having seen that the flow in the main riser depends upon the elevation of the radiators, it is easy to see that the way in which it is distributed on the different floors must be considered. For example, in *B*, Fig. 105, there will be a more rapid flow through the riser with the radiators as shown, than there would be if they were reversed and the largest one were placed upon the first floor.

We get the average elevation of the system by multiplying the square feet of radiation on each floor by the elevation above the heater, then adding these products together and dividing the same by the total radiation in the whole system. In the case shown in *B*, the average elevation of the system would be

$$\frac{(100 \times 30) + (50 \times 20) + (25 \times 10)}{100 + 50 + 25} = 24 \text{ feet};$$

and we must proportion the main riser the same as though the whole radiation were on the second floor. Looking in Table XXVII, we find, for the second story, that a 1½-inch pipe will supply 140 square



SECTIONAL STEAM BOILER.

Made by American Radiator Company.



SECTIONAL WATER BOILER.

feet; and a 2-inch pipe, 275 feet. Probably a 1½-inch pipe would be sufficient.

Although the height of stories varies in different buildings, 10 feet will be found sufficiently accurate for ordinary practice.

INDIRECT HOT-WATER HEATING

This is used under the same conditions as indirect steam, and the heaters used are similar to those already described. Special



Fig. 105. Diagram to Illustrate Finding of Average Elevation of Heating System.

attention is given to the form of the sections, in order that there may be an even distribution of water through all parts of them. As the stacks are placed in the basement of a building, and only a short distance above the boiler, extra large pipes must be used to secure a proper circulation, for the *head* producing flow is small. The stack

casings, cold-air and warm-air pipes, and registers are the same as in steam heating.

Types of Radiators. The radiators for indirect hot-water heating are of the same general form as those used for steam. Those shown in Figs. 52, 53, 56, 106, and 107 are common patterns. The *drum pin*, Fig. 106, is an excellent form, as the method of making the connections insures a uniform distribution of water through the stack.

Fig. 107 shows a radiator of good form for water circulation, and also of good depth, which is a necessary point in the design of hot-water radiators. They should be not less than 12 or 15 inches deep for good results. Box coils of the form given for steam may also be



Fig. 106. "Drum Pin" Indirect Hot-Water Radiator.

used, provided the connections for supply and return are made of good size.

Size of Stacks. As indirect hot-water heaters are used principally in the warming of dwelling-houses, and in combination with direct radiation, the easiest method is to compute the surfaces required for direct radiation, and multiply these results by 1.5 for pin radiators of good depth. For other forms the factor should vary from 1.5 to 2, depending upon the depth and proportion of free area for air-flow between the sections.

If it is desired to calculate the required surface directly by the thermal unit method, we may allow an efficiency of from 360 to 400 for good types in zero weather.

In schoolhouse and hospital work, where larger volumes of air are warmed to lower temperatures, an efficiency as high as 500 B. T. U. may be allowed for radiators of good form.

Flues and Casings. For cleanliness, as well as for obtaining the best results, indirect stacks should be hung at one side of the register or flue receiving the warm air, and the cold-air duct should enter beneath the heater at the other side. A space of at least 10 inches, and preferably 12, should be allowed for the warm air above the stack. The top of the casing should pitch upward toward the warm-air outlet at least an inch in its length. A space of from 8 to 10 inches should be allowed for cold air below the stack.

As the amount of air warmed per square foot of heating surface is less than in the case of steam, we may make the flues somewhat smaller as compared with the size of heater. The following proportions may be used under usual conditions for dwelling-houses: $1\frac{1}{2}$ square inches per square foot of radiation for the first floor, $1\frac{1}{4}$ square inches for the second floor, and $1\frac{1}{4}$ square inches for the cold-air duct.



Fig. 107. Indirect Hot-Water Radiator.

Pipe Connections. In indirect hot-water work, it is not desirable to supply more than 80 to 100 square feet of radiation from a single connection. When the requirements call for larger stacks, they should be divided into two or more groups according to size.

It is customary to carry up the main from the boiler to a point near the basement ceiling, where it is air-vented through a small pipe leading to the expansion tank. The various branches should grade downward and connect with the tops of the stacks. In this way, all air, both from the boiler and from the stacks, will find its way to the highest point in the main, and be carried off automatically.

As an additional precaution, a pet-cock air-valve should be placed in the last section of each stack, and brought out through the casing by means of a short pipe.

TABLE XXVIII

Radiating Surface Supplied by Pipes of Various Sizes—Indirect Hot-Water System

Diameter of Pipe	Square Feet of Radiating Surface			
	100 Ft. Run	200 Ft. Run	300 Ft. Run	400 Ft. Run
1 in.	15			
1¼ "	30	25		
1½ "	50	40	25	
2 "	100	75	60	50
2½ "	175	125	100	90
3 "	275	200	150	140
3½ "	425	300	225	200
4 "	600	425	350	300
5 "		700	575	500
6 "				800
7 "				1,200

Some engineers make a practice of carrying the main to the ceiling of the first story, and then dropping to the basement before branching to the stacks, the idea being to accelerate the flow of water through the main, which is liable to be sluggish on account of the small difference in elevation between the boiler and stacks. If the return leg of the loop is left uncovered, there will be a slight drop in temperature, tending to produce this result; but in any case it will be exceedingly small. With supply and return mains of suitable size and properly graded, there should be no difficulty in securing a good circulation in basements of average height.

Pipe Sizes. As the difference in elevation between the stacks and the heater is necessarily small, the pipes should be of ample size to offset the slow velocity of flow through them. The sizes mentioned in Table XXVIII, for runs up to 400 feet, will be found to supply ample radiating surface for ordinary conditions. Some engineers make a practice of using somewhat smaller pipes, but the larger sizes will in general be found more satisfactory.

CARE AND MANAGEMENT OF HOT-WATER HEATERS

The directions given for the care of steam-heating boilers apply in a general way to hot-water heaters, as to the methods of caring for the fires and for cleaning and filling the heater. Only the special points of difference need be considered. Before building the fire, all the pipes and radiators must be full of water, and the expansion tank

should be partially filled as indicated by the gauge-glass. Should the water in any of the radiators fail to circulate, see that the valves are wide open and that the radiator is free from air. Water must always be added at the expansion tank when for any reason it is drawn from the system.

The required temperature of the water will depend upon the outside conditions, and only enough fire should be carried to keep the rooms comfortably warm. Thermometers should be placed in the flow and return pipes near the heater, as a guide. Special forms are made for this purpose, in which the bulb is immersed in a bath of oil or mercury (see Fig. 108).



Fig. 108. Thermometer Attached to Feed-Pipe near Heater, to Determine Temperature of Water.

FORCED HOT-WATER CIRCULATION

While the gravity system of hot-water heating is well adapted to buildings of small and medium size, there is a limit to which it can be carried economically. This is due to the slow movement of the water, which calls for pipes of excessive size. To overcome this difficulty, pumps are used to force the water through the mains at a comparatively high velocity.

The water may be heated in a boiler in the same manner as for gravity circulation, or exhaust steam may be utilized in a feed-water heater of large size. Sometimes part of the heat is derived from an economizer placed in the smoke passage from the boilers.

Systems of Piping. The mains for forced circulation are usually run in one of two ways. In the *two-pipe system*, shown in Fig. 109, the supply and return are carried side by side, the former reducing in size, and the latter increasing as the branches are taken off.

The flow through the risers is produced by the difference in pressure in the supply and return mains; and as this is greatest nearest the pump, it is necessary to place throttle-valves in the risers to prevent short-circuiting and to secure an even distribution through all parts of the system.

Fig. 110 shows the *single-pipe* or *circuit system.* This is similar to the one already described for gravity circulation, except that it can be used on a much larger scale.

A single main is carried entirely around the building in this case, the ends being connected with the suction and discharge of the pump as shown.

As the pressure or head in the main drops constantly throughout the circuit, from the discharge of the pump back to the suction, it is



Fig. 109. "Two-Pipe" System for Forced Hot-Water Circulation.

evident that if a supply riser be taken off at any point, and the return be connected into the main a short distance along the line, there will be a sufficient difference in pressure between the two points to produce a circulation through the two risers and the connecting radiators. A distance of 8 or 10 feet between the connections is usually ample to produce the necessary circulation, and even less if the supply is taken from the top of the main and the return connected into the side.

Sizes of Mains and Branches. As the velocity of flow is independent of the temperature and elevation when a pump is used, it is necessary to consider only the volume of water to be moved and the length of run.

The volume is found by the equation

$$Q = \frac{R\ E}{500\ T},$$

in which

Q = Gallons of water required per minute;
R = Square feet of radiating surface to be supplied;
E = Efficiency of radiating surface in B. T. U. per sq. foot per hour;
T = Drop in temperature of the water in passing through the heating system.

In systems of this kind, where the circulation is comparatively rapid, it is customary to assume a drop in temperature of 30° to 40°, between the supply and return.

Having determined the gallons of water to be moved, the required size of main can be found by assuming the velocity of flow, which for pipes from 5 to 8 inches in diameter may be taken at 400 to 500



Fig. 110. "Single-Pipe" or "Circuit" System for Forced Hot-Water Circulation.

feet per minute. A velocity as high as 600 feet is sometimes allowed for pipes of large size, while the velocity in those of smaller diameter should be proportionally reduced to 250 or 300 feet for a 3-inch pipe. The next step is to find the pressure or head necessary to force the water through the main at the given velocity. This in general should not exceed 50 or 60 feet, and much better pump efficiencies will be obtained with heads not exceeding 35 or 40 feet.

As the water in a heating system is in a state of equilibrium, the only power necessary to produce a circulation is that required to overcome the friction in the pipes and radiators; and, as the area of the passageways through the latter is usually large in comparison with the former, it is customary to consider only the head necessary to force the water through the mains, taking into consideration the additional friction produced by valves and fittings.

Each long-turn elbow may be taken as adding about 4 feet to the length of pipe; a short-turn fitting, about 9 feet; 6-inch and 4-inch swing check-valves, 50 feet and 25 feet, respectively; and 6-inch and 4-inch globe check-valves, 200 feet and 130 feet, respectively.

Table XXIX is prepared especially for determining the size of mains for different conditions, and is used as follows:

Example. Suppose that a heating system requires the circulation of 480 gallons of water per minute through a circuit main 600 feet in length. The pipe contains 12 long-turn elbows and 1 swing check-valve. What diameter of main should be used?

Assuming a velocity of 480 feet per minute as a trial velocity, we follow along the line corresponding to that velocity, and find that a 5-inch pipe will deliver the required volume of water under a head of 4.9 feet for each 100 feet length of run.

The actual length of the main, including the equivalent of the fittings as additional length, is

$$600 + (12 \times 9) + 50 = 758 \text{ feet};$$

hence the total head required is $4.9 \times 7.58 = 37$ feet. As both the assumed velocity and the necessary head come within practicable limits, this is the size of pipe which would probably be used. If it were desired to reduce the power for running the pump, the size of main could be increased. That is, Table XXIX shows that a 6-inch pipe would deliver the same volume of water with a friction head of only about 2 feet per 100 feet in length, or a total head of $2 \times 7.58 = 15$ feet.

The risers in the circuit system are usually made the same size as for gravity work. With double mains, as shown in Fig. 109, they may be somewhat smaller, a reduction of one size for diameters over 1¼ inches being common

The branches connecting the risers with the mains may be proportioned from the combined areas of the risers. When the branches are of considerable size, the diameter may be computed from the available head and volume of water to be moved.

Pumps. Centrifugal pumps are usually employed in connection with forced hot-water circulation, in preference to pumps of the piston or plunger type. They are simple in construction, having no valves, produce a continuous flow of water, and, for the low heads

TABLE XXIX

Capacity in Gallons per Minute Discharged at Velocities of 300 to 540 Feet per Minute—Also Friction Head in Feet, per 100 Feet Length of Pipe

	DIAMETER OF PIPE											
	3-Inch		4-Inch		5-Inch		6-Inch		7-Inch		8-Inch	
Velocity	Capacity	Friction	Capacity	Friction	Capacity	Friction	Capacity	Friction	Capacity	Friction	Capacity	Friction
300	110	3.41	195	2.56	306	2.05	440	1.70	600	1.46	783	1.28
480	176	8.16	314	6.12	490	4.9	705	4.08	959	3.49	1,253	3.06
540	198	10.1	352	7.64	550	6.11	794	5.09	1,079	4.36	1,410	3.82

against which they are operated, have a good efficiency. A pump of this type, with a direct-connected engine, is shown in Fig. 111.

Under ordinary conditions the efficiency of a centrifugal pump falls off considerably for heads above 30 or 35 feet; but special high-speed pumps are constructed which work with a good efficiency against 500 feet or more.

Under favorable conditions an efficiency of 60 to 70 per cent is often obtained; but for hot-water circulation it is more common to assume an efficiency of about 50 per cent for the average case.

The horse-power required for driving a pump is given by the following formula:

$$\text{H. P.} = \frac{H \times V \times 8.3}{33{,}000 \times E},$$

in which

H = Friction head in feet;
V = Gallons of water delivered per minute;
E = Efficiency of pump.

Centrifugal pumps are made in many sizes and with varying proportions, to meet the different requirements of capacity and head.

Heaters. If the water is heated in a boiler, any good form may be used, the same as for gravity work. In case tubular boilers are used, the entire shell may be filled with tubes, as no steam space is required.

In order to prevent the water from passing in a direct line from the inlet to the outlet, a series of baffle-plates should be used to bring it in contact with all parts of the heating surface.

When steam is used for heating the water, it is customary to employ a closed feed-water heater with the steam on the inside of the tubes and the water on the outside.

Any good form of heater can be used for this purpose by providing it with steam connections of sufficient size. In the ordinary form of heater, the feed-water flows through the tubes, and the connections are therefore small, making it necessary to substitute special nozzles of large size when used in the manner here described.

When computing the required amount of heating surface in the tubes of a heater, it is customary to assume an efficiency of about 200 B. T. U. per square foot of surface per hour, per degree difference in temperature between the water and steam.

It is usual to circulate the water at a somewhat higher temperature in systems of this kind, and a maximum initial temperature of 200 degrees, with a drop of 40 degrees in the heating system, may be used in computing the size of heater. If exhaust steam is used at atmospheric pressure, there will be a difference of 212 − 180 = 32 degrees, between the *average* temperature of the water and the steam, giving an efficiency of 200 × 32 = 6,400 B. T. U. per square foot of heating surface.

From this it is evident that 6,400 ÷ 170 = 38 square feet of direct radiating surface, or 6,400 ÷ 400 = 16 square feet of indirect, may be supplied from each square foot of tube surface in the heater.

Example. A building having 6,000 square feet of direct, and 2,000 square feet of indirect radiation, is to be warmed by hot water under forced circulation. Steam at atmospheric pressure is to be used for heating the water. How many square feet of heating surface should the heater contain?

6,000 ÷ 38 = 158; and 2,000 ÷ 16 = 125; therefore, 158 + 125 = 283 square feet, the area of heating surface called for.

When the exhaust steam is not sufficient for the requirements, an auxiliary live steam heater is used in connection with it.



Fig. 111. Centrifugal Pump Direct-Connected to Engine, for Forced Hot-Water Circulation.

EXAMPLES FOR PRACTICE

1. A building contains 10,000 square feet of direct radiation and 4,000 square feet of indirect radiation. How many gallons of water must be circulated through the mains per minute, allowing a drop in temperature of 40 degrees? Ans. 165 gal.

2. In the above example, what size of main should be used, assuming the circuit to be 300 feet in length and to contain ten long-turn elbows? The friction head is not to exceed 10 ft., and the velocity of flow not to exceed 300 feet per minute. Ans. 4-inch.

3. What horse-power will be required to drive a centrifugal pump delivering 400 gallons per minute against a friction head of 40 feet, assuming an efficiency of 50 per cent for the pump?

Ans. 8 H. P.

4. A building contains 10,000 square feet of direct radiation and 5,000 square feet of indirect radiation. Steam at atmospheric pressure is to be used. The initial temperature of the water is to be 200°; and the final, 160°. How many square feet of heating surface should the heater contain? ANS. 575 sq. ft.

5. How many square feet would be required in the above heater (Example 4) if the initial temperature of the water were 180° and the final temperature 150°? ANS. 399 sq. ft.

EXHAUST-STEAM HEATING

Steam, after being used in an engine, contains the greater part of its heat; and if not condensed or used for other purposes, it can usually be employed for heating without affecting to any great extent the power of the engine. In general, we may say that it is a matter of economy to use the exhaust for heating, although various factors must be considered in each case to determine to what extent this is true. The more important considerations bearing upon the matter are: the relative quantities of steam required for power and for heating; the length of the heating season; the type of engine used; the pressure carried; and, finally, whether the plant under consideration is entirely new, or whether, on the other hand, it involves the adapting of an old heating system to a new plant.

The first use to be made of the exhaust steam is the heating of the feed-water, as this effects a constant saving both summer and winter, and can be done without materially increasing the back-pressure on the engine. Under ordinary conditions, about one-sixth of the steam supplied to the engine can be used in this way, or more nearly one-fifth of the exhaust *discharged* from the engine.

We may assume in average practice that about 80 per cent of the steam supplied to an engine is discharged in the form of steam at a lower pressure, the remaining 20 per cent being partly converted into work and partly lost through cylinder condensation. Taking this into account, there remains, after deducting the steam used for feed-water heating, $.8 \times \frac{4}{5} = .64$ of the entire quantity of steam supplied to the engine, available for heating purposes.

When the quantity of steam required for heating is small compared with the total amount supplied to the engine, or where the heating season is short, it is often more economical to run the engine

condensing and use the live steam for heating. This can be determined in any particular case by computing the saving in fuel by the use of a condenser, taking into account the interest and depreciation on the first cost of the condensing apparatus, and the cost of water, if it must be purchased, and comparing it with the cost of heating with live steam.

Usually, however, in the case of office buildings and institutions, and commonly in the case of shops and factories, especially in northerly latitudes, it is advantageous to use the exhaust for heating, even if a condenser is installed for summer use only. The principal objection raised to the use of exhaust steam has been the higher back-pressure required on the engines, resulting in a loss of power nearly proportional to the ratio of the back-pressure to the mean effective pressure. There are two ways of offsetting this loss—one, by raising the initial or boiler pressure; and the other, by increasing the cut-off of the engine. Engines are usually designed to work most economically at a given cut-off, so that in most cases it is undesirable to change it to any extent. Raising the boiler pressure, on the other hand, is not so objectionable if the increase amounts to only a few pounds.

Under ordinary conditions in the case of a simple engine, a rise of 3 pounds in the back-pressure calls for an increase of about 5 pounds in the boiler pressure, to maintain the same power at the engine.

The indicator card shows a back-pressure of about 2 pounds when an engine is exhausting into the atmosphere, so that an increase of 3 pounds would bring the pressure up to a total of 5 pounds which should be more than sufficient to circulate the steam through any well-designed heating system.

If it is desired to reduce rather than increase the back-pressure, one of the so-called *vacuum systems*, described later, can be used.

The systems of steam heating which have been described are those in which the water of condensation flows back into the boiler by gravity. Where exhaust steam is used, the pressure is much below that of the boiler, and it must be returned either by a pump or by a return trap. The exhaust steam is often insufficient to supply the entire heating system, and must be supplemented by live steam taken directly from the boiler. This must first pass through a reducing

valve in order to reduce the pressure to correspond with that carried in the heating system.

An engine does not deliver steam continuously, but at regular intervals, at the end of each stroke; and the amount is likely to vary with the work done, since the governor is adjusted to admit steam in such a quantity as is required to maintain a uniform speed. If the work is light, very little steam will be admitted to the engine; and for this reason the supply available for heating may vary somewhat, depending upon the use made of the power delivered by the engine. In mills the amount of exhaust steam is practically constant; in office buildings where power is used for lighting, the variation is greater, especially if power is also required for the running of elevators.

The general requirements for a successful system of exhaust steam heating include a system of piping of such proportions that only a slight increase in back-pressure will be thrown upon the engine; a connection which shall automatically supply live steam at a reduced pressure as needed; provision for removing the oil from the exhaust steam; a relief or back-pressure valve arranged to prevent any sudden increase in back pressure on the engine; and a return system of some kind for returning the water of condensation to the boiler against a higher pressure. These requirements may be met in various ways, depending upon actual conditions found in different cases.

To prevent sudden changes in the back-pressure, due to irregular supply of steam, the exhaust pipe from the engine is often carried to a closed tank having a capacity from 30 to 40 times that of the engine cylinder. This tank may be provided with baffle-plates or other arrangements and may serve as a separator for removing the oil from the steam as it passes through.

Any system of piping may be used; but great care should be taken that as little resistance as possible is introduced at bends and fittings; and the mains and branches should be of ample size. Usually the best results are obtained from the system in which the main steam pipe is carried directly to the top of the building, the distributing pipes being run from that point, and the radiating surfaces supplied by a down-flowing current of steam.

Before taking up the matter of piping in detail a few of the more important pieces of apparatus will be described in a brief way.

Reducing Valves. The action of pressure-reducing valves has

been taken up quite fully in "Boiler Accessories," and need not be repeated here. When the reduction in pressure is large, as in the case of a combined power and heating plant, the valve may be one or two sizes smaller than the low-pressure main into which it discharges. For example, a 5-inch valve will supply an 8-inch main; a 4-inch a 6-inch main, a 3-inch a 5-inch main, a 2½-inch a 4-inch main, etc.

For the smaller sizes, the difference should not be more than one size. All reducing valves should be provided with a valved by-pass for cutting out the valve in case of repairs. This connection is usually made as shown in plan by Fig. 112.

Grease Extractor. When exhaust steam is used for heating purposes, it must first be passed through some form of separator for removing the oil; and as an additional precaution it is well to pass the



Fig. 112. Connections of Reducing Valve in Exhaust-Steam Heating System.

water of condensation through a separating tank before returning it to the boilers.

Such an arrangement is shown in Fig. 113. As the oil collects on the surface of the water in the tank, it can be made to overflow into the sewer by closing the valve in the connection with the receiving tank, for a short time.

As much of the oil as possible should be removed before the steam enters the pipes and radiators, else a coating will be formed on their inner surfaces, which will reduce their heating efficiency. The separation of the oil is usually effected by introducing a series of baffling plates in the path of the steam; the particles of oil striking these are stopped, and thus separated from the steam. The oil drops into a receiver provided for this purpose and is discharged through a trap to the sewer.

In the separator, or extractor, shown in Fig. 114, the separation is accomplished by a series of plates placed in a vertical position in the

body of the separator, through which the steam must pass. These plates consist of upright hollow columns, with openings at regular intervals for the admission of water and oil, which drain downward to the receiver below. The steam takes a zigzag course, and all of it comes in contact with the intercepting plates, which insures a thorough separation of the oil and other solid matter from the steam. Another form, shown in Fig. 115, gives excellent results, and has the advantage of providing an equalizing chamber for overcoming, to some extent, the unequal pressure due to the varying load on the engine. It consists of a tank or receiver about 4 feet in diameter, with heavy boiler-iron heads slightly crowned to give stiffness.



Fig. 113. Separator for Removing Oil from Exhaust Steam and Water Condensation.

Through the center is a layer of excelsior (wooden shavings of long fibre) about 12 inches in thickness, supported on an iron grating, with a similar grating laid over the top to hold it in place. The steam enters the space below the excelsior and passes upward, as shown by the arrows. The oil is caught by the excelsior, which can be renewed from time to time as it becomes saturated. The oil and water which fall to the bottom of the receiver are carried off through a trap. Live steam may be admitted through a reducing valve, for supplementing the exhaust when necessary.

Back-Pressure Valve. This is a form of relief valve which is placed in the outboard exhaust pipe to prevent the pressure in the heating system from rising above a given point. Its office is the



THE THERMOGRADE SEMI-AUTOMATIC SYSTEM OF HEATING
Showing a Thermograde Valve as Applied to Radiator

reverse of the reducing valve, which supplies more steam when the pressure becomes too low. The form shown in Fig. 116 is designed for a vertical pipe. The valve proper consists of two discs of unequal area, the combined area of which equals that of the pipe. The force tending to open the valve is that due to the steam pressure acting on an area equal to the difference in area between the two discs; it is clear from the cut that the pressure acting on the larger disc tends to open the valve while the pressure on the smaller acts in the opposite direction. The valve-stem is connected by a link and crank arm with a spindle upon which is a lever and weight outside. As the valve opens, the weight is raised, so that, by placing it in different positions on the lever arm, the valve will open at any desired pressure.



Fig. 114. Oil Separator Consisting of Vertical Plates with Openings Giving Steam a Zigzag Course.

Fig. 117 shows a different type, in which a spring is used instead of a weight. This valve has a single disc moving in a vertical direction. The valve stem is in the form of a piston or dash-pot which prevents a too sudden movement and makes it more quiet in its action. The disc is held on its seat against the steam pressure by a lever attached to the spring as shown. When the pressure of the steam on the underside becomes greater than the tension of the spring, the valve lifts and allows the steam to escape. The tension of the spring can be varied by means of the adjusting screw at its upper end.

A back-pressure valve is simply a low-pressure safety-valve

designed with a specially large opening for the passage of steam through it. These valves are made for horizontal as well as for vertical pipes.



Fig. 115. Oil Separator Consisting of a Tank in which Steam is Filtered by Passing Upward through a Layer of Excelsior.

Exhaust Head. This is a form of separator placed at the top of an outboard exhaust pipe to prevent the water carried up in the steam from falling upon the roofs of buildings or in the street below. Fig. 118 is known as a centrifugal exhaust head. The steam, on entering at the bottom, is given a whirling or rotary motion by the spiral deflectors; and the water is thrown outward by centrifugal force against the sides of the chamber, from which it flows into the shallow trough at the base, and is carried away through the drip-pipe, which is brought down and connected with a drain-pipe inside the building. The passage of the steam outboard is shown by the arrows. Other forms are used in which the water is separated from the steam by deflectors which change the direction of the currents.



Fig. 116. Automatically Acting Back-Pressure Valve Attached to Vertical Pipe. For Preventing Rise of Pressure in System above any Desired Point.

Automatic Return-Pumps. In exhaust heating plants, the condensation is returned to the boilers by means of some form of return-pump. A combined pump and receiver of the form illus-

trated in Fig. 119 is generally used. This consists of a cast-iron or wrought-iron tank mounted on a base in connection with a boiler feed-pump. Inside the tank is a ball-float connected by means of levers with a valve in the steam pipe which is connected with the pump. When the water-line in the tank rises above a certain level, the float is raised and opens the steam valve, which starts the pump. When the water is lowered to its normal level, the valve closes and the pump stops. By this arrangement, a constant water-line is maintained in the receiver, and the pump runs only as needed to care for the condensation as it returns from the heating system. If dry returns are used, they may be brought together and connected with the top of the receiver. If it is desired to seal the horizontal runs, as



Fig. 117. Back-Pressure Valve Automatically Operated by a Spring.



Fig. 118. Centrifugal Exhaust Head.

is usually the case, the receiver may be raised to a height sufficient to give the required elevation and the returns connected near the bottom below the water-line.

A *balance-pipe*, so called, should connect the heating main with the top of the tank, for equalizing the pressure; otherwise the steam above the water would condense, and the vacuum thus formed would draw all the water into the tank, leaving the returns practically empty and thus destroying the condition sought. Sometimes an independent regulator or pump governor is used in place of a receiver. One type is shown in Fig. 120. The return main is connected at

the upper opening, and the pump suction at the lower. A float inside the chamber operates the steam valve shown at the top, and the pump works automatically as in the case just described.

If it is desired to raise the water-line, the regulator may be elevated to the desired height and connections made as shown in Fig. 121.

Return Traps. The principle of the return trap has been described in "Boiler Accessories," but its practical form and application



Fig. 119. Combined Receiver and Automatic Pump for Returning Water of Condensation to Boiler.

will be taken up here. The type shown in Fig. 122 has all its working parts outside the trap. It consists of a cast-iron bowl pivoted at *G* and *H*. There is an opening through *G* connecting with the inside of the bowl. The pipe *K* connects through *C* with an interior pipe opening near the top (see Fig. 123). The pipe *D* connects with a receiver, into which all the returns are brought. *A* is a check-valve allowing water to pass through in the direction shown by the arrow. *E* is a pipe connecting with the boiler below the water-line. *B* is a

check opening toward the boiler, and K, a pipe connected with the steam main or drum.

The action of the trap is as follows: As the bowl fills with water from the receiver, it overbalances the weighted lever and drops to the bottom of the ring. This opens the valve C, and admits steam at boiler pressure to the top of the trap. Being at a higher level the water flows by gravity into the boiler, through the pipe E. Water and steam are kept from passing out through D by the check A.



Fig. 120. Automatic Float-Operated Pump Governor Used instead of a Receiver.

When the trap has emptied itself, the weight of the ball raises it to the original position, which movement closes the valve C and opens the small vent F. The pressure in the bowl being relieved, water flows in from the receiver through D, until the trap is filled, when the



Fig. 121. Pump Regulator Placed at Sufficient Height to Raise Water-Line to Point Desired.

process is repeated. In order to work satisfactorily, the trap should be placed at least 3 feet above the water-level in the boiler, and the

pressure in the returns must always be sufficient to raise the water from the receiver to the trap against atmospheric pressure, which is theoretically about 1 pound for every 2 feet in height. In practice there will be more or less friction to overcome, and suitable adjustments must be made for each particular case.



Fig. 122. Return Trap with Working Parts External.

Fig. 124 shows another form of trap acting upon the same principle, except that in this case the steam valve is operated by a bucket or float inside the trap. The pipe connections are practically the same as with the trap just described.

Return traps are more commonly used in smaller plants where it is desired to avoid the expense and care of a pump.

Damper-Regulators. Every heating and every power plant should be provided with automatic means for closing the dampers when the steam pressure reaches a certain point, and for opening them again when the pressure drops. There are various regulators designed for this purpose, a simple form of which is shown in Fig. 125.


Fig. 123. Showing Interior Detail of Return Trap of Fig. 122.

Steam at boiler pressure is admitted beneath a diaphragm which is balanced by a weighted lever. When the pressure rises to a certain point, it raises the lever slightly and opens a valve which admits water under pressure above a diaphragm located near the smoke-pipe. This action forces down a lever connected by chains with the damper, and closes it. When the steam pressure drops, the water-valve is closed, and the different parts of the apparatus take their original positions.

Another form similar in principle is shown in Fig. 126. In this

case a piston is operated by the water-pressure, instead of a diaphragm. In both types the pressures at which the damper shall open and close are regulated by suitable adjustments of the weights upon the levers.

Pipe Connections. The method of making the pipe connections in any particular case will depend upon the general arrangement of the apparatus and the various conditions. Fig. 127 illustrates



Fig. 124. Return Trap with Steam Valve Operated by Bucket or Float Inside.

the general principles to be followed, and by suitable changes may be used as a guide in the design of new systems.

Steam first passes from the boilers into a large drum or header. From this, a main, provided with a shut-off valve, is taken as shown; one branch is carried to the engines, while another is connected with the heating system through a reducing valve having a by-pass and cut-out valves. The exhaust from the engines connects with the large main over the boilers at a point just above the steam drum. The

branch at the right is carried outboard through a back-pressure valve which may be set to carry any desired pressure on the system. The other branch at the left passes through an oil separator into the heating system. The connections between the mains and radiators are made in the usual way, and the main return is carried back to the return pump near the floor. A false water-line or seal is obtained by elevating the pump regulator as already described. An equalizing



Fig. 125. Simple Form of Automatic Damper-Regulator, Operated by Lever Attached to Diaphragm, for Closing Dampers when Steam Pressure Reaches a Certain Point.

or balance pipe connects the top of the regulator with the low-pressure heating main, and high pressure is supplied to the pump as shown.

A sight-feed lubricator should be placed in this pipe above the automatic valve; and a valved by-pass should be placed around the regulator, for running the pump in case of accident or repairs. The oil separator should be drained through a special oil trap to a catch-basin or to the sewer; and the steam drum or any other low points

or pockets in the high-pressure piping should be dripped to the return tank through suitable traps.

Means should be provided for draining all parts of the system to the sewer, and all traps and special apparatus should be by-passed. The return-pump should always be duplicated in a plant of any size, as a safeguard against accident; and the two pumps should be run alternately, to make sure that one is always in working order.



Fig. 126. Automatic Damper-Regulator Operated by Piston Actuated by Water-Pressure.

One piece of apparatus not shown in Fig. 127 is the feed-water heater. If all of the exhaust steam can be utilized for heating purposes, this is not necessary, as the cold water for feeding the boilers may be discharged into the return pipe and be pumped in with the condensation. In summertime, however, when the heating plant is not in use, a feed-water heater is necessary, as a large amount of heat



Fig. 127. General Method of Making Pipe Connections for Exhaust-Steam Heating.

which would otherwise be wasted may be saved in this way. The connections will depend somewhat upon the form of heater used; but in general a single connection with the heating main inside the back-pressure valve is all that is necessary. The condensation from the heater should be trapped to the sewer.



THE STURTEVANT STEAM HOT BLAST APPARATUS.

Three-Quarter Housing Steam Fan and Two-Group Corrugated Sectional Base Heater.

HEATING AND VENTILATION

PART III

VACUUM SYSTEMS

Low-Pressure or Vacuum Systems. In the systems of steam heating which have been described up to this point, the pressure carried has always been above that of the atmosphere, and the action of gravity has been depended upon to carry the water of condensation back to the boiler or receiver; the air in the radiators has been forced out through air-valves by the pressure of steam back of it. Methods will now be taken up in which the pressure in the heating system is less than the atmosphere, and where the circulation through the radiators is produced by suction rather than by pressure. Systems of this kind have several advantages over the ordinary methods of circulation under pressure. *First*—no back-pressure is produced at the engines when used in connection with exhaust steam; but rather there will be a reduction of pressure due to the partial vacuum existing in the radiators. *Second*—there is a complete removal of air from the coils and radiators, so that all portions are steam-filled and available for heating purposes. *Third*—there is complete drainage through the returns, especially those having long horizontal runs; and there is absence of water-hammer. *Fourth*—smaller return pipes may be used. The two older systems of this kind in common use are known as the Webster and Paul systems; other systems of recent introduction are described in the Instruction Paper on Steam and Hot-Water Fitting.



Fig. 128. Air Outlet-Valve for Radiator, Automatically Operated by Expansion and Contraction of Vulcanite Stem.

Webster System. This consists primarily of an automatic outlet-valve on each coil and radiator, connected with some form of suction apparatus such as a pump or ejector. One type of valve used is

shown in section in Fig. 128, which replaces the usual hand-valve at the return end of the radiator. It is similar in construction to some of the air-valves already described, consisting of a rubber or vulcanite stem closing against a valve opening when made to expand by the presence of steam. When water or air fills the valve, the stem contracts and allows it to be sucked out as shown by the arrows. A perforated metal strainer surrounds the stem or expansion piece, to prevent dirt and sediment from clogging the valve.



Fig. 129. Thermostat Attached to Angle-Valve with Top Removed.

Fig. 129 shows the valve—or *thermostat*, as it is called—attached to an ordinary angle-valve with the top removed; and Fig. 130 indicates the method of draining the bottoms of risers or the ends of mains.

Fig. 131 shows another form of this valve, called a *water-seal motor*. This is used under practically the same conditions as the one described above. Its action is as follows:

Ordinarily, the seal A is down, and the central tube-valve is resting upon the seat, closing the port K and preventing direct communication between the interior of the motor-body E and the outlet L. The outlet is attached to a pipe leading to a vacuum-pump, or other draining apparatus, which exhausts the space F above the seal through the annular space between the spindle B and the inside of the central tube G. The water of condensation, accumulating in the radiator or coil, passes into the chamber E, through the inlet C, rises in the chamber, and seals the space between the seal-shell A and the sleeve of the bonnet D. The differential pressure thus created causes the seal A to rise, lifting the end of the central tube off the seat, thus opening a clear passageway for the ejection of the water of condensation.



Fig. 130. Showing Method of Draining Bottoms of Risers or Ends of Mains.

When all the water of condensation has been drawn out of the radiator, the seal and tube are reseated by gravity, thus closing the port *K*, preventing waste or loss of steam; and the pressure is equalized above and below the seal because of the absence of water. This action is practically instantaneous. When the condensation is small in quantity, the discharge is intermittent and rapid.

The space between the seal *A* and the sleeve of the bonnet *D*, and the annular space between the central tube *G* and the spindle *B*,



Fig. 131. Water-Seal Motor.

form a passageway through which the air is continually withdrawn by the vacuum pump or other draining apparatus.

The action outlined continues as long as water is present.

No adjustment whatever is necessary; the motor is entirely automatic.

One special advantage claimed for this system is that the amount of steam admitted to the radiators may be regulated to suit the requirements of outside temperature; and is possible without wate-



Fig. 132. Showing General Application of Webster System to Exhaust-Steam Heating.



DIRECT-INDIRECT SYSTEM OF WARMING, SHOWING ADJUSTABLE DAMPER.
American Radiator Company.

logging or hammering. This may be done at will by closing down on the inlet supply to the desired degree. The result is the admission of a smaller amount of steam to the radiator than it is calculated to condense normally. The condensation is removed as fast as formed, by the opening of the thermostatic valve.

The general application of this system to exhaust heating is shown in Fig. 132. Exhaust steam is brought from the engine as shown; one branch is connected with a feed-water heater, while the other is carried upward and through a grease extractor, where it branches again, one line leading outboard through a back-pressure valve and the other connecting with the heating main. A live steam connection is made through a reducing valve, as in the ordinary system. Valved connections are made with the coils and radiators in the usual manner; but the return valves are replaced by the special thermostatic valves described above.

The main return is brought down to a vacuum pump which discharges into a *return tank*, where the air is separated from the water and passes off through the vapor pipe at the top. The condensation then flows into the feed-water heater, from which it is automatically pumped back into the boilers. The cold-water feed supply is connected with the return tank, and a small cold-water jet is connected into the suction at the vacuum pump for increasing the vacuum in the heating system by the condensation of steam at this point.

Paul System. In this system the suction is connected with the air-valves instead of the returns, and the vacuum is produced by means of a steam ejector instead of a pump. The returns are carried back to a receiving tank, and pumped back to the boiler in the usual manner. The ejector in this case is called the *exhauster*.

Fig. 133 shows the general method of making the pipe connections with the radiators in this system; and Fig. 134, the details of connection at the exhauster.

A A are the returns from the air-valves, and connect with the exhausters as shown. Live steam is admitted in small quantities through the valves *B B*; and the mixture of air and steam is discharged outboard through the pipe *C*. *D D* are gauges showing the pressure in the system; and *E E* are check-valves. The advantage of this system depends principally upon the quick removal of air from the various radiators and pipes, which constitutes the principal obstruction

to circulation; the inductive action in many cases is sufficient to cause the system to operate somewhat below atmospheric pressure.

Where exhaust steam is used for heating, the radiators should



Fig. 133. Showing General Method of Making Pipe and Radiator Connections in Paul System.

be somewhat increased in size, owing to the lower temperature of the steam. It is common practice to add from 20 to 30 per cent to the sizes required for low-pressure live steam.

FORCED BLAST

In a system of forced circulation by means of a fan or blower the action is positive and practically constant under all usual conditions of outside temperature and wind action. This gives it a decided advantage over natural or gravity methods, which are af-



Fig. 134. Details of Connections at Exhauster, Paul System.

fected to a greater or less degree by changes in wind-pressure, and makes it especially adapted to the ventilation and warming of large buildings such as shops, factories, schools, churches, halls, theaters, etc., where large and definite air-quantities are required.

Exhaust Method. This consists in drawing the air out of a building, and providing for the heat thus carried away by placing

steam coils under windows or in other positions where the inward leakage is supposed to be the greatest. When this method is used, a partial vacuum is created within the building or room, and all currents and leaks are inward; there is nothing to govern definitely the quality and place of introduction of the air, and it is difficult to provide suitable means for warming it.

Plenum Method. In this case the air is forced into the building, and its quality, temperature, and point of admission are completely under control. All spaces are filled with air under a slight pressure, and the leakage is outward, thus preventing the drawing of foul air into the room from any outside source. But above all, ample opportunity is given for properly warming the air by means of heaters, either in direct connection with the fan or in separate passages leading to the various rooms.

Form of Heating Surface. The best type of heater for any particular case will depend upon the volume and final temperature of the air, the steam pressure, and the available space. When the air is to be heated to a high temperature for both warming and ventilating a building, as in the case of a shop or mill, heaters of the general form shown in Figs. 135, 136, and 137 are used. These may also be adapted to all classes of work by varying the proportions as required. They can be made shallow and of large superficial area, for the comparatively low temperatures used in purely ventilating work; or deeper, with less height and breadth, as higher temperatures are required.

Fig. 135 shows in section a heater of this type, and illustrates the circulation of steam through it. It consists of sectional cast-iron bases with loops of wrought-iron pipe connected as shown. The steam enters the upper part of the bases or headers, and passes up one side of the loops, then across the top and down on the other side, where the condensation is taken off through the return drip, which is separated from the inlet by a partition. These heaters are made up in sections of 2 and 4 rows of pipes each. The height varies from $3\frac{1}{2}$ to 9 feet, and the width from 3 feet to 7 feet in the standard sizes. They are usually made up of 1-inch pipe, although $1\frac{1}{4}$-inch is commonly used in the larger sizes. Fig. 136 shows another form; in this case all the loops are made of practically the same length by the special form of construction shown. This is claimed to prevent the short-

circuiting of steam through the shorter loops, which causes the outer pipes to remain cold. This form of heater is usually encased in a



Fig. 135. Showing Circulation of Steam in Large Coil-Pipe Radiator for Heating Mills, Shops, etc.

sheet-steel housing as shown in Fig. 137, but may be supported on a foundation between brick walls if desired.

Fig. 138 shows a special form of heater particularly adapted to ventilating work where the air does not have to be raised above 70 or 80 degrees. It is made up of 1-inch wrought-iron pipe connected



Fig. 136. Another Type of Large Coil Radiator for Mills, Factories, etc.

with supply and return headers; each section contains 14 pipes, and they are usually made up in groups of 5 sections each. These coils are supported upon tee-irons resting upon a brick foundation. Heat-

ers of this form are usually made to extend across the side of a room with brick walls at the sides, instead of being encased in steel housings.

Fig. 139 shows a front view of a cast-iron sectional heater for use under the same conditions as the pipe heaters already described. This heater is made up of several banks of sections, like the one shown in the cut, and enclosed in a steel-plate casing.

Cast-iron indirect radiators of the pin type are well adapted for use in connection with mechanical ventilation, and also for heating



Fig. 137. Large Coil-Pipe Radiator Encased in Sheet-Steel Housing.

where the air-volume is large and the temperature not too high, as in churches and halls. They make a convenient form of heater for schoolhouse and similar work, for, being shallow, they can be supported upon I-beams at such an elevation that the condensation will be returned to the boilers by gravity.

In the case of vertical pipe heaters, the bases are below the water-line of the boilers, and the condensation must be returned by the use of pumps and traps.

Efficiency of Pipe Heaters. The efficiency of the heaters used in connection with forced blast varies greatly, depending upon the temperature of the entering air, its velocity between the pipes, the temperature to which it is raised, and the steam pressure carried in the heater. The general method in which the heater is made up is also an important factor.

In designing a heater of this kind, care must be taken that the free area between the pipes is not contracted to such an extent that an excessive velocity will be required to pass the given quantity of



Fig. 138. Heater Especially Adapted to Ventilation where Air does not Have to be Heated above 70 to 80 degrees F.

air through it. In ordinary work it is customary to assume a velocity of 800 to 1,000 feet per minute; higher velocities call for a greater pressure on the fan, which is not desirable in ventilating work.

In the heaters shown, about .4 of the total area is free for the passage of air; that is, a heater 5 feet wide and 6 feet high would have a total area of $5 \times 6 = 30$ square feet, and a free area between the pipes of $30 \times .4 = 12$ square feet. The depth or number of rows of pipe does not affect the free area, although the friction is increased and additional work is thrown upon the fan. The efficiency in any

given heater will be increased by increasing the velocity of the air through it; but the final temperature will be diminished; that is, a larger quantity of air will be heated to a lower temperature in the second case, and, while the total heat given off is greater, the air-quantity increases more rapidly than the heat-quantity, which causes a drop in temperature.

Increasing the number of rows of pipe in a heater, with a constant air-quantity, increases the final temperature of the air, but diminishes the efficiency of the heater, because the average difference in temperature between the air and the steam is less. Increasing the steam pressure in the heater (and consequently its temperature) increases both the final temperature of the air and the efficiency of the heater. Table XXX has been prepared from different tests, and may be used as a guide in computing probable results under ordinary working conditions. In this table it is assumed that the air enters the heater at a temperature of zero and passes between the pipes with a velocity of 800 feet per minute. Column 1 gives the number of rows of pipe in the heater, ranging from 4 to 20 rows; and columns 2, 3, and 4, show the final temperature to which the entering air will be raised from zero under various pressures. Under 5 pounds pressure, for example, the rise in temperature ranges from 30 to 140 degrees; under 20 pounds, 35 to 150 degrees; and under 60 pounds, 45 to 170 degrees. Columns 5, 6, and 7 give approximately the corresponding efficiency of the heater. For example, air passing through a heater 10 pipes deep and carrying 20 pounds pressure, will be raised to a temperature of 90 degrees, and the heater will have an efficiency of 1,650 B. T. U. per square foot of surface per hour.



Fig. 139. Front View of Cast-Iron Sectional Heater. The Banks of Sections are Enclosed in a Steel-Plate Casing.

TABLE XXX

Data Concerning Pipe Heaters

Temperature of entering air, zero.—Velocity of air between the pipes, 800 feet per minute.

Rows of Pipe Deep	Temperature to which Air will be Raised from Zero			Efficiency of Heating Surface in B. T. U., per Square Foot per Hour		
	Steam Pressure in Heater			Steam Pressure in Heater		
	5 lbs.	20 lbs.	60 lbs.	5 lbs.	20 lbs.	60 lbs.
4	30	35	45	1,600	1,800	2,000
6	50	55	65	1,600	1,800	2,000
8	65	70	85	1,500	1,650	1,850
10	80	90	105	1,500	1,650	1,850
12	95	105	125	1,500	1,650	1,850
14	105	120	140	1,400	1,500	1,700
16	120	130	150	1,400	1,500	1,700
18	130	140	160	1,300	1,400	1,600
20	140	150	170	1,300	1,400	1,600

For a velocity of 1,000 feet, multiply the *temperatures* given in the table by .9, and the *efficiencies* by 1.1.

Example. How many square feet of radiation will be required to raise 600,000 cubic feet of air per hour from zero to 80 degrees, with a velocity through the heater of 800 feet per minute and a steam pressure of 5 pounds? What must be the total area of the heater front, and how many rows of pipes must it have?

Referring back to the formula for heat required for ventilation, we have

$$\frac{600{,}000 \times 80}{55} = 872{,}727 \text{ B. T. U. required.}$$

Referring to Table XXX, we find that for the above conditions a heater 10 pipes deep is required, and that an efficiency of 1,500 B. T. U. will be obtained. Then $\frac{872{,}727}{1{,}500} = 582$ square feet of surface required, which may be taken as 600 in round numbers. $\frac{600{,}000}{60} = 10{,}000$ cubic feet of air per minute; and $\frac{10{,}000}{800} = 12.5$ square feet of free area required through the heater. If we assume .4 of the total heater front to be free for the passage of air, then $\frac{12.5}{.4} = 31$ square feet, the total area required.

For convenience in estimating the approximate dimensions of a heater, Table XXXI is given. The standard heaters made by different manufacturers vary somewhat, but the dimensions given in the table represent average practice. Column 3 gives the square feet of heating surface in a single row of pipes of the dimensions given in columns 1 and 2; and column 4 gives the free area between the pipes.

TABLE XXXI

Dimensions of Heaters

Width of Section	Height of Pipes	Square Feet of Surface	Free Area through Heater in Sq. Ft.
3 feet	3 feet 6 inches	20	4.2
3 "	4 " 0 "	22	4.8
3 "	4 " 6 "	25	5.4
3 "	5 " 0 "	28	6.0
4 "	4 " 6 "	34	7.2
4 "	5 " 0 "	38	8.0
4 "	5 " 6 "	42	8.8
4 "	6 " 0 "	45	9.6
5 "	5 " 6 "	52	11.0
5 "	6 " 0 "	57	12.0
5 "	6 " 6 "	62	13.0
5 "	7 " 0 "	67	14.0
6 "	6 " 6 "	75	15.6
6 "	7 " 0 "	81	16.8
6 "	7 " 6 "	87	18.0
6 "	8 " 0 "	92	19.2
7 "	7 " 6 "	98	21.0
7 "	8 " 0 "	108	22.4
7 "	8 " 6 "	109	23.8
7 "	9 " 0 "	116	25.2

In calculating the total height of the heater, add 1 foot for the base.

These sections are made up of 1-inch pipe, except the last or 7-foot sections, which are made of 1¼-inch pipe.

Using this table in connection with the example just given, we should look in the last column for a section having a free area of 12.5 square feet; here we find that a 5 feet by 6 feet 6 inches section has a free opening of 13 square feet and a radiating surface of 62 square

feet. The conditions call for 10 rows of pipes and $10 \times 62 = 620$ square feet of radiating surface, which is slightly more than called for, but which would be near enough for all practical purposes.

EXAMPLE FOR PRACTICE

Compute the dimensions of a heater to warm 20,000 cubic feet of air per minute from 10 below zero to 70 degrees above, with 5 pounds steam pressure.

ANS. 1,164 sq. ft. of rad. surface 10 pipes deep.
25 sq. ft. free area through heater.

Use twenty 5 ft. by 6 ft. sections, side by side, which gives 24 square feet area and 1,140 square feet of surface.

The general method of computing the size of heater for any given building is the same as in the case of indirect heating. First obtain the B. T. U. required for ventilation, and to that add the heat loss through walls, etc.; and divide the result by the efficiency of the heater under the given conditions.

Example. An audience hall is to be provided with 400,000 cubic feet of air per hour. The heat loss through walls, etc., is 250,000 B.T.U. per hour in zero weather. What will be the size of heater, and how many rows of pipe deep must it be, with 20 pounds steam pressure?

$$\frac{400{,}000 \times 70}{55} = 509{,}090 \text{ B. T. U. for ventilation.}$$

Therefore 250,000 + 509,090 = 759,090 B. T. U., total to be supplied.

We must next find to what temperature the entering air must be raised in order to bring in the required amount of heat, so that the number of rows of pipe in the heater may be obtained and its corresponding efficiency determined. We have entering the room for purposes of ventilation, 400,000 cubic feet of air every hour, at a temperature of 70 degrees; and the problem now becomes: To what temperature must this air be raised to carry in 250,000 B. T. U. additional for warming?

We have learned that 1 B. T. U. will raise 55 cubic feet of air 1 degree. Then 250,000 B. T. U. will raise $250{,}000 \times 55$ cubic feet of air 1 degree.

$$\frac{250{,}000 \times 55}{400{,}000} = 34 +$$

The air in this case must be raised to 70 + 34 = 104 degrees, to provide

for both ventilation and warming. Referring to Table XXX, we find that a heater 12 pipes deep will be required, and that the corresponding efficiency of the heater will be 1,650 B. T. U. Then $\frac{759,090}{1,650}$ = 460 square feet of surface required.

Efficiency of Cast-Iron Heaters. Heaters made up of indirect pin radiators of the usual depth, have an efficiency of at least 1,500 B. T. U., with steam at 10 pounds pressure, and are easily capable of warming air from zero to 80 degrees or over when computed on this basis. The free space between the sections bears such a relation to the heating surface that ample area is provided for the flow of air through the heater, without producing an excessive velocity.

The heater shown in Fig. 139 may be counted on for an efficiency at least equal to that of a pipe heater; and in computing the depth, one row of sections may be taken as representing 4 rows of pipe.

Pipe Connections. In the heater shown in Fig. 135, all the sections take their supply from a common header, the supply pipe connecting with the top, and the return being taken from the lower division at the end, as shown.

In Fig. 137 the base is divided into two parts, one for live steam, and the other for exhaust. The supply pipes connect with the upper compartments, and the drips are taken off as shown. Separate traps should be provided for the two pressures.

The connections in Fig. 136 are similar to those just described, except that the supply and return headers, or bases, are drained through separate pipes and traps, there being a slight difference in pressure between the two, which is likely to interfere with the proper drainage if brought into the same one. This heater is arranged to take exhaust steam, but has a connection for feeding in live steam through a reducing valve if desired, the whole heater being under one pressure.

In heating and ventilating work where a close regulation of temperature is required, it is usual to divide the heater into several sections, depending upon its size, and to provide each with a valve in the supply and return. In making the divisions, special care should be taken to arrange for as many combinations as possible. For example, a heater 10 pipes deep may be made up of three sections—one of

2 rows, and two of 4 rows each. By means of this division, 2, 4, 6, 8, or 10 rows of pipe can be used at one time, as the outside weather conditions may require.

When possible, the return from each section should be provided with a water-seal two or three feet in depth. In the case of overhead heaters, the returns may be sealed by the water-line of the boiler or by the use of a special water-line trap; but vertical pipe heaters resting on foundations near the floor are usually provided with siphon loops extending into a pit. If this arrangement is not convenient, a separate trap should be placed on the return from each section. The main return, in addition to its connection with the boiler or



Fig. 140. Heater Made Up of Interchangeable Sections.

pump receiver, should have a connection with the sewer for blowing out when steam is first turned on. Sometimes each section is provided with a connection of this kind.

Large automatic air-valves should be connected with each section; and it is well to supplement these with a hand pet-cock, unless individual blow-off valves are provided as described above.

If the fan is driven by a steam engine, provision should be made for using the exhaust in the heater; and part of the sections should be so valved that they may be supplied with either exhaust or live steam.

Fig. 140 shows an arrangement in which all of the sections are interchangeable.

From 50 to 60 square feet of radiating surface should be provided in the exhaust portion of the heater for each engine horse-power, and should be divided into at least three sections, so that it can be proportioned to the requirements of different outside temperatures.

Pipe Sizes. The sizes of the mains and branches may be computed from the tables already given in Part II, taking into account the higher efficiency of the heater and the short runs of piping.

Table XXXII, based on experience, has been found to give satisfactory results when the apparatus is near the boilers. If the main supply pipe is of considerable length, its diameter should be checked by the method previously given.

TABLE XXXII

Pipe Sizes

Square Feet of Surface	Diameter of Steam Pipe	Diameter of Return
150	2 inches	1¼ inches
300	2½ "	1½ "
500	3 "	2 "
700	3½ "	2 "
1,000	4 "	2½ "
2,000	5 "	2½ "
3,000	6 "	3 "

Heaters of the patterns shown in Figs. 135, 136, and 137 are usually tapped at the factory for high or low pressure as desired, and these sizes may be followed in making the pipe connections.

The sizes marked on Fig. 136 may be used for all ordinary work where the pressure runs from 5 to 20 pounds; for pressures above that, the supply connections may be reduced one size.

FANS

There are two types of fans in common use, known as the *centrifugal fan* or *blower*, and the *disc fan* or *propeller*. The former consists of a number of straight or slightly curved blades extending radially from an axis, as shown in Fig. 141. When the fan is in motion, the air in contact with the blades is thrown outward by the action of centrifugal force, and delivered at the circumference or

periphery of the wheel. A partial vacuum is thus produced at the center of the wheel, and air from the outside flows in to take the place of that which has been discharged.

Fig. 142 illustrates the action of a centrifugal fan, the arrows showing the path of the air. This type of fan is usually enclosed in a steel-plate casing of such form as to provide for the free movement of the air as it escapes from the periphery of the wheel. An opening in the circumference of the casing serves as an outlet into the distributing ducts which carry the air to the various rooms to be ventilated.



Fig. 141. Centrifugal Fan or Blower.

A fan with casing, is shown in Fig. 143; and a combined heater and fan, with direct-connected engine, is shown in Fig. 144.

The discharge opening can be located in any position desired, either up, down, top horizontal, bottom horizontal, or at any angle.



Fig. 142. Illustrating Action of Centrifugal Fan. The Arrows Show the Path of the Air.

Where the height of the fan room is limited, a form called the *three-quarter housing* may be used, in which the lower part of the casing is replaced by a brick or cemented pit extending below the floor-level as shown in Fig. 145.

Another form of centrifugal fan is shown in Fig. 146. This is known as the *cone fan*, and is commonly placed in an opening in a brick wall, and discharges air from its entire periphery into a room called a *plenum chamber*, with which the various distributing ducts connect.

This fan is often made double by placing two wheels back to



FRONT VIEW OF SECTIONAL STEAM AND HOT-WATER BOILER
Giblin & Co., Utica, N. Y.



SECTIONAL STEAM AND HOT-WATER BOILER
Cut Open to Show Course Taken by Hot Gases and by Water

back and surrounding them with a steel casing in a similar manner to the one shown in Fig. 143.

Cone fans are particularly adapted to church and schoolhouse work, as they are capable of moving large volumes of air at moderate speeds.

Fig. 147 shows a form of small direct-connected exhauster commonly used for ventilating toilet-rooms, chemical hoods, etc.

Centrifugal fans are used almost exclusively for supplying air for the ventilation of buildings, and for forced-blast heating. They are also used as exhausters for removing the air from buildings in cases where there is considerable resistance due to the small size or excessive length of the discharge ducts.



Fig. 143. Centrifugal Fan with Casing.

General Proportions. The general form of a fan wheel is shown in Fig. 141, which represents a single spider wheel with curved blades. Those over 4 feet in diameter usually have two spiders, while fans of large size are often provided with three or more. The number of floats or blades commonly varies from six to twelve, depending upon the diameter of the fan. They are made both curved and straight; the former, it is claimed, run more quietly, but, if curved too much, will not work so well against a high pressure as the latter form.

The relative proportions of a fan wheel vary somewhat in the case of different makes. The following are averages taken from fans of different sizes as made by several well-known manufacturers for general ventilating and similar work:

Width of fan at center = Diameter × .52
Width of fan at perimeter = Width at center × .8
Diameter of inlet = Diameter of wheel × .68



Fig. 144. Combined Heater and Centrifugal Fan with Direct-Connected Engine.



Fig. 145. Centrifugal Fan in "Three-Quarter Housing." Used where Headroom is Limited; Extra Space Provided by Pit under Floor-Level.

Fans are made both with double and with single inlets, the former being called *blowers* and the latter *exhausters*. The size of a fan is commonly expressed in inches, which means the approximate height of the casing of a full-housed fan. The diameter of the wheel is usually expressed in feet, and can be found in any given case by dividing the size in inches by 20. For example, a 120-inch fan has a wheel $120 \div 20 = 6$ feet in diameter.



Fig. 146. "Cone" Fan. Discharges through Opening in Wall into a "Plenum Chamber" Connecting with Distributing Ducts.

Theory of Centrifugal Fans. The action of a fan is affected to such an extent by the various conditions under which it operates, that it is impossible to give fixed rules for determining the exact results to be expected in any particular instance. This being the case, it seems best to take up the matter briefly from a theoretical

standpoint, and then show what corrections are necessary in the case of a given fan under actual working conditions.

There are various methods for determining the capacity of a fan at different speeds, and the power necessary to drive it; each manufacturer has his own formulæ for this purpose, based upon tests of his own particular fans. The methods given here apply in a general way to fans having proportions which represent the *average* of several standard makes; and the results obtained will be



Fig. 147. Small, Direct-Connected Exhauster for Ventilating Toilet-Rooms, Chemical Hoods, etc.

found to correspond well with those obtained in practice under ordinary conditions.

As already stated, the rotation of a fan of this type sets in motion the air between the blades, which, by the action of centrifugal force, is delivered at the periphery of the wheel into the casing surrounding it. As the velocity of flow through the discharge outlet depends upon the pressure or head within the casing, and this in turn upon the velocity of the blades, it becomes necessary to examine briefly into the relations existing between these quantities.

Pressure. The pressure referred to in connection with a fan, is that in the discharge outlet, and represents the force which drives the air through the ducts and flues. The greater the pressure with a given resistance in the pipes, the greater will be the volume of air delivered; and the greater the resistance, the greater the pressure required to deliver a given quantity.

The pressure within a fan casing is caused by the air being thrown from the tips of the blades, and varies with the velocity of rotation; that is, the higher the speed of the fan, the greater will be the pressure produced. Where the dimensions of a fan and casing are properly proportioned, the velocity of air-flow through the outlet will be the same as that of the tips of the blades, and the pressure within the casing will be that corresponding to this velocity.

Table XXXIII gives the necessary speed for fans of different diameters to produce different pressures, and also the velocity of air-flow due to these pressures.

TABLE XXXIII

Fan Speeds, Pressures, and Velocities of Air-Flow

Pressure, in Ounces per Sq. Inch	Diameter of Fan Wheel, in Feet								Velocity of Flow, in Feet per Minute
	3	4	5	6	7	8	9	10	
	Revolutions per Minute								
¼	274	206	164	137	117	103	92	82	2,585
⅜	336	252	202	168	144	126	112	101	3,165
½	338	291	232	194	166	146	129	116	3,653
¾	433	325	260	217	186	163	144	130	4,084

The application of this table will be made plain by a brief discussion of *blast area.*

Blast Area. When the outlet from a fan casing is small, the air will pass out with a velocity equal to that of the tips of the blades; and the pressure within the casing will be that corresponding to the tip velocity. That is, a 3-foot fan wheel revolving at a speed of 274 revolutions per minute will produce a pressure within the fan casing of ¼ ounce per square inch, and will cause a velocity of flow through the discharge outlet of 2,585 feet per minute (see Table XXXIII).

Now, if the opening be slowly increased, while the speed of the fan remains constant, the air will continue to flow with the same velocity until a certain area of outlet is reached. If the outlet be still further increased, the pressure in the casing will begin to drop, and the velocity of outflow become less than the tip velocity. The effective area of outlet at the point when this change begins to take place, is called the *blast area* or *capacity area* of the fan. This varies somewhat with different types and makes of fans; but for the common form of blower, it is approximately $\frac{1}{3}$ of the projected area of the fan opening at the periphery—that is, $\frac{Dw}{3}$, in which D is the diameter of the fan wheel, and w its width at the periphery. It has already been stated under "General Proportions" that $W = .52\,D$, and $w = .8\,W$; so that we may write $A = \frac{D \times .8\,W}{3} = \frac{D \times .8 \times .52\,D}{3} = .14\,D^2$, in which A = the blast area, and D the diameter of the fan.

As a matter of fact, the outlet of a fan casing is always made larger than the blast area; and the result is that the pressure drops below that due to the tip velocity, and the velocity of flow through the outlet becomes less than that given in the last column of Table XXXIII for any given speed of fan.

Effective Area of Outlet. The size of discharge outlet varies somewhat for different makes; but for a large number of fans examined it was found to average about 2.22 times the blast area as computed by the above method. When air or a liquid flows through an orifice, the stream is more or less contracted, depending upon the form of the orifice.

In the case of a fan outlet, the *effective area* may be taken as about .8 of the actual area. This makes the effective area of a fan outlet equal to $.8 \times 2.22 = 1.78$ times the blast area.

Table XXXIV gives the effective areas of fans of different diameter as computed by the above method. That is, Effective area $= .14D^2 \times 1.78 = .25D^2$.

Speed. We have seen that when the discharge outlet is made larger than the blast area, the pressure within the fan casing drops below that due to the tip velocity; so that, in order to bring the pressure up to its original point, the speed of the fan must be increased above that given in Table XXXIII.

TABLE XXXIV
Effective Areas of Fans

Diameter of Fan, in Feet	Effective Area of Outlet, in Square Feet
3	2.3
4	4.0
5	6.3
6	9.1
7	12.3
8	16.0
9	20.4
10	25.2

Tests upon a fan of practically the same proportions as those previously given, show that, when the effective outlet area is made 1.78 the blast area, the speed must be increased 1.2 times in order to keep the pressure at the same point as when the outlet is equal to or less than the blast area.

Capacity. The capacity of a fan is the volume of air discharged in a given time, and is usually expressed in cubic feet per minute. It is equal to the effective area of discharge *multiplied by* the velocity of flow through it.

Example. At what speed must a 6-foot fan be run to maintain a pressure of ½ ounce, and what volume of air will be delivered per minute?

From Table XXXIII we find that a 6-foot fan must run at a speed of 194 revolutions per minute to maintain the given pressure when the outlet is equal to the blast area, or 194 × 1.2 = 233 revolutions per minute under actual conditions. The velocity of flow through the outlet at ½ ounce pressure, is 3,653 feet per minute (Table XXXIII); and the effective area of outlet of a 6-foot fan is 9.1 square feet (Table XXXIV). Therefore the volume of air delivered per minute is equal to 9.1 × 3,653 = 33,242 cubic feet.

Example. It is desired to move 52,000 cubic feet of air per minute at a pressure of ¼ ounce. What size and speed of fan will be required? Looking in Table XXXIII, we find that the velocity through the fan outlet for ¼-ounce pressure is 2,585, which calls for an outlet area of 52,000 ÷ 2,585 = 20.1 square feet. Looking in Table XXXIV, we find this corresponds very nearly to a 9-foot fan, which is the size called for. Referring again to Table XXXIII, the speed necessary to maintain the required pressure under the given conditions is found to be 92 × 1.2 = 110 revolutions per minute.

Effect of Resistance. Thus far it has been assumed that the fan was discharging into the open air against atmospheric pressure. The effect of adding a resistance by connecting it with a series of ventilating ducts, is the same as partially closing the discharge outlet. Carefully conducted tests upon this type of fan have shown that the reduction of air-flow is very nearly in proportion to the reduction of the discharge area. That is, if the outlet of the fan is closed to one-half its original area, the quantity of air discharged will be practically one-half that delivered by the fan with a free opening. The effect of attaching a fan to the ventilating flues of a building like a schoolhouse, church, or hall, where the ducts have easy bends and where the velocity of air-flow through them is not over 1,000 to 1,200 feet per minute, is about the same as reducing the outlet 20 per cent. For factories with deep heaters and smaller ducts, where the velocity runs up to 1,500 or 1,800 feet per minute, the effect is equivalent to closing the outlet at least 30 per cent, and even more in very large buildings.

For schoolhouses and similar work a fan should not be run much above the speed necessary to maintain a pressure of $\frac{3}{8}$ ounce at the outlet. Higher speeds are accompanied with greater expenditure of power, and are likely to produce a roaring noise or to cause vibration. A much lower speed does not provide sufficient pressure to give proper control of the air-distribution during strong winds. For factories, a higher pressure of $\frac{5}{8}$ to $\frac{3}{4}$ ounce is more generally employed.

Actually the pressure is increased slightly by restricting the outlet at constant speed; but this is seldom taken into account in ventilating work, as volume, speed, and power are the quantities sought.

Example. A school building requires 32,000 cubic feet of air per minute. What size and speed of fan will be required?

If the resistance of the ducts and flues is equivalent to cutting down the discharge outlet 20 per cent, we must make the computations for a fan which will discharge 32,000 ÷ .8 = 40,000 cubic feet in free air.

Looking in Table XXXIII, we find the velocity for $\frac{3}{8}$-ounce pressure to be 3,165 feet per minute; therefore the size of fan outlet must be 40,000 ÷ 3,165 = 12.6 square feet, which, from Table XXXIV, we find corresponds very nearly to a 7-foot fan.

Referring again to Table XXXIII, the required speed is found to be 144 × 1.2 = 173 revolutions per minute.

Example. A factory requires 21,000 cubic feet of air per minute for warming and ventilating. What size and speed of fan will be required?

21,000 ÷ .7 = 30,000, the volume to provide for with a fan discharging into free air. Assuming a pressure of $\frac{5}{8}$ ounce, the velocity will be 4,084 feet per minute, from which the area of outlet is found to be 30,000 ÷ 4,084 = 7.3 square feet. This, we find, does not correspond to any of the sizes given in Table XXXIV. As standard fans are not usually made in half-sizes above 5 feet, we shall use a 5-foot fan and run it at a higher speed.

A 5-foot fan has an outlet area of 6.3 square feet, and at $\frac{5}{8}$-ounce pressure it would deliver 6.3 × 4,084 = 25,729 cubic feet of air per minute, at a speed of 260 × 1.2 = 312 revolutions per minute. The volume of air delivered by a fan varies approximately as the speed; so, in order to bring the volume up to the required 30,000, the speed must be increased by the ratio 30,000 ÷ 25,729 = 1.16, making the final speed 312 × 1.16 = 362 revolutions per minute. In the same way, a 6-foot fan could have been used and run at a proportionally lower speed.

Power Required. The work done by a fan in moving air is represented by the pressure exerted, *multiplied by* the distance through which it acts.

Table XXXV gives the horse-power required for moving the air which will flow through each square foot of the effective outlet area, under different pressures.

This table gives only the power necessary for *moving* the air, and does not take into consideration the friction of the air in passing through the fan, nor that of the fan itself.

The efficiency of a fan varies with the speed, the size of outlet, and the pressure against which the fan is working. Under favorable conditions, with properly proportioned fans, we may count on an efficiency of about .35.

Example. What horse-power will be required to drive an 8-foot fan at such a speed as to maintain a pressure of $\frac{1}{2}$ ounce?

An 8-foot fan has an outlet area of 16 square feet (Table XXXIV); and from Table XXXV we find that .5 horse-power is required to move the air which will flow through each square foot of outlet under

TABLE XXXV

Power Required for Moving Air under Different Pressures

Pressure in Ounces per Square Inch	Horse-Power for Moving Air which will Flow through Each Square Foot of Effective Outlet Area
¼	.18
⅜	.33
½	.50
⅝	.70

½-ounce pressure. Therefore the power required to move the air alone is $16 \times .5 = 8$, and the total horse-power is $8 \div .35 = 23$.

Effect of Resistance. In the above case, it is assumed that the fan is discharging into free air. If a resistance is added, the effect is the same as partially closing the outlet, and the volume of air moved and the horse-power required are both reduced in very nearly the same proportion. This reduction, as already stated, may be taken as 20 per cent for schoolhouse and similar work, and 30 per cent for factories.

For example, if the fan just considered was to be used for ventilating a schoolhouse, delivering air under a pressure of ½ ounce, the necessary horse-power would be only $23 \times .8 = 18.4$. If used for a factory, delivering air under a pressure of ⅝ ounce, the required horse-power would be $\frac{16 \times .7}{.35} \times .7 = 22.3$.

General Rules. The methods above described may be briefly expressed as follows:

Capacity—$Q = A \times v \times F$, in which

Q = Cubic feet of air per minute;

A = Effective area of fan outlet (Table XXXIV);

v = Velocity of flow through outlet;

$F = \begin{cases} 3{,}165 \text{ (⅜-ounce pressure) for schoolhouses, etc.;} \\ 4{,}084 \text{ (⅝-ounce pressure) for factories;} \end{cases}$

$F = \begin{cases} .8 \text{ for schoolhouses, etc.;} \\ .7 \text{ for factories.} \end{cases}$

Speed—Take the speed from Table XXXIII, corresponding to the given pressure and size of fan, and multiply by 1.2.

Horse-Power—H.P. $= \frac{A \times p \times F}{.35}$, in which

H.P. = Horse-power;

A = Effective area of fan outlet;

p = Horse-power to move air which will flow through 1 square foot of fan outlet under given pressure (Table XXXV);

$= \begin{cases} .33 \text{ for schoolhouses, etc.;} \\ .7 \text{ for factories.} \end{cases}$

$F = \begin{cases} .8 \text{ for schoolhouses, etc.;} \\ .7 \text{ for factories.} \end{cases}$

EXAMPLES

1. A schoolhouse requires an air-supply of 30,000 cubic feet per minute. What will be the required size of fan, its speed, and the H. P. of engine to drive it?

ANS. { 7 ft. in diameter. 173 r. p. m. 9 H. P.

2. What will be the size and speed of fan, and horse-power of engine, to heat and ventilate a factory requiring 1,080,000 cubic feet of air per hour?

ANS. { 6 ft. in diameter. 260 r. p. m. 8.8 H. P.

General Relations. The following general relations between the volume, pressure, and power will often be found useful in deciding upon the size of a fan:

(1) The volume of air delivered varies *directly* as the speed of the fan; that is, doubling the number of revolutions doubles the volume of air delivered.

(2) The pressure varies as the *square* of the speed. For example, if the speed is doubled, the pressure is increased $2 \times 2 = 4$ times; etc.

(3) The power required to run the fan varies as the *cube* of the speed. Thus, if the speed is doubled, the power required is increased $2 \times 2 \times 2 = 8$ times; etc.

The value of a knowledge of these relations may be illustrated by the following example:

Suppose for any reason it were desired to double the volume of air delivered by a certain fan. At first thought we might decide to use the same fan and run it twice as fast; but when we come to consider the power required, we should find that this would have to be increased 8 times, and it would probably be much cheaper in the long run to put in a larger fan and run it at lower speed.

Disc or Propeller Fans. When air is to be moved against a very slight resistance, as in the case of exhaust ventilation, the disc or propeller type of wheel may be used. This is shown in different forms in Figs. 149 and 150. This type of fan is light in construction, requires but little power at low speeds, and is easily erected. It may be

conveniently placed in the attic or upper story of a building, where it may be driven either by a direct- or belt-connected electric motor. Fig. 148 shows a fan equipped with a direct-connected motor, and Fig. 151 the general arrangement when a belted motor is used. These fans are largely used for the ventilation of toilet and smoking rooms, restaurants, etc., and are usually mounted in a wall opening, as shown in Fig. 151. A damper should always be provided for shutting off the opening when the fan is not in use. The fans shown in Figs. 149 and 150 are provided with pulleys for belt connection.



Fig. 148. Propeller Fan Direct-Connected to Motor.

Fans of this kind are often connected with the main vent flues of large buildings, such as schools, halls, churches, theaters, etc., and are especially adapted for use in connection with gravity heating systems. They are usually run by electric motors, and as a rule are placed in positions where an engine could not be connected, and also in buildings where steam pressure is not available.

Capacity of Disc Fans. The capacity of a disc fan varies greatly with the type and the conditions under which it operates. The rated

capacities usually given in catalogues are for fans revolving in free air—that is, mounted in an opening without being connected with ducts or subjected to other frictional resistance.

As the capacity and necessary power are so dependent upon the resistance to be overcome, it is difficult to give definite rules for determining them. The following data, based upon actual tests,



Fig. 149. Another Form of Propeller Fan, with Special Type of Blade.

apply to fans working against a resistance such as would be produced by connecting with a system of ducts of medium length through which the air was drawn at a velocity not greater than 600 or 800 feet per minute. Under these conditions, a good type of fan will propel the air in a direction parallel to the shaft a distance equal to about .7 of its diameter at each revolution; and from this we have the equation:

$$Q = .7\ D \times R \times A,$$

in which

Q = Cubic feet of air discharged per minute;
D = Diameter of fan, in feet;
R = Revolutions per minute;
A = Area of fan, in square feet.

In order to obtain the best results, the linear velocity of air-flow through the fan should range from 800 to 1,200 feet per minute.

Table XXXVI gives the revolutions per minute for fans of different diameter to produce a linear velocity of 1,000 feet, the volume delivered at this speed, and the horse-power required.

The horse-power is computed by allowing .14 H. P. for each 1,000 cubic feet of air moved, when the velocity through the fan is 800 feet per minute; .16 H. P. for 1,000 feet velocity; and .18 H. P. for 1,200 feet velocity. These factors are empirical, and based on tests.



Fig. 150. Propeller Fan with Wheel on Shaft for Belt Connection.



Fig. 151. Fan Belt-Connected to Motor.

Example. Assuming a velocity of 800 feet per minute through a 4-foot fan, what volume will be delivered per minute, and what speed and horse-power will be required?

TABLE XXXVI

Disc Fans, their Capacity, Speed, etc.

Dia. of Fan, in Inches	Rev. per Min.	Cubic Feet of Air Moved	Horse-Power Required
18	952	1,700	.27
24	716	3,100	.50
30	572	4,900	.78
36	476	7,100	1.2
42	408	9,400	1.5
48	343	12,000	1.9
54	317	15,800	2.5
60	286	19,400	3.1
72	238	28,300	4.5

The area of a 4-foot fan is 12.5 square feet; and at 800 velocity the volume would be $12.5 \times 800 = 10{,}000$ cubic feet. Next solve for the speed by the equation $Q = .7D \times R \times A$, which, when transposed, takes the form

$$R = \frac{Q}{.7\,D \times A}.$$

Substituting the known quantities, we have:

$$R = \frac{10{,}000}{.7 \times 4 \times 12.5} = 286.$$

The horse-power is $10 \times .14 = 1.4$.

Fan Engines. A simple, quiet-running engine is desirable for use in connection with a fan or blower. The engine may be either horizontal or vertical; and for schoolhouse and similar work, should be provided with a large cylinder, so that the required power may be developed without carrying a boiler pressure much above 30 pounds. In some cases, cylinders of such size are used that a boiler pressure of 12 or 15 pounds is sufficient. The quantity of steam which an engine consumes is of minor importance, as the exhaust can be turned into the coils and used for heating purposes. If space allows, the engine should always be belted to the fan. Where it is direct-connected, as in Fig. 144, there is likely to be trouble from noise, as any slight looseness or pounding in the engine will be communicated to the air-ducts, and the sound will be carried to the rooms

above. Figs. 152 and 153 show common forms of fan engines. The latter is especially adapted to this purpose, as all bearings are enclosed



Fig. 152 A Common Form of Fan Engine.

and protected from dust and grit. A horizontal engine for fan use is shown in Fig. 154.

In case an engine is belted, the distance between the shafts of the fan and engine should not in general be much less than 10 feet



GROUP OF VENTO CAST-IRON HOT-BLAST HEATERS, TWENTY SECTIONS LONG
American Radiator Co., Chicago, Ill.

for fans up to 7 or 8 feet in diameter, and 12 feet for those of larger size. When possible, the tight or driving side of the belt should be at the bottom, so that the loose side, coming on top, will tend to wrap around the pulleys and so increase the arc of contact.

Motors. Electric motors are especially adapted for use in connection with fans. This method of driving is more expensive



Fig. 153. Another Form of Fan Engine, with Bearings Enclosed to Protect Them from Dust and Grit.

than by the use of an engine, especially if electricity must be purchased from outside parties; but if the building contains its own power plant, so that the exhaust steam can be utilized for heating, the convenience and simplicity of motor-driven fans often more than offset the additional cost of operation.

Direct-connected motors are always preferable to belted, if a direct current is available, on account of greater quietness of action. This is due both to the slower speed of the motor and to the absence of belts.

Sufficient speed regulation can be obtained with direct-connected machines, without excessive waste of energy, by the use of a rheostat.

If a direct current is not available, and an alternating current must be used, the advantages of electric driving are greatly reduced, as high-speed motors with belts must be employed, and, furthermore, satisfactory speed regulation is not easily attainable.



Fig. 154. Horizontal Engine for Fan Use.

Area of Ducts and Flues. With the blower type of fan, the size of the main ducts may be based on a velocity of 1,200 to 1,500 feet per minute; the branches, on a velocity of 1,000 to 1,200 feet per minute, and as low as 600 to 800 feet when the pipes are small. Flue velocities of 500 to 700 feet per minute may be used, although the lower velocity is preferable. The size of the inlet register should be such that the velocity of the entering air will not exceed about 300 feet per minute. The velocity between the inlet windows and the fan or heater should not exceed about 800 feet.

The air-ducts and flues are usually made of galvanized iron, the

ducts being run at the basement ceiling. No. 20 and No. 22 iron is used for the larger sizes, and No. 24 to No. 28 for the smaller.

Regulating dampers should be placed in the branches leading to each flue, for increasing or reducing the air-supply to the different rooms. Adjustable deflectors are often placed at the fork of a pipe for the same purpose. One of these is shown in Fig. 155.



Fig. 155. Adjustable Deflector Placed at Fork of Pipe to Regulate Air-Supply.

Fig. 156 illustrates a common arrangement of fan and heater where the type of heater shown in Fig. 138 is used; and Fig. 157 is a self-contained apparatus in which the heater is inclosed in a steel casing.

Factory Heating. The application of forced blast for the warming of factories and shops, is shown in Figs. 158 and 159. The proportional heating surface in this case is generally expressed in the number of cubic feet in the building for each linear foot of 1-inch steam pipe in the heater. On this basis, in factory practice, with all of the air taken from out of doors, there are generally allowed from 100 to 150 cubic feet of space per foot of pipe, according as exhaust or live steam is used, live steam in this case indicating steam of about 80 pounds pressure. If practically all the air is returned from the



Fig. 156. Common Arrangement of Fan with Heater of Type Shown in Fig. 138.

buildings to the heater, these figures may be raised to about 140 as a minimum, and possibly 200 as a maximum, per foot of pipe. The



Fig. 157. Self-Contained Heater and Blower in Steel Casing.

heaters in Table XXXI may be changed to linear feet of 1 inch pipe by multiplying the numbers in column three (square feet of surface) by three.

EXAMPLES FOR PRACTICE

1. A machine shop 100 feet long by 50 feet wide and having 3 stories, each 10 feet high, is to be warmed by forced blast, using



Fig. 158. Illustrating Application of Forced Blast for Warming a Factory.

exhaust steam in the heater. The air is to be returned to the heater from the building, and the whole amount contained in the building is to pass through the heater every 15 minutes. What size of blower

will be required, and what will be the H. P. of the engine required to run it? How many linear feet of 1-inch pipe should the heater contain?

ANS. { 4-foot blower.
6 H. P. engine.
1,071 feet of pipe.



Fig. 159. Centrifugal Blower Producing Forced Blast for Heating a Shop.

2. Find the size of blower, engine, and heater for a factory 200 feet long, 60 feet wide, and having 4 stories, each 10 feet high, using live steam at 80 pounds pressure in the heater, and changing the air every 20 minutes by taking in cold air from out of doors.

ANS. { 6-foot blower.
13 H. P. engine.
3,200 feet of pipe.

In using this method of computation, judgment must be employed, which can come only from experience. The figures given are for average conditions of construction and exposure.

Double-Duct System. The varying exposures of the rooms of a school or other building similarly occupied, require that more heat shall be supplied to some than to others. Rooms that are on the south side of the building and exposed to the sun, may perhaps be kept perfectly comfortable with a supply of heat that will maintain a temperature of only 50 or 60 degrees in rooms on the opposite side of the building which are exposed to high winds and shut off from the warmth of the sun.



Fig. 160. Hot-Blast Apparatus with Double Duct for Supplying Air at Different Temperatures to Different Parts of a Building.

With a constant and equal air-supply to each room, it is evident that the temperature must be directly proportional to the cooling surfaces and exposure, and that no building of this character can be properly heated and ventilated if the temperature cannot be varied without affecting the air-supply.

There are two methods of overcoming this difficulty:

The older arrangement consists in heating the air by means of a primary coil at or near the fan, to about 60 degrees, or to the minimum temperature required within the building. From the coil it passes to the bases of the various flues, and is there still further heated as required, by secondary or supplementary heaters placed at the base of each flue.

With the second and more recent method, a single heater is employed, and all the air is heated to the maximum required to maintain the desired temperature in the most exposed rooms, while the temperature of the other rooms is regulated by mixing with the hot air a sufficient volume of cold air at the bases of the different flues. This result is best accomplished by designing a hot-blast apparatus so that the air shall be forced, rather than drawn through the heater, and by providing a by-pass through which it may be discharged without passing across the heated pipes.



Fig. 161. Mixing Damper for Regulating Temperature of Air Supplied by Double-Duct System.

The passage for the cool air is usually above and separate from the heater pipes, as shown in Fig. 160. Extending from the apparatus is a double system of ducts, usually of galvanized iron, suspended from the ceiling. At the base of each flue is placed a mixing damper, which is controlled by a chain from the room above, and so designed as to admit either a full volume of hot air, a full volume of cool or tempered air, or to mix them in any desired proportion without affecting the resulting total volume delivered to the room. A damper o this form is shown in Fig. 161.

Fig. 162 shows an arrangement of disc fan and heater where the air is first drawn through a tempering coil, then a portion of it forced through a second heater and into the warm-air pipes, while the remain-

der is by-passed under the heater into the cold-air pipes. Mixing



Fig. 162. Warming System Combining Tempering Coil, Disc Fan, Second Heater, and Double Ducts.

dampers are placed at the bases of the flues as already described, to regulate the temperature in different rooms.

ELECTRIC HEATING

Unless electricity is produced at a very low cost, it is not commercially practicable for heating residences or large buildings. The electric heater, however, has quite a wide field of application in heating small offices, bathrooms, electric cars, etc. It is a convenient method of warming rooms on cold mornings in late spring and early fall, when furnace or steam heat is not at hand. It has the special advantage of being instantly available, and the amount of heat can be regulated at will. The heaters are perfectly clean, do not vitiate the air, and are portable.

Electric Heat and Energy. The commercial unit for electricity is one watt for one hour, and is equal to 3.41 B. T. U. Electricity is usually sold on the basis of 1,000 watt-hours (called *Kilowatt-hours*),



Fig. 163. Electric Car-Heater.

which is equivalent to 3,410 B. T. U. A watt is the product obtained by multiplying a current of 1 ampere by an electromotive force of 1 volt.

From the above we see that the B. T. U. required per hour for warming, divided by 3,410, will give the kilowatt-hours necessary for supplying the required amount of heat.

Construction of Electric Heaters. Heat is obtained from the electric current by placing a greater or less resistance in its path. Various forms of heaters have been employed. Some of the simplest consist merely of coils or loops of iron wire, arranged in parallel rows, so that the current can be passed through as many coils as are needed to provide the required amount of heat. In other forms, the heating material is surrounded with fire-clay, enamel, or asbestos, and in some cases the material itself has been such as to give considerable resistance to the current. A form of electric car-heater is shown in Fig. 163. Forms of radiators are shown in Figs. 164 and 165.

Calculation of Electric Heaters. The formula for the calculation of electric heaters is

$$H = I^2 R t \times .24,$$

in which

H = Heat, in calories;
I = Current, in amperes;
R = Resistance, in ohms;
t = Time, in seconds.



Fig. 164. Electric Radiator.

Examples. What resistance must an electric heater have, to give off 6,000 B. T. U. per hour, with a current of 20 amperes?

We have learned that 1 B. T. U. = 252 calories; so, in the present case, 6,000 × 252 = 1,512,000 calories must be provided.

Substituting the known values in the formula, we have

$$1{,}512{,}000 = 20^2 \times R \times 3{,}600 \times .24,$$

from which

$$R = \frac{1{,}512{,}000}{345{,}600} = 4.37 \text{ ohms.}$$

A heater having a resistance of 3 ohms is to supply 3,000 B. T. U. per hour. What current will be required?



Fig. 165. Another Form of Electric Radiator.

3,000 × 252 = 756,000 calories. Substituting the known values in the formula, and solving for I, we have

$$756{,}000 = I^2 \times 3 \times 3{,}600 \times .24,$$

from which

$$I = \sqrt{291.6} = 17 + \text{ amperes.}$$

Connections for Electric Heaters. The method of wiring for electric heaters is essentially the same as for lights which require the same amount of current. A constant electromotive force or voltage

is maintained in the main wire leading to the heaters. A much less voltage is carried on the return wire, and the current in passing through the heater from the main to the return, drops in voltage or pressure. This drop provides the energy which is transformed into heat.

The principle of electric heating is much the same as that involved in the non-gravity return system of steam heating. In that system, the pressure on the main steam pipes is that of the boiler, while that on the return is much less, the reduction in pressure occurring in the passage of the steam through the radiators; the water of condensation is received into a tank, and returned to the boiler by a pump.

In a system of electric heating, the main wires must be sufficiently large to prevent a sensible reduction in voltage or pressure between the generator and the heater, so that the pressure in them shall be substantially that in the generator. The pressure or voltage in the main return wire is also constant, but very low, and the generator has an office similar to that of the steam pump in the system just described—that is, of raising the pressure of the return current up to that in the main. The power supplied to the generator can be considered the same as the boiler in the first case. All the current which passes from the main to the return must flow through the heater, and in so doing its pressure or voltage falls from that of the main to that of the return.

From the generator shown in Fig. 166, main and return wires are run the same as in a two-pipe system of steam heating, and these are proportioned to carry the required current without sensible drop or loss of pressure. Between these wires are placed the various heaters, which are arranged so that when electric connection is made they draw the current from the main and discharge it into the return wire. Connections are made and broken by switches, which take the place of valves on steam radiators.

Cost of Electric Heating. The expense of electric heating must in every case be great, unless the electricity can be supplied at an exceedingly low cost. Estimated on the basis of present practice, the average transformation into electricity does not account for more than 4 per cent of the energy in the fuel which is burned in the furnace. Although under best conditions 15 per cent has been realized, it would not be safe to assume that in ordinary practice more than 5

per cent could be transformed into electrical energy. In heating with steam, hot water, or hot air, the average amount utilized will probably be about 60 per cent, so that the expense of electrical heating is approximately from 12 to 15 times greater than by these methods.

TEMPERATURE REGULATORS

The principal systems of automatic temperature control now in use, consist of three essential features; *First,* an air-compressor, reservoir, and distributing pipes; *second,* thermostats, which are



Fig. 166. General System of Wiring a House for Electric Heating.

placed in the rooms to be regulated; and *third,* special diaphragm or pneumatic valves at the radiators.

The *air-compressor* is usually operated by water-pressure in small plants and by steam in larger ones; electricity is used in some cases. Fig. 167 shows a form of water compressor. It is similar in principle to a direct-acting steam pump, in which water under pressure takes the place of steam. A piston in the upper cylinder compresses the air, which is stored in a reservoir provided for the purpose. When the pressure in the reservoir drops below a certain

point, the compressor is started automatically, and continues to operate until the pressure is brought up to its working standard.

A *thermostat* is simply a mechanism for opening and closing one or more small valves, and is actuated by changes in the tempera-

Fig. 167. Air-Compressor Operated by Water-Pressure, Automatically Controlled, and Operating to Regulate Temperature by Controlling Radiator Valves.



Fig. 168. Thermostat Controlling Valves on Radiators, and Operating through Expansion or Contraction of Metal Strip *E*.

ture of the air in which it is placed. Fig. 168 shows a thermostat in which the valves are operated by the expansion and contraction of the metal strip *E*. The degree of temperature at which it acts may be adjusted by throwing the pointer at the bottom one way or the other. Fig. 169 shows the same thermostat with its ornamental

casing in place. The thermostat shown in Fig. 170 operates on a somewhat different principle. It consists of a vessel separated into two chambers by a metal diaphragm. One of these chambers is partially filled with a liquid which will boil at a temperature below that desired in the room. The vapor of the liquid produces considerable pressure at the normal temperature of the room, and a slight increase of heat crowds the diaphragm over and operates the small valves in a manner similar to that of the metal strip in the case just described.



Fig. 169. Thermostat of Fig. 168 in Ornamental Casing.

The general form of a *diaphragm valve* is shown in Fig. 171. These replace the usual hand-valves at the radiators. They are similar in construction to the ordinary globe or angle valve, except that the stem slides up and down instead of being threaded and running in a nut. The top of the stem connects with a flat plate, which rests against a rubber diaphragm. The valve is held open by a spring, as shown, and is closed by admitting compressed air to the space above the diaphragm.

In connecting up the system, small concealed pipes are carried from the air-reservoir to the thermostat, which is placed upon an inside wall of the room, and from there to the diaphragm valve at the radiator. When the temperature of the room reaches the maximum point for which the thermostat is set, its action opens a small valve and admits air-pressure to the diaphragm, thus closing off the

steam from the radiator. When the temperature falls, the thermostat acts in the opposite manner, and shuts off the air-pressure from the diaphragm valve, at the same time opening a small exhaust which allows the air above the diaphragm to escape. The pressure being removed, the valve opens and again admits steam to the radiator.

Diaphragm Motors. Dampers are operated pneumatically in a similar manner to steam valves. A *diaphragm motor*, so called, is acted upon by the air-pressure; and this lifts a lever which is properly connected to the damper by means of chains or levers, thus securing the desired movement.

Dampers. When mixing dampers are operated pneumatically, a specially designed thermostat for giving a graduated movement



Fig. 170. Thermostat Operating through Expansion or Contraction of the Vapor of a Volatile Liquid.

to the damper should be used. By this arrangement the damper is held in such a position at all times as to admit the proper proportions of hot and cold or tempered air for producing the desired temperature in the room with which it is connected.

Large dampers which are to be operated pneumatically, should be made up in sections or louvres. Dampers constructed in this manner are handled much more easily than when made in a single piece.

It often happens, in large plants, that there are valves and dampers in places which are not easily reached for hand manipulation. These may be provided with diaphragms and connected with the air-pressure system for operation by hand-switches or cocks



VIEW OF CULEBRA FROM RESERVOIR, SHOWING ADMINISTRATION BUILDING TO LEFT, HOTEL TO RIGHT, AND Y. M. C. A. CLUBHOUSE IN CENTER

Note the Open Style of Construction of the Houses to Permit Good Ventilation

conveniently located at some central point in the basement or boiler room.

Telethermometer. This is a device for indicating on a dial at some central point the temperature of various rooms or ducts in different parts of a building. A special *transmitter* is placed in each of the rooms and electrically connected with a central switchboard. Then, by means of suitable switches, any room may be thrown in circuit with the *recorder*, and the temperature existing in the room at that time read from the dial.



Fig. 171. Exterior View, and Section Showing Interior Mechanism of Diaphragm Valve.

Humidostat. The *humidostat* is a device to be placed in one or more rooms of a building for maintaining an even percentage of moisture in the air. The apparatus consists of two essential parts—the *humidostat* and the *humidifier*. The former corresponds to the thermostat in a system of temperature control, and operates a pneumatic valve or other mechanism connected with the humidifier when the percentage of moisture rises above or falls below certain limits. The operating medium is compressed air, the same as for temperature control; and the two devices are usually connected with the same pressure system.

The normal moisture of a room is 70 per cent, and should never exceed that. In cold weather it will be necessary to reduce the amount of moisture somewhat, owing to the "sweating" of walls and windows.

The method of moistening the air will depend somewhat upon circumstances. If the air for ventilation is delivered to the rooms at a temperature not exceeding 70 degrees, the humidifier is best placed in the main air-duct. If the air enters at a higher temperature, the humidifier must be located in the same room with the humidostat.

The moistener or humidifier may be of any one of several forms. Where steam heating is used, and where the steam is clean and odorless and free from oil from engines, a perforated pipe (or pipes) in the air-duct is the simplest and best humidifier. The outlets are properly adjusted, and then the humidostat shuts off and lets on the steam as required. Sometimes a water spray, particularly of warm water, may be used in place of steam. When neither steam jet nor water spray is advisable, an evaporating pan containing a steam coil may be used, the humidostat controlling the steam to the coil, and the water-level in the pan being kept constant by means of a ball-cock.

AIR-FILTERS AND AIR-WASHERS

In cases where the air for ventilating purposes is likely to contain soot or street dust, it is desirable to provide some form of filter for purifying it before delivering to the rooms. If the air-quantity is small and there is plenty of room between the inlet windows and the fan, screens of light cheesecloth may be used for this purpose. The cloth should be tacked to light but substantial wooden frames, which can be easily removed for frequent cleaning. These screens are usually set up in "saw-tooth" fashion in order to give as much surface as possible in the least space.

Another arrangement, used in case of large volumes of air, is to provide a number of light cloth bags of considerable length, through which the air is drawn before reaching the heater. These are fastened to a suitable frame or partition for holding them open. The great objection to filters of this kind is their obstruction to the passage of the air, especially when filled with dust, the frequent intervals at which they should be cleaned, and the great amount of filtering surface required.



Fig. 172. One Form of Spray Filter or Air-Washer, for Removing Dust or Soot from Air Required for Ventilation.

An apparatus which is coming quite generally into use for this purpose, and which does away with the disadvantages noted above, is the *spray filter* or *air-washer*, one form of which is shown in Fig. 172. Air enters as indicated, and first passes through a tempering coil to raise it above the freezing point in winter weather; then passes through the spray-chamber, where the dirt is removed; then through an eliminator for removing the water; and then through a second heater on its way to the fan.

The water is forced through the spray-heads by means of a small centrifugal pump, either belted to the fan shaft or driven by an independent motor.

HEATING AND VENTILATION OF VARIOUS CLASSES OF BUILDINGS

The different methods used in heating and ventilation, together with the manner of computing the various proportions of the apparatus, having been

taken up, the application of these systems to the different classes of buildings will now be considered briefly.

School Buildings. For school buildings of small size, the furnace system is simple, convenient, and generally effective. Its use is confined as a general rule to buildings having not more than six or eight rooms. For large ones this method must generally give way to some form of indirect steam system with one or more boilers, which occupy less space, and are more easily cared for than a number of furnaces scattered about in different parts of the basement. As in all systems that depend on natural circulation, the supply and removal of air is considerably affected by changes in the outside temperature and by winds.

The furnaces used are generally built of cast iron, this material being durable, and easily made to present large and effective heating surfaces. To adapt the larger sizes of house-heating furnaces to schools, a much larger space must be provided between the body and the casing, to permit a sufficient volume of air to pass to the rooms. The free area of the air-passage should be sufficient to allow a velocity of about 400 feet per minute.

The size of furnace is based on the amount of heat lost by radiation and conduction through walls and windows, *plus* that carried away by air passing up the ventilating flues. These quantities may be computed by the usual methods for "loss of heat by conduction through walls," and "heat required for ventilation." With more regular and skilful attendance, it is safe to assume a higher rate of combustion in schoolhouse heaters than in those used for warming residences. Allowing a maximum combustion of 6 pounds of coal per hour per square foot of grate, and assuming that 8,000 B. T. U. per pound are taken up by the air passing over the furnace, we have $6 \times 8{,}000 = 48{,}000$ B. T. U. furnished per hour per square foot of grate. Therefore, if we divide the total B. T. U. required for both warming and ventilation by 48,000, it will give us the necessary grate surface in square feet. It has been found in practice that a furnace with a firepot 32 inches in diameter, and having ample heating surface, is capable of heating two 50-pupil rooms in zero weather. The sizes of ducts and flues may be determined by rules already given under furnace and indirect steam heating.

The velocity of the warm air within the uptake flues depends

upon their height and the difference in temperature between the warm air within the flues and the cold air outside. The action of the wind also affects the velocity of air-flow. It has been found by experience that flues having sectional areas of about 6 square feet for first-floor rooms, 5 square feet for the second floor, and 4½ square feet for the third, will be of ample size for standard classrooms seating from 40 to 50 pupils in primary and grammar schools. These sizes may be used for both furnace and indirect gravity steam heating.

The vent flues may be made 5 square feet for the first floor, and 6 square feet for the second and third floors. They may be arranged in banks, and carried through the roof in the form of large chimneys, or may be carried to the attic space and there gathered by means of galvanized-iron ducts connecting with roof vents of wood or copper construction.

In order to make the vent flues "draw" sufficiently in mild or heavy weather, it is necessary to provide some means for warming the air within them to a temperature somewhat above that of the rooms with which they connect. This may be done by placing a small stove made specially for the purpose, at the base of each flue. If this is done, it is necessary to carry the air down and connect with the flue just below the stove.

The cold-air supply duct to each furnace should be made ¾ the size of all the warm-air flues if free from bends, or the full size if obstructed in any way.

The inlet and outlet openings from the rooms into the flues, are commonly provided with grilles of iron wire having a mesh of 2 to 2½ inches. Both flat and square wire are used for this purpose. Mixing dampers for regulating the temperature of the rooms should be provided for each flue. The effectiveness of these dampers will depend largely upon their construction; and they should be made tight against cold-air leakage, by covering the surfaces or flanges against which they close with some form of asbestos felting. Both inlet and outlet gratings should be provided with adjustable dampers. One of the disadvantages of this system is the delivery of all the heat to the room from a single point, and this not always in a position to give the best results. The outer walls are thus left unwarmed, except as the heat is diffused throughout the room by air-currents. When there is considerable glass surface, as in most of our modern schoolrooms,

draughts and currents of cold air are frequently found along the outside walls.

The indirect gravity system of steam heating comes next in cost of installation. One important advantage of this system over furnace heating comes from the ability to place the heating coils at the base of the flues, thus doing away with horizontal runs of air-pipe, which are required to some extent in furnace heating. The warm-air currents in the flues are less affected by variations in the direction and force of the wind where this construction is possible, and this is of much importance in exposed locations.

The method of supplying cold air to the coils or heaters is important, and should be carefully worked out. The supply should be taken from at least two sides of the building, or, if possible, from all four sides. When it is taken from four sides, each inlet should be made large enough to supply one-half the amount, or, in other words, any two should give the total quantity required. It is often possible to arrange the flues in groups so that all the heating stacks may be placed in two or more cold-air chambers, depending upon the size of the building. A cold-air trunk line may be run through the center of the basement, connecting with the outside on all four sides, and having branches supplying each cold-air chamber.

Cast-iron pin-radiators are particularly adapted to this class of work.

The *School-Pin*, having a section about 10 inches in depth and rated at 15 square feet of heating surface per section, is used quite extensively for this purpose. Stacks containing about 240 square feet of surface for southerly rooms, and 260 for those having a northerly exposure, have been found ample for ordinary conditions in zero weather.

A very satisfactory arrangement is the use of indirect heaters for warming the air needed for ventilation, and the placing of direct radiation in the rooms for heating purposes. The general construction of the indirect stacks and flues may be the same; but the heating surface can be reduced, as the air in this case must be raised only to 70 or 75 degrees in zero weather, the heat to offset that lost by conduction, etc., through walls and windows being provided by the direct surface. The mixing dampers may be omitted, and the temperature of the room regulated by opening or closing the steam valves

on the direct coils, which should be done automatically. The direct-heating surface, which is best made up of lines of 1¼-inch pipe, should be placed along the outer walls beneath the windows This supplies heat where most needed, and does away with the tendency to draughts. In mild weather, during the spring and fall, the indirect heaters may prove sufficient for both ventilation and warming.

Where direct radiation is placed in the rooms, the quantity of heat supplied is not affected by varying wind conditions, as is the case in indirect heating. Although the air-supply may be reduced at times, the heat quantity is not changed. Direct radiation has the disadvantage of a more or less unsightly appearance, and architects and owners often object to the running of mains or risers through the rooms of the building. Air-valves should always be provided with drip connections carried to a sink or dry well in the basement.

When circulation coils are used, a good method of drainage is to carry separate returns from each coil to the basement, and to place the air-valves in the drops just below the basement ceiling. A check-valve should be placed below the water-line in each return.

The gravity system has the fault of not supplying a uniform quantity of air under all conditions of outside temperature, the same as a furnace, but when properly arranged, may be made to give quite satisfactory results.

The fan or blower system for ventilation, with direct radiation in the rooms for warming, is considered to be one of the best possible arrangements.

In designing a plant of this kind, the main heating coil should be of sufficient size to warm the total air-supply to 70 or 75 degrees in the coldest weather, and the direct surface should be proportioned for heating the building independently of the indirect system. Automatic temperature regulation should be used in connection with systems of this kind, by placing pneumatic valves on the direct radiation. It is customary to carry from 3 to 8 pounds pressure on the direct system, and from 8 to 15 pounds on the main coil, depending upon the outside temperature. The foot-warmers, vestibule, and office heaters should be placed on a separate line of piping, with separate returns and trap, so that they can be used independently of the rest of the building if desired. Where there is a large assembly hall, it should be arranged so that it can be both warmed and venti-

lated when the rest of the building is shut off. This can be done by a proper arrangement of valves and dampers.

When different parts of the system are run on different pressures, the returns from each should discharge through separate traps into a receiver having connection with the atmosphere by means of a vent pipe. Fig. 173 shows a common arrangement for the return connections in a combination system of this kind. The different traps discharge into the vented receiver as shown; and the water is pumped back to the boiler automatically when it rises above a given level in the receiver, a pump governor being used to start and stop the pumps as required.

A water-level or seal of suitable height is maintained in the main returns, by placing the trap at the required elevation and bringing the returns into it near the bottom; a balance pipe is connected with the top for equalizing the pressure, the same as in the case of a pump governor. Sometimes a fan is used with the heating coils placed at the base of the flues, instead of in the rooms. Where this is done the radiating surface may be reduced about one-half. This system is less expensive to install, but has the disadvantage of removing the heating surface from the cold walls, where it is most needed.

With a blower type of fan, the size of the main ducts may be based on a velocity of from 1,000 to 1,200 feet per minute, and the branches on a velocity of 800 to 1,000 feet per minute.

The velocity in the vertical flues may be from 600 to 700 feet per minute, although the lower velocity is preferable.

The size of the inlet registers should be such that the velocity of the entering air will not exceed 350 to 400 feet per minute.

When the air is delivered through a register at the high velocities mentioned, some means must be provided for diffusing the entering current, in order to prevent disagreeable draughts. This is usually accomplished by the use of deflecting blades of galvanized iron, set in a vertical position and at varying angles, so that the air is thrown towards each side as it issues from the register. The size of the vent flues should be about the same as for a gravity system—that is, about 6 square feet for a standard classroom, and in the same proportion for smaller rooms.

Vent-flue heaters are not usually required in connection with a fan system, as the force of the fan is sufficient to supply the required



Fig. 173. General Arrangement of Return Connections Especially Adapted to Large Buildings where Different Parts of the Heating System are under Different Pressures.

quantity of air at all times without the aspirating effect of the vent flues.

The method of piping shown in Fig. 173 applies especially to buildings of large size. In the case of medium-sized buildings, it is often possible to use pin radiation for the main heater, placing the same well above the water-line of the boilers and thus returning the condensation by gravity, without the use of pumps or traps. When this arrangement is used, an engine with a large cylinder should be employed, so that the steam pressure will not exceed 15 or 18 pounds, and the whole system, including the direct surface, may be run upon the same system.

This is a very simple arrangement, and is adapted to all buildings of small and medium size where the heater can be placed at a sufficient height above the boilers.

Temperature control is usually secured automatically by placing pneumatic valves upon either the direct or supplementary heaters. Mixing dampers are sometimes used instead, in the latter case. Every fan system should be provided with a thermometer of large size for indicating the temperature of the air in the main duct just beyond the fan.

The ventilation of the toilet-rooms of a school building is a matter of the greatest importance. The first requirement is that the air-movement shall be *into* these rooms from the corridors instead of outward. To obtain this result, it is necessary to produce a slight vacuum within, and this cannot well be done if fresh air is forced into them.

One of the most satisfactory arrangements is to provide exhaust ventilation only, and to remove the greater part of the air through local vents connecting with the fixtures.

Hospitals. The best system for heating and ventilating a hospital depends upon the character and arrangement of the buildings. It is desirable in all cases to do the heating from a central plant, rather than to carry fires in the separate buildings, both on account of economy and for cleanliness.

In the case of small cottage hospitals with two or three buildings placed close together, indirect hot water affords a desirable system for the wards, with direct heat for the other rooms; but where there are several buildings, and especially if they are some distance apart, it

becomes necessary to substitute steam unless the water is pumped through the mains. For large city buildings, a fan system is always desirable.

If the building is tall compared with its ground area, so that the horizontal supply ducts will be comparatively short, the double-duct system may be used with good results. Where the rooms are of good size, and the number of supply flues not great, the use of supplementary heaters at the bases of the flues makes a satisfactory arrangement. Direct radiation should never be used in the wards when it can be avoided, even in connection with an independent air-supply, as it offers too great an opportunity for the accumulation of dust in places which are difficult to reach.

It is common to provide from 80 to 100 cubic feet of air per minute per patient in ordinary wards, and from 100 to 120 cubic feet in contagious wards.

The usual ward building of a modern cottage-hospital generally contains a main ward having from 8 to 12 beds, and a number of private rooms of one bed each.

In addition to these, there are a diet kitchen, duty-room, toilet-rooms, bathrooms, linen-closets, and lockers.

For moderately sheltered locations, 30 square feet of indirect steam radiation has been found sufficient in zero weather for a single ward with one exposed wall and a single window, when upon the south side of the building.

For northerly rooms, 40 square feet should be used. In exposed locations, the heaters may be made 40 and 50 square feet for north and south rooms respectively. The standard pin-radiators rated at 10 square feet of heating surface per section, are commonly used for this purpose. In case hot water is used, the same number of sections of the deep-pin pattern rated at 15 square feet each may be employed, making a total of 45 and 60 square feet per room. For corner rooms having two exposed walls and two windows, the amount of radiation should be increased about 50 per cent over that given above.

The wards are usually furnished with fireplaces which provide for the discharge ventilation. In case the fireplaces are omitted, a special vent flue, either of brick or of galvanized iron, should be provided. These should not be less than 8 by 12 inches for single wards, and the equivalent for each bed in a large ward. Each flue of this

kind should have a loop of steam pipe for producing a draught. A loop of 1-inch pipe, 10 or 12 feet in height, is usually sufficient for this purpose.

Other rooms than wards are usually heated with direct radiators, the sizes of which may be computed in the same manner as for dwelling-houses.

Steam tables for the kitchen, sterilizers, and laundry machinery, require higher pressures than is necessary for heating.

In large plants the boilers are usually run at high pressure, and the pressure reduced for heating. A good arrangement for small plants is to provide sufficient boiler power for warming and ventilating purposes, and run at a pressure of 3 to 5 pounds. In addition to this, a small high-pressure boiler carrying 70 or 80 pounds should be furnished for laundry work and water heating.

Churches. Churches may be warmed by furnaces, by indirect steam, or by means of a fan. For small buildings the furnace is more commonly used. This apparatus is the simplest of all and is comparatively inexpensive. Heat may be generated quickly, and when the fires are no longer needed, they may be allowed to go out without danger of damage to any part of the system from freezing.

It is not usually necessary that the heating apparatus be large enough to warm the entire building at one time to 70 degrees with frequent change of air. If the building is thoroughly warmed before occupancy, either by rotation or by a slow inward movement of outside air, the chapel or Sunday-school room may be shut off until near the close of the service in the auditorium, when a portion of the warm air may be turned into it. When the service ends, the switch-damper is opened wide, and all the air is discharged into the Sunday-school room. The position of the warm-air registers will depend somewhat upon the construction of the building, but it is well to keep them near the outer walls and the colder parts of the room. Large inlet registers should be placed in the floor near the entrance doors, to stop cold draughts from blowing up the aisles when the doors are opened, and also to be used as foot-warmers.

Ceiling ventilators are generally provided, but should be no larger than is necessary to remove the products of combustion from the gaslights, etc. If too large, much of the warmest and purest air will escape through them. The main vent flues should be placed

in or near the floor and should be connected with a vent shaft leading outboard. This flue should be provided with a small stove or flue heater made specially for this purpose. In cold weather the natural draught will be found sufficient in most cases.

The same general rules are to be followed in the case of indirect steam as have been described for furnace heating. The stacks are placed beneath the registers or flues, and mixing dampers provided. If there are large windows, flues should be arranged to open in the window-sills, so that a sheet of warm air may be delivered in front of the windows, to counteract the effects of cold down-draughts from the exposed glass. These flues may usually be made 3 or 4 inches in depth, and should extend the entire width of the window. Small rooms, such as vestibules, library, pastor's room, etc., are usually heated with direct radiators. Rooms which are used during the week are often connected with an independent heater so that they may be warmed without running the large boilers, as would otherwise be necessary.

When a fan is used, it is desirable, if possible, to deliver the air to the auditorium through a large number of small openings. This is often done by constructing a shallow box under each pew, running its entire length, and connecting it with the distributing ducts or a plenum space by means of a pipe from below. The air is delivered at a low velocity through a long slot, as shown in Fig. 174.

The warm-air flues in the window-sills should be retained, but may be made shallower, and the air forced in at a high velocity.

If the auditorium has a sloping floor, a plenum space may be provided between the upper or raised portion and the main floor. Sometimes a shallow basement 3 or 4 feet in height, with a cemented floor, and extending under the entire auditorium, is used as an air or plenum space.

If the basement is of good height and used for storage or other purposes, it is necessary to carry galvanized-iron ducts at the ceiling under the center of each double row of pews, and to connect with each pair by means of branch uptakes. The size of these should be equal to 3 or 4 square inches for each occupant.

Another method is to supply the air through a small register in the end of each pew. This simplifies the pew construction somewhat, but otherwise is not so satisfactory as the preceding method.

If the special pew construction is too expensive, or for any other reason cannot well be used, and the fan is to be retained, the greater part of the air is best introduced through wall registers placed about 8 feet above the floor, with exhaust openings at or near the floor. By this arrangement the air is thrown horizontally toward the center of the church, and much of it falls to the breathing level without rising to the upper part of the room.

Halls. The treatment of a large audience hall is similar to that of a church, the warming being usually done in one of the three ways already described. Where a fan is used, the air is commonly delivered through wall registers placed in part near the floor, and partly at a height of 7 or 8 feet above it. They should be made of ample size, so that there will be freedom from draughts. A part of the vents should be placed in the ceiling, and the remainder near the floor. All ceiling vents, in both halls and churches, should be provided with dampers having means for holding them in any desired position. If indirect gravity heaters are used, it will generally be necessary to place heating coils in the vent flues for use in mild weather; but if the fresh air is supplied by means of a fan, there will usually be pressure enough in the room to force the air out without the aid of other means. When the vent air-ways are restricted, or the air is impeded in any way, electric ventilating fans are often used. These give especially good results in warmer weather, when natural ventilation is sluggish. The temperature may be regulated either by using the double-duct system or by shutting off or turning on a greater or less number of sections in the main heater. After an audience hall is once warmed and filled with people, very little heat is required to keep it comfortable, even in the coldest weather.



Fig. 174. An Approved Method of Delivering Warm Air to the Auditorium of a Church.

Theaters. In designing heating and ventilating systems for

theaters, a wide experience and the greatest care are necessary to secure the best results. A theater consists of three parts: the body of the house, or auditorium; the stage and dressing-rooms, and the foyer, lobbies, corridors, stairways, and offices. Theaters are usually located in cities, and surrounded with other buildings on two or more sides, thus allowing no direct connection by windows with the external air; for this reason artificial means are necessary for providing suitable ventilation, and a forced circulation by means of a fan is the only satisfactory means of accomplishing this. It is usually advisable to create a slight excess of pressure in the auditorium, in order that all openings shall allow for the discharge rather than the inward leakage of air.

The general and most approved method of air-distribution is to force it into closed spaces beneath the auditorium and balcony floors, and allow it to discharge upward through small openings among the seats. One of the best methods is through chair-legs of special latticed design, which are placed over suitable openings in the floor; in this way the air is delivered to the room in small streams, at a low velocity, without draughts or currents. The discharge ventilation should be largely through ceiling vents, and this may be assisted if necessary by the use of ventilating fans. Vent openings should also be provided at the rear of the balconies, either in the wall or in the ceiling, and these should be connected with an exhaust fan either in the basement or in the attic, as is most convenient.

The close seating of the occupants produces a large amount of animal heat, which usually increases the temperature from 6 to 10 degrees, or even more; so that, in considering a theater once filled and thoroughly warmed, it becomes more of a question of cooling than one of warming to produce comfort.

The dressing-rooms should be provided with a generous supply of fresh air, sufficient to change the entire contents once in 10 minutes at least, and should have discharge flues of sufficient size to carry away this amount of air at a velocity not exceeding 300 feet per minute, unless connected with an exhaust fan, in which case the velocity may be doubled. The foyer, corridors, dressing-rooms, etc., are generally heated by direct radiators, which may be concealed by ornamental screens if desired.

Office Buildings. This class of buildings may be satisfactorily

warmed by direct steam, hot water, or, where ventilation is desired, by the fan system. Probably direct steam is used more frequently than any other system for this purpose. Vacuum systems are well adapted to the conditions usually found in this type of building, as most modern office buildings have their own light and power plants, and the exhaust steam can thus be utilized for heating purposes. The piping may be either single or double. If the former is used, it is better to carry a single main riser to the upper story, and run drops to the basement, as by this means the steam and water flow in the same direction, and much smaller pipes can be used than would be the case if risers were carried from the basement upward.

Special provision must be made for the expansion of the risers or drops in tall buildings. They are usually anchored at the center, and allowed to expand in both directions. The connections with the radiators must not be so rigid as to cause undue strains or to lift the radiators from the floor.

It is customary, in most cases, to make the connections with the end farthest from the riser; this gives a length of horizontal pipe which has a certain amount of spring, and will care for any vertical movement of the riser that is likely to occur. Forced hot-water circulation is often used in connection with exhaust steam. The water is warmed by the steam in large heaters similar to feed-water heaters and is circulated through the system by means of centrifugal pumps. This has the usual advantage of hot water over steam, inasmuch as the temperature of the radiators may be regulated to suit the conditions of outside temperature.

When a fan system is used the arrangement of the air-ways is usually somewhat different from any of those yet described. Owing to the great height of these buildings, and the large number of small rooms which they contain, it is impossible to carry up separate flues from the basement. One of the best arrangements is to construct false ceilings in the corridor-ways on each floor, thus forming air-ducts which may receive their supply through one or more large uptakes extending from the basement to the top of the building. These corridor air-ways may be tapped over the door of each room, the openings being provided with suitable regulating dampers for gauging the air-supply to each. Adjustable deflectors should be placed in the main air-shafts for proportioning the quantity to be delivered



STURTEVANT AIR HEATER
B. F. Sturtevant Co., Hyde Park, Mass.

to each floor. If both supply and discharge ventilation are to be provided, the fresh air may be carried in galvanized-iron ducts within the ceiling spaces, and the remainder used for conveying the exhausted air to uptakes leading to a discharge fan placed upon the roof of the building. In both of these cases, it is assumed that heat is supplied to the rooms by direct radiation, and that the air-supply is for ventilation only.

Apartment Houses. These are warmed by furnaces, direct steam, and hot water. Furnaces are more often used in the smaller houses, as they are cheaper to install, and require a less skilful attendant to operate them. Steam is probably used more than any other system in blocks of larger size. A well-designed single-pipe connection, with automatic air-valves dripped to the basement, is probably the most satisfactory in this class of work. People who are more or less unfamiliar with steam systems are apt to overlook one of the valves in shutting off or turning on steam; and where only one valve is used, the difficulty arising from this is avoided. Where pet-cock air-valves are used, they are often left open through carelessness; and the automatic valves, unless dripped, are likely to give more or less trouble.

Greenhouses and Conservatories. Buildings of this class are heated in some cases by steam and in others by hot water, some florists preferring one and some the other. Either system, when properly designed and constructed, should give satisfaction, although hot water has its usual advantage of a variable temperature. The methods of piping are, in a general way, like those already described, and the pipes may be located to run underneath the beds of growing plants or above, as bottom or top heat is desired. The main is generally run near the upper part of the greenhouse and to the farthest extremity, in one or more branches, with a pitch upward from the heater for hot water and with a pitch downward for steam. The principal radiating surface is made of parallel lines of $1\frac{1}{2}$ inch or larger pipe, placed under the benches and supplied by the return current. Figs. 175, 176, and 177 show a common method of running the piping in greenhouse work. Fig. 175 shows a plan and elevation of the building with its lines of pipe; and Figs. 176 and 177 give details of the pipe connections of the outer and inner groups of pipes respectively.

Any system of piping which gives free circulation and which is adapted to the local conditions, should give satisfactory results. The radiating surface may be computed from the rules already given. As the average greenhouse is composed almost entirely of glass, we



Fig. 175. Plan and Elevation Showing One Method of Running Piping in a Greenhouse

may for purposes of calculation consider it such; and if we divide the total exposed surface by 4, we shall get practically the same result as if we assumed a heat loss of 85 B. T. U. per square foot of surface per hour, and an efficiency of 330 B. T. U. for the heating

coils; so that we may say, in general, that the square feet of radiating surface required equals the total exposed surface, divided by 4 for steam coils, and by 2.5 for hot-water. These results should be increased from 10 to 20 per cent for exposed locations.

CARE AND MANAGEMENT

The care of furnaces, hot-water heaters, and steam boilers has been discussed in connection with the design of these different systems of heating, and need not be repeated. The management of the heating and ventilating systems in large school buildings is a matter of much importance, especially in those using a fan system. To obtain the best results, as much depends upon the skill of the operating engineer as upon that of the designer.

Beginning in the boiler-room, he should exercise special care in the management of his fires, and the instruction given in "Boiler Accessories" should be carefully followed; all flues and smoke passages should be kept clear and free from accumulations of soot and ashes by means of a brush or steam jet. Pumps and engine should be kept clean and in perfect adjustment, and extra care should be taken when they are in rooms through which the air-supply is drawn, or the odor of oil will be carried to the rooms. All steam traps should be examined at regular intervals to see that they are in working order; and upon any sign of trouble, they should be taken apart and carefully cleaned.

The air-valves on all direct and indirect radiators should be inspected often; and upon the failure of any room to heat properly, the air-valve should first be looked to as a probable cause of the difficulty. Adjusting dampers should be placed in the base of each flue, so that the flow to each room may be regulated independently. In starting up a new plant, the system should be put in proper balance by a suitable adjustment of these dampers; and, when once adjusted, they should be marked, and left in these positions. The temperature of the rooms should never be regulated by closing the inlet registers. These should never be touched unless the room is to be unused for a day or more.

In designing a fan system, provision should be made for *air-rotation*; that is, the arrangement should be such that the same air may be taken from the building and passed through the fan and



Fig. 176. Connections of Outer Groups of Pipes of Greenhouse Shown in Fig. 175.



Fig. 177. Connections of Inner Groups of Pipes of Greenhouse Shown in Fig. 175.

heater continuously. This is usually accomplished by closing the main vent flues and the cold-air inlet to the building, then opening the class-room doors into the corridor-ways, and drawing the air down the stair-wells to the basement and into the space back of the main heater through doors provided for this purpose. In warming up a building in the morning, this should always be done until about fifteen minutes before school opens. The vent flues should then be opened, doors into corridors closed, cold-air inlets opened wide, and the full volume of fresh air taken from out of doors.

At night time the dampers in the main vents should be closed, to prevent the warm air contained in the building from escaping. The fresh air should be delivered to the rooms at a temperature of from 70 to 75 degrees; and this temperature must be obtained by proper use of the shut-off valves, thus running a greater or less number of sections on the main heater. A little experience will show the engineer how many sections to carry for different degrees of outside temperature. A dial thermometer should be placed in the main warm-air duct near the fan, so that the temperature of the air delivered to the rooms can be easily noted.

The exhaust steam from the engine and pumps should be turned into the main heater; this will supply a greater number of sections in mild weather than in cold, owing to the less rapid condensation.



A BATTERY OF IDEAL STEAM BOILERS SHOWING METHOD OF YOKING THE MAIN SUPPLY AND RETURN PIPE.

American Radiator Company.

STEAM AND HOT WATER FITTING

STEAM BOILERS AND CONNECTIONS

Small Cast-Iron Boilers. For small low-pressure steam heating jobs, boilers made up of very few sections are used. Two types are illustrated in Figs. 1 and 2. The ratings of such boilers range, as a rule, from about 200 square feet to 800 square feet. These figures and those following are intended to give merely a general idea of the capacities of boilers of various types. There is no hard and fast rule governing the matter, manufacturers varying greatly in their practice. The ratings mentioned are given in the number of square feet of direct radiation the boiler is rated to supply, with steam at from 3 to 5 pounds' pressure when the radiators are surrounded by air at 70° F.



Fig. 1. Small Low-Pressure Steam Heating Boiler.

Boilers similar, in a general way, to the one illustrated in Fig. 3 are used for jobs somewhat larger than the boilers above described would be adapted to. These

boilers have grates ranging generally from 18 inches to 36 inches diameter, and are rated from about 300 square feet to 1,600 square feet, or more.

The boilers above described have the disadvantage of not being capable of having their grate surface increased by adding sections, as may readily be done with boilers having vertical sections.

Cast-Iron Boilers with Vertical Sections. Boilers for jobs having



Fig. 2. Small Low-Pressure Steam Heating Boiler.

anywhere from 500 to 5,000 square feet of surface, or more, are made up of vertical sections, as in Fig. 4, connected either by slip nipples or by drums and nipples with long screws and lock-nuts.

Very many slip-nipple boilers are now being manufactured, finding favor with fitters owing to the ease with which they can be erected.

The larger sizes of vertical sectional boilers are often made up of two sets of sections placed opposite each other, as shown in Fig. 5. Such boilers are rated up to 6,000 square feet and over.

Arrangement of Grates. Certain makers, in order to avoid making patterns for a boiler with a wide grate, secure the necessary grate surface by adding to the length. For ordinary low-pressure heating, the efficiency of any grate over 6 feet in length falls off very rapidly, owing to the difficulty of properly caring for the fire. Six feet should be considered about the limit for the length of a grate in a low-pressure boiler.



Fig. 3. Steam Heating Boiler.

Not long ago few portable boilers with grates wider than 36 inches were manufactured. Now, boilers with 42-inch, 48-inch, and even wider grates, are common.

Selection of Boilers. It is well in selecting a boiler, to see that the proportion of heating surface to grate surface is not less than 16 to 1, and in large boilers not less than 20 to 1; that the fire-box is deep, so that ample coal may be put on to burn through the night; that the grate is not too long for convenient firing and cleaning; that there is ample steam space;

and that the water line is not broken into too many small areas involving the likelihood that water will be lifted by rapid evaporation and wet steam result. See to it, also, that the ash-pit is deep, and that the grate is of a design that will permit convenient operation of the boiler.

On large jobs, it is better, as a rule, to use two boilers. One must remember that a plant must be designed for the coldest weather; and since the average temperature during the heating season is, in many Northern sections, not far from 40°, one of a pair of boilers will be sufficient under average conditions to do the work with economy; whereas a single, large boiler, during a good part of the heating season, would have to be run with drafts checked and under very unfavorable conditions as to economy. It is almost as poor economy to have too large a boiler as to have one too small, for, if run with the feed-door open or drafts closely checked, incomplete combustion takes place.



Fig. 4. Steam Heating Boiler with Vertical Sections.

Boilers for Soft Coal. Some boilers for burning soft coal are arranged with a perforated pipe or duct discharging heated air above the fire to make the combustion more complete and thus diminish the amount of smoke given off. This arrangement is of somewhat doubtful utility, since it is difficult to heat the air properly, and to regulate its admission.

It is necessary, for soft coal boilers, that the flues and smoke-pipe be larger than for hard coal heaters, in order to provide for the more rapid accumulation of soot. Soft coal boilers are also built on the

down-draft principle, the air being drawn down through the fire instead of passing upward in the usual manner.

Coke Boilers. Coke is a popular fuel in some parts of the coun-



Fig. 5. Vertical Sectional Boiler.

try; and certain makers are putting out specially designed boilers for this service, having a very deep fire-box.

Boiler Setting and Foundations. Brick setting of boilers, as



Fig. 6. Boiler in Brick Setting.

in the case of furnaces, has been quite generally discarded, except in cases where the space around and above the boiler is used as a cen-

tral heating chamber for indirect systems, the radiators being placed above the heater (see Fig. 6). The pipes lead off as in furnace heating.

The ash-pits under most boilers are rather shallow; therefore



Fig. 7. Pit for Collection of Hot Ashes.

it is a good plan to excavate and build a pit not less than 4 to 6 inches below the floor, to give additional space for the collection of hot ashes, thus avoiding the burning-out of grates. Such pits should be built preferably of brick, and the bottom should be paved with bricks on edge, to prevent their being easily dislodged. Fig. 7 shows the general arrangement of an ash-pit built as described.



Fig. 8. Typical Arrangement of Return, Showing Check Valve.

Boiler Connections. Small jobs frequently have no stop valves at the boiler. In the case of larger ones, or where there are two boilers, valves in the supply mains must always be accompanied with check valves in the returns; otherwise, in case a stop valve in the main steam line is closed, the water will be backed out of the main returns at the boiler, by the pressure. Should the water partially leave the boiler in this manner and then suddenly return, the water coming in contact with the heated sections will crack them.

A stop valve should be placed between the boiler and the check valve in the return. A typical arrangement of return, etc., is shown

in Fig. 8. It is convenient to have an independent drain connection from the returns to provide for drawing off the water in the system without emptying the water from the boiler. The latter, of course, has its independent blow-off cock. The water supply to the boiler should be controlled by a lock-shield valve or a cock that cannot be tampered with by any person not in charge. Boilers having eight sections or more, as a rule, have two or more steam outlets, thus reducing the likelihood of the boiler priming or making wet steam, since, with a single outlet, the velocity of steam through it may be so great that the water is picked up and carried into the piping system.



Fig. 9. Method of Connecting Two Boilers.

When two boilers are to be connected, especial care must be taken to make them maintain an even water line when working together. Fig. 9 shows a method of making these connections that is simple and effective. The valved connection between the two boilers, below the water, gives free communication between them, making them work as one and preventing a difference in the water level in the two boilers. The equalizing pipe is often omitted, the header being made about twice the diameter of the pipes leading to it from the boilers.

The returns are connected with the twin boilers practically as

shown in Fig. 8, the check valve being placed between the stop valve of each boiler and the main return.

Boiler Fittings or Trimmings. It is important to have a reliable safety-valve, preferably one of the "pop" type specially designed for steam heating systems.

The damper regulators used are of the ordinary diaphragm pattern, and should be connected by chains with both the lower draft door below the grate, and with the cold-air check in the smoke connection.

The steam gauge with siphon, the water column, water gauge, gauge cocks, etc., require no special description.

Capacity of Boilers. Boiler capacities are commonly expressed in the number of square feet of direct radiating surface they will supply without undue forcing. Mains and risers should, of course, be added to the actual amount of surface in the radiators and coils. Even if the pipes are covered, a small allowance should be added to the combined surface of the radiators. Not less than 50 per cent, and preferably 60 per cent, must be added to indirect radiation, to reduce it to equivalent direct radiation; and not less than 25 to 30 per cent to direct-indirect radiation, to get its equivalent in direct surface. Another point to be kept in mind in selecting a boiler for heating rooms to be kept at different temperatures, is that more heat is given off per square foot of radiation in a room at 50°, for example, than in a room kept at 70°, the amount given off being approximately proportional to the difference in temperature between the steam and the air. With steam at, say, 220°, corresponding to a trifle over 2 pounds' pressure, the difference, in the case assumed, would be $220° - 50° = 170°$, and $220° - 70° = 150°$. That is, the actual amount of radiation in the rooms to be kept at 50° should be multiplied by $\frac{170}{150}$ to ascertain the amount of radiation in a 70° room that would give off the same amount of heat.

It is common practice to allow roughly for the loss of heat from uncovered mains, branches, and risers, by adding about 25 per cent to the actual direct radiating surface in radiators and coils.

Example. What should be the capacity of a boiler to supply steam to 1,000 square feet of direct radiation in a room to be kept at 70°, to 800 square feet of indirect radiation; and to 1,500 square feet of direct radiation, in rooms to be kept at 50° F.?

Direct radiation	1,000 sq. ft.
Equivalent in direct radiation of 800 sq. ft. of indirect = 800 × 1½ =	1,200 " "
Equivalent in direct radiation, in rooms at 70°, of 1,500 sq. ft. in rooms at 50° = $\frac{7}{11}$ × 1,500 =	1,700 " "
Total equivalent D. R. S. (direct radiating surface) exposed in 70° air =	3,900 sq. ft.
Add 25 per cent of actual surface to allow approximately for piping =	825 " "
Total equivalent D. R. S., or Boiler Rating =	4,725 sq. ft.

Grate Surface and Heating Capacity. It is advisable always to check the catalogue ratings of boilers as follows, when selecting one for a given service:

Suppose the Direct Radiating Surface, including piping, is 3,000 square feet. One square foot, it may be assumed, will give off about 250 heat units in one hour—a *heat unit* being the amount of heat necessary to raise the temperature of 1 pound of water 1 degree Fahrenheit. A pound of coal may safely be counted on to give off to the water in the boiler 8,000 heat units. Now, 3,000 sq. ft. × 250 heat units ÷ 8,000 heat units, gives the amount of coal burned per hour; and this, divided by the square feet of grate, gives the rate of combustion per square foot per hour. Suppose in this case, the grate has an area of 15 sq. ft.; then $\frac{3000 \times 250}{8000 \times 15}$ = 6.25 pounds coal burned per square foot of grate surface per hour. This is not a high rate for boilers of this size, though for ordinary house-heating boilers the rate should not exceed 5 pounds; and for small heaters having 2 to 4 square feet of grate, the rate should be as low as 3 to 4 pounds per square foot of grate per hour. Otherwise, more frequent attention will be required than it is convenient to give to the operation of such small boilers. This is where depth of fire-box plays an important part, for, with a shallow fire, the coal quickly burns through, necessitating frequent firing.

Coal Consumption. For house-heating boilers a fair maximum rate of combustion is 5 pounds per square foot of grate per hour. In many residences it is the custom to bank the fire at night, when the rate will fall to, say, 1 pound. In cold weather, then, one square foot of grate would burn 5 pounds of coal for each of 16 hours, and 1 pound during each of the remaining 8 hours, a total of 80 + 8 = 88 pounds.

In many sections of the country, the average outside temperature during the heating season is about 40°; and since the heat required is proportional to the difference in temperature between indoors and outside, the average coal consumption would be only $\frac{70° - 40°}{70° - 0°} = \frac{3}{7}$ of the maximum in zero weather.

With a heating season of 200 days, the coal burned on one square foot of grate would be $200 \times \frac{3}{7} \times 88 = 7{,}600$ pounds in round numbers, corresponding to an average rate throughout the season of $\frac{7{,}600 \text{ pounds}}{200 \text{ days} \times 24 \text{ hrs.}} = 1.6$ pounds approximately.

A method of approximating the coal consumption for a given amount of radiating surface, designed to maintain a constant temperature in rooms of 70° day and night, would be to multiply the surface (which, for example, take at 1,000 square feet, including allowance for mains) by 250 heat units—the amount given off by a square foot per hour—and then multiply the product by $\frac{3}{7}$, as explained above, to allow for average conditions. This gives $1{,}000 \times 250 \times \frac{3}{7}$, which, divided by 8,000 heat units per pound of coal, gives the weight of coal required per hour; and this, multiplied by the hours per season, gives the total consumption.

Non-Conducting Coverings. It is customary to cover cast-iron sectional boilers with non-conducting material composed as a rule chiefly of asbestos or magnesia applied in a coating $1\frac{1}{2}$ to 2 inches thick, the exterior being finished hard and smooth.

Exposed basement piping in first-class work is covered with sectional covering $\frac{3}{4}$ inch to 1 inch thick, according to the character of the work.

The loss of heat through fairly good coverings, is not far from 20 per cent of the loss from a bare pipe, which, with low-pressure steam, is approximately 2 heat units per square foot per hour for each degree difference in temperature between the steam and the surrounding air.

STEAM RADIATORS AND COILS

Direct Radiators. The commonest forms of radiators to-day are the cast iron vertical loop varieties, types of which are shown in Figs. 2 and 13 in Part I (Heating and Ventilation). These are



A COMPLETE STEAM-HEATING PLANT
This Combines the Boiler and Radiator, and Gas is Used for Fuel
James B. Clow & Sons, Chicago

made up with slip-nipple or screw-nipple connections, the standard height being about 36 to 38 inches.

It is, of course, advisable to use radiators of standard height when possible, since they are cheaper than the lower radiators, which must



Fig. 10. Low Radiator to be Placed Below Window Sill.

be used when placed below window sills (see Fig. 10). Single-column radiators are more effective than those having a greater number of vertical loops, since in the latter the air flow is retarded and the outer loops cut off the radiant heat from the inner ones. Radiators with four or more columns are generally used where the length of the space in which they must be placed is limited.



Fig. 11. Concealed Radiator with Register Face.

Wall radiators (see Fig. 4, Part I, Heating and Ventilation) have become very popular because of their neat appearance and the small distance they project into the room. They are very effective heaters, and, although more expensive than certain other types of cast-iron radiators, less surface is required, which tends to offset the increased cost. These radiators are made up in such a variety of forms that they can be adapted to almost any location.

Concealed Radiators. A favorite method of concealing radiators

is to place them below window-sills, with a grating or register face in front of and above them, as shown in Fig. 11. By this arrangement, the radiant heat is to a great extent cut off. The gratings must have ample area to permit the free circulation of air, and should have not



Fig. 12. Radiator for Use without Gratings.

less than 2 or 2½ square inches of free area to each square foot of radiating surface, for inlets and outlets respectively. It is advisable to increase these allowances slightly when possible.

The same rule applies to radiators placed below seats. A radia-



Fig. 13. Hook Plates.



Fig. 14. Expansion Plates.

tor designed specially for this purpose, for use without gratings, is shown in Fig. 12.

Wall Coils. An ordinary wall coil or manifold coil, made up generally of 1¼-inch pipe, with branch tees or manifolds, is illustrated

in Fig. 39, Part I (Heating and Ventilation). The long runs of such coils rest on hook plates (Fig. 13); the short pipes near the corner, on expansion plates (Fig. 14), on which the pipes are free to move when the long pipes expand. Such coils are very effective when placed below the windows of a factory, in which class of buildings they find their widest application.

Miter Coils. Miter coils, as shown in Fig. 15, are used for overhead heating, the coils being suspended about 8 to 10 feet from the floor, and 3 to 4 feet from the walls. A good type of hanger is shown in Fig. 16. The same type of coil, when placed alongside a wall, is known in certain sections as a *harp* coil (see Fig. 17), and may be used where long runs must be made along a wall, but where it is impossible to install the type of coil shown in Fig. 39, Part I (Heating and Ventilation), owing to doorways or other obstructions. Two harp coils could be used along a wall, for example, avoiding a doorway; and the expansion of the pipes would be provided for by the short vertical lines.



Fig. 15. Miter Coils for Overhead Heating.



Fig. 16. An Approved Type of Hanger.

Return-Bend Coils. Return-bend coils, known in some parts of the country as *trombone* coils, are shown in Fig. 40, Part I (Heating and Ventilation). These are suitable only for rather short runs, since the steam must pass through the several horizontal pipes successively, and, if the radiating surface is greater than the capacity of the upper line of pipe to supply it properly, the steam is condensed before reaching the lower lines. With the harp or other coils having headers or branch tees, sufficient steam can enter to fill all the pipes at once, passing through the parallel lines at the same time.

Direct-Indirect Radiators. A *direct-indirect* radiator is shown in Fig. 18. The air enters through a louvered or slatted wall opening with screen. Provision is made to shut this off and admit air simultaneously from the room, making the radiator essentially a direct radiator when the cold air is shut off. The best location for the cold-air opening is probably just below the sills, the wall boxes being less conspicuous in this position.

Two forms of indirect radiators are



Fig. 17. Harp Coil.

shown in Fig. 7, Part I, and Fig. 3, Part II (Heating and Ventilation), the shallow sections being used largely for house heating, the deep ones for schoolhouse systems. The latter are provided with extra long nipples for spacing the sections about 4 inches on centers, to give a proper passage for a large volume of air.



Fig. 18. Direct-Indirect Radiator.

Indirect Radiators. The indirect radiators are enclosed in galvanized-iron casings about 30 inches deep, giving a space of 6 or 8 inches above and below the radiators. The beams over the radiators are commonly covered with rough boards, to which tin or

tin and asbestos is nailed, the casing being flanged at the top and screwed or nailed to these boards.

The casings should be made with corners of a type that will permit the ready removal of the sides in case of repairs being needed; and the bottom of the casing should be provided with a slide for inspection and cleaning. The larger sections, when used for schoolhouse heating, are arranged as shown in Fig. 19, with a mixing damper designed to cause a mingling of the warm and cold air in the flue, the volume discharged being but slightly reduced, with a decrease in temperature due to opening the damper to cold air. The space for the passage of air between the shallow sections containing about 10 square feet each, is about $\frac{1}{3}$ of a foot; the space between the sections of the deep pattern is not far from $\frac{1}{2}$ a foot when the sections are properly spaced.



Fig. 19. Arrangement of Casings for Use in Connection with Indirect Radiators.

Heat Given Off by Steam Radiators. Of the heat emitted by direct radiators, approximately one-half is by radiation, the balance by convection or the contact of air. Since practically no heat is radiated from concealed radiators, it is very important that proper provision should be made for the passage of an adequate volume of air over the heating surface.

TABLE I

Heat Units Emitted from Radiators and Coils

Radiation per square foot of radiating surface per hour.—In rooms at 70° F. temperature.—With steam at 3 to 5 pounds' pressure.

TYPE OF RADIATOR	HEAT UNITS EMITTED (Approximate)
Concealed cast-iron direct radiators	175–200
Ordinary cast-iron vertical-section radiators	250
Wall radiators	300
Pipe coils on walls	325
Pipe coils overhead (pipes side by side)	350
Ordinary cast-iron extended-surface indirect radiators (air admitted from outdoors)	400

Wall radiators and coils give off more heat under the same conditions than is emitted by ordinary vertical cast-iron radiators.

Much might be said regarding the efficiency of radiators due to their height, form, and arrangement. For the purposes of this course, however, only fair average values will be given, as set forth in Table I, a discussion of radiator tests, etc., being omitted to avoid unnecessary detail.

STEAM PIPING

Size of Main for Circuit System. Since the main of a circuit system, as described in Part I (Heating and Ventilation), must carry both steam and water of condensation, it should be made considerably larger in proportion to the surface supplied than mains which are dripped at intervals or which carry only the condensation from the main itself.

Sizes, ample for circuit mains of ordinary length, are indicated in the accompanying table:

TABLE II

Sizes of Circuit Mains

Diameter of Circuit Main	Direct Radiating Surface
2 inches	200 sq. ft.
2½ "	350 " "
3 "	600 " "
3½ "	900 " "
4 "	1,200 " "
4½ "	1,700 " "
5 "	2,100 " "
6 "	3,000 " "

Dry Return System. In many cases it is desirable to run the supply and return mains overhead. Such systems contain less water than wet return systems, and are therefore more susceptible to changes in the fire, because of the smaller quantity of water in the apparatus. The return mains must be made larger than when they are placed below the water line, since they are filled with steam, except the space occupied by the return water running along the bottom. The pipes should have a greater pitch than wet returns.

With dry returns, if certain supply risers are of inadequate size, steam is apt to back up into the radiator through the dry returns and to cause a holding-back of the water in the radiators. To prevent this,

check valves are sometimes introduced in the branch returns. If the piping is properly proportioned, however, this is unnecessary. Siphon drips are frequently used, as explained in Part I (Heating and Ventilation).

Wet Return Systems. This system, illustrated in Fig. 20, provides for water sealing all returns and drips, and avoids the backing-up action mentioned above. Suppose, for example, the pressure in one of the vertical returns is ½ pound less than in the others; then, since a column of water 2.3 feet high corresponds to 1 pound pressure, the water will back up this particular return about 1.15 feet higher than in the others and thus equalize the difference in pressure. Where the mains must be long, the wet return system affords the opportunity to rise and drip the supply main as often as necessary; whereas, with the dry return system, the main and return have a gradual pitch from start to finish. This often brings the return so low as to interfere with head room. With the wet return system the return may be dropped below the floor line at doorways without interfering with the circulation. The sizes of wet returns may be made considerably smaller than dry returns for a given radiating surface, as shown in Table III.



Fig. 20. Wet Return System.



Fig. 21. Overhead Feed System.

Overhead Feed System. The overhead feed system (see Fig. 21)

is most commonly used in connection with exhaust steam plants, since in such systems the exhaust pipe from the engines must be carried to the roof, and the steam supply to the building may conveniently be taken from a tee near the upper end of this pipe. The main should be pitched down, and outlets taken from the bottom, to drain the condensation through the risers (see Fig. 22). With this system the water of condensation always flows in the same direction as the steam; hence the horizontal pipes and the risers may be made somewhat smaller than in up-feed systems.



Fig. 22. Outlet Taken from Bottom of Main.

This system has the advantage of placing the big pipes in the attic, where their heating effect is less objectionable than in the basement. As the pipes gradually decrease in size from top to bottom, this gives small pipes on the lower floors, which in modern buildings generally contain a few large rooms and little space for concealing pipes. It is frequently advisable to combine with this system the up-feed method of heating the first floor, which is generally high-studded and requires a large amount of radiation. Relieving the down-feed system of this load means smaller risers throughout the building, which, in the modern sky-scraper, results in a saving that more than offsets the cost of the separate up-feed system for the lower floor. Another reason why it is advisable to put the lower floor on a separate system, is that the steam is dry, whereas the steam from an overhead system becomes pretty wet from condensation by the time it reaches the lower floor.



Fig. 23. Siphon Trap.

One-Pipe System. The one-pipe up-feed system is most commonly used in connection with relatively small heating plants. It has the advantage of simplicity, there being but a single valve to operate. In tall buildings with the up-feed system, the risers must be objectionably large to provide for the passage of steam up, and water of condensation down, the same pipe. With the overhead system, the risers may be made considerably smaller, since the water is not hindered in its passage by a flow of steam in the opposite direction. With this one-pipe system, the radiator connections should be short and pitched downward toward the risers to avoid pockets. When used in high buildings with the overhead system, the lower portion of the risers must be liberally proportioned, otherwise the steam will become too wet.



Fig. 24. Arrangement to Rise and Drip in Mains at Intervals.

The Two-Pipe System. This system is commonly used where the radiator connections must be long and where it would be impossible to secure a proper pitch to insure good drainage with one-pipe radiator connections. Coils are nearly always made up with two-pipe connections. In high buildings, where a large amount of radiation must be carried by each riser, they may be made smaller if two-pipe connections are made with the radiators. This is often a decided advantage, especially if the risers are to be concealed.



Fig. 25. Arrangement for Draining with Indirect System.

Draining Mains and Risers. With long mains, it frequently is the case that if given a continuous pitch they would be too low at the extreme ends; and it is therefore customary to rise and drip at intervals, as shown in Figs. 23 and 24.

The *siphon trap* (Fig. 23) prevents a greater pressure being introduced along the overhead return than occurs at the extreme end, since any excess in pressure at an intermediate point merely forces down the water in the inlet leg of the siphon trap to a point where the difference in pressure in the two mains is equalized by the higher level of water maintained in the outlet pipe of the syphon trap.



Fig. 26. Risers Drained to Main and Main Drained at End.

With indirect systems, the mains are frequently drained through the benches or stacks of radiators, the connections being taken from the bottom of the main. It is assumed that all the indirects will not be shut off at the same time (see Fig. 25).

Mains and risers are commonly drained as shown in Fig. 20, connections being taken from the bottom of the main and the heel of the riser. Risers are not infrequently drained to the main, which in turn is drained at the end (see Fig. 26). This arrangement requires less fitting than when the



Fig. 27. Showing Artificial Water Line.

risers are relieved at the base, as shown in Fig. 20. If the mains are long, they should be dripped at intervals of 50 to 75 feet.

Overhead-feed mains on a down-feed system are nearly always dripped from the bottom to the various risers, as previously stated.

Artificial Water Line. It is sometimes necessary, when a boiler

is set very low with reference to the returns, and it is desired to use a wet return system, to seal the relief pipes by means of an artificial water line established as shown in Fig. 27. The equalizing pipe is to be connected with a steam main.

When the discharge from the system leads to an open return, a trap must be used. One of the type shown in Fig. 28, arranged with an equalizing pipe and set at the proper level, will hold the water line in the system, no standpipe being required.



Fig. 28. Water Line Trap with Equalizing Pipe.

Pipe Sizes.—Mains. The capacities of pipes to supply heating surface increase more rapidly than their sectional areas; that is, a 6-inch pipe, with about four times the area of a 3-inch pipe, will supply nearly six times as much surface.

Table III shows the amounts of radiating surface in gravity-return systems which main pipes 100 feet long, of different diameters, may be safely counted on to supply with low-pressure steam (say, 3 to 5 lbs.).

In case the radiating surface is located some distance above the water line in the boiler, the carrying capacity of the pipes may be increased as much as 50 per cent, owing to the greater drop in pressure that may be allowed without interfering with the return of water to the boiler.

Mains are frequently made much larger than necessary, simply because the fact has been overlooked that the radiators are located well above the boiler, and that a drop in pressure between the boiler and the end of the main of ¼ lb., or even more, would be permissible.

The greater the drop in pressure allowed the smaller may be the pipe for a given capacity.

Pipe Sizes.—One-Pipe Risers. Riser capacities are given in Table IV.

TABLE III

Capacity of Supply Mains, Gravity Return System, and Size of Dry and Wet Returns

Mains 100 ft. long.—Steam at low pressure (3 to 5 lbs.).

Diameter of Supply Pipe	Capacity in Direct Radiating Surface	Diameter of Dry Return	Diameter of Wet Return
1 inch	55 sq. ft.	¾ inch	¾ inch
1¼ inches	115 " "	1 "	1 "
1½ "	175 " "	1¼ inches	1¼ inches
2 "	325 " "	1½ "	1¼ "
2½ "	570 " "	2 "	1½ "
3 "	1,000 " "	2½ "	2 "
3½ "	1,480 " "	3 "	2½ "
4 "	2,000 " "	3 "	2½ "
4½ "	2,770 " "	3 "	2½ "
5 "	3,500 " "	3½-4 "	3 "
6 "	5,700 " "	4-5 "	3½-4 "
7 "	8,800 " "	4-5 "	4 "
8 "	12,000 " "	4-5 "	4 "
10 "	20,000 " "	5-6 "	4 "
12 "	33,000 " "	5-6 "	4-5 "

For lengths greater than 100 ft. and for same drop in pressure as for 100 ft., multiply the above figures by 0.8 for 150 ft.; 0.7 for 200 ft.; 0.6 for 300 ft.; 0.5 for 400 ft.; 0.4 for 600 ft.; and 0.3 for 1,000 ft. When the pressure at the supply end of the pipe can be increased for long runs so that the drop in pressure for each 100 ft. can be the same, then the figures in the table can be used for long runs.

TABLE IV

Capacities of One-Pipe Risers

Size of Pipe	Capacity, Up-Feed	Capacity, Down-Feed
1 inch	30 sq. ft.	60 sq. ft.
1¼ inches	60 " "	110 " "
1½ "	120 " "	160 " "
2 "	200 " "	260 " "
2½ "	300 " "	400 " "
3 "	450 " "	600 " "
3½ "	620 " "	800 " "
4 "	800 " "	1,000 " "

The capacities of the 1-inch and 1¼-inch pipes for up-feed are somewhat greater than those stated; but they are given as above, since these figures correspond closely to standard radiator tapping, and it is advisable to make the pipes of the same size as the tapped openings.

In high buildings with the down-feed system, the lower half of the risers should be based on not much more than half the capacities stated in the right-hand column, in order that the pipes may be of ample size to carry off the great amount of condensation from the radiators above, without making the steam too wet for use in the radiators below. The pipe to the lowest radiator connection should be not less than 2-inch.

Pipe Sizes.—Two-Pipe Risers. With the two-pipe system, the capacity of the risers is of course, considerably greater than with the one-pipe system, since the condensation is carried off through a separate system of returns.

Table V gives the approximate capacities of risers for the two-pipe system.

TABLE V

Capacities of Two-Pipe Risers

Size, Supply Riser	Capacity, Up-Feed System	Capacity, Down-Feed System	Size, Return Riser
1 inch	50 sq. ft.	55 sq. ft.	¾ inch
1¼ inches	100 " "	115 " "	1 "
1½ "	150 " "	175 " "	1 -1¼ inches
2 "	270 " "	325 " "	1 -1¼ "
2½ "	470 " "	570 " "	1¼-1½ "
3 "	840 " "	1,000 " "	1¼-1½ "
3½ "	1,200 " "	1,480 " "	1½-2 "
4 "	1,600 " "	2,000 " "	1½-2 "

In buildings over six stories high, with the up-feed system, use 10 per cent less surface than stated in the third column, to allow for the increased length and condensation.

Pipe Sizes, Indirect. Supply connections with indirect radiators must be larger for a given surface than for direct radiators. The following table gives ample sizes when the radiators are but little above the water line of the boiler. When this distance is con-

TABLE VI

Sizes of Supply Connections for Indirect Radiators

Diameter of Pipe	Indirect Radiating Surface Supplied
1 inch	40 sq. ft.
1¼ inches	70 " "
1½ "	100 " "
2 "	180 " "
2½ "	330 " "
3 "	600 " "
3½ "	900 " "
4 "	1,200 " "
4½ "	1,600 " "
5 "	2,100 " "
6 "	3,400 " "
7 "	5,400 " "
8 "	7,200 " "

siderable, the pipes may be safely rated to supply one-third more surface; for a greater drop in pressure may be allowed between the

supply and the return mains, and drop in pressure means a greater velocity in the pipes, and consequently a greater flow of steam to the radiators.

Indirect radiators are seldom tapped larger than 2 inches; therefore radiators that require larger connections should be subdivided in groups.

STEAM PRESSURES AND TEMPERATURES

Steam pressures and temperatures have a certain definite relation to each other, the temperature increasing with the pressure, but not as rapidly for a given increase with high-pressure as with low-pressure steam. For example, with an increase in pressure from 10 pounds to 20 pounds, the temperature rises about 19° F.; whereas with an increase of 10 pounds from 90 to 100 pounds the temperature increases

TABLE VII

Temperature of Steam at Various Pressures

Vacuum (in Inches of Mercury)	Temp. °F.	Gauge Pressure (lbs. per sq. in.)	Temp. °F.
0	212.1	0	212
5	203.1	1.3	216.3
10	192.4	2.3	219.4
12	187.5	3.3	222.4
14	182.1	4.3	225.2
16	176.0	5.3	227.9
18	169.4	10.3	240.0
20	161.5	20.3	259.2
22	152.3	30.3	274.3
24	147.9	40.3	286.9
26	125.6	50.3	297.8
28	101.4	60.3	307.4
		70.3	316.0
		80.3	323.9
		90.3	331.1
		100.3	337.8
		150.3	365.7
		200.3	387.7

only about 7° F. From atmospheric pressure to 10 pounds' gauge pressure, the increase in temperature is nearly 28° F; a slight difference in the pressure in radiators making a marked difference in their temperature.

In the case of a *partial vacuum*, so called—expressed generally

in inches of mercury—the decrease in temperature as a condition of perfect vacuum is approached is very marked, as shown in table VII, which gives also steam temperatures corresponding to various pressures. The latter are given in each case $\frac{3}{10}$ of a pound in excess of the gauge pressure, as practically all tables of the properties of steam give the absolute pressure—that is, the pressure above a vacuum—the absolute pressure corresponding to 5.3 pounds' gauge pressure, for example, being 20 pounds absolute.

The atmospheric pressure at sea-level is practically 14.7 pounds absolute, and the boiling point of water is 212°. As the pressure decreases, due to altitude or to the removal of air from a vessel by artificial means, the boiling point falls.

EXPANSION

Amount of Expansion. An allowance of $\frac{8}{1000}$ of an inch per 100 feet of pipe for each degree rise in temperature, is a fair allowance in computing the amount of expansion that will take place in a line of pipe.

One must assume the temperature at which the pipe will be put up—say anywhere from 0° to 40° in an unfinished building in winter—and, knowing the pressure to be carried, look up in a table of the properties of saturated steam the temperature corresponding. See table VII.

Example. Find the expansion that will take place in a line 100 feet long put up in 30-degree weather, when it is filled with steam at 80 pounds' pressure. The temperature corresponding to 80 pounds'



Fig. 29. Offset and Swivels.

steam pressure is 324°; the increase from 30° is 294°, which multiplied by $\frac{8}{1000}$ gives $2\frac{35}{100}$ inches expansion, or, expressed in decimals, 2.35 inches.

In low-pressure work 100 feet of pipe heated from 30° to 230° will expand about 1.6 inches.

Provision for Expansion. The expansion of mains can generally be provided for by offsets and swivels, as shown in Fig. 29. All that is necessary is to have the two vertical nipples placed far enough apart, as determined by the length of the horizontal offset, to permit the expansion to take place without too much turning on the threads. The less the turn, the less will be the likelihood of leakage. The shorter the offsets, the greater the number that must be used.



Fig. 30. Swing to Allow for Expansion of Risers.

A pretty conservative rule would be to allow 4 feet of offset to each inch of expansion to be taken up on the line. In the case of underground work a good deal of the expansion can be taken up where pipes enter buildings by the same kind of swings as shown in Fig. 29, making them longer and thus reducing the number of expansion joints or offsets in the tunnel or duct.

Expansion of Risers. In providing for the expansion of risers, considerable skill must be used, especially in tall buildings. In buildings of not over 6 to 8 stories, or possibly 10 floors at the outside, if they are not high-studded, the expansion may all be taken up in the basement, using swings like those shown in Fig. 30, similar swings being used in the attic also if the overhead-feed system is used, the connections being taken from the bottom of the main, as previously stated.

In higher buildings than those mentioned, either slip-pattern expansion joints or swivels made up of pipe and fittings are commonly used. One of these to every six to eight floors is generally considered sufficient, depending on the length and arrangement of the radiator connections. One must be sure the pipes above and below slip joints are in proper alignment; otherwise, binding and leakage will occur. If the risers are concealed, such joints must be made accessible through proper openings in the walls, as the packing will have to be taken up from time to time and replaced.



Fig. 31. Expansion Joints. Offsets Nearly Horizontal.

Expansion joints made up of pipes are illustrated in Fig. 31. Such joints are unsightly if exposed; but they may generally be concealed either in specially provided pockets in the floor or in spaces furred down below the ceilings and near the walls.

When expansion joints are used, the risers should be anchored about midway between them. These anchors consist merely of clamps around the pipes fastened to the beams, one type being shown in Fig. 32.



Fig. 32. Anchor for Riser.

Radiator Connections. Considerable ingenuity is exhibited by good fitters in arranging radiator connections. One should always study the end sought, and then provide the necessary means to secure that end. For example, on a floor at which the riser is anchored, almost any sort of radiator connection will answer, since expansion need not be provided for.

Where expansion takes place, swivels must be provided in the radiator connections, to allow for same. Fig. 33 shows a convenient way of taking off radiator connections from risers, any expansion



Fig. 33. Radiator Connections from Riser.

being taken up by the turning of the horizontal connection in the parallel nipples. The connection should of course pitch back toward

the riser, to drain freely. Where the expansion is considerable, this is difficult to accomplish unless the radiator is slightly raised.

When risers must be located along the same wall as that on which the radiator is placed, the swivels may be arranged as shown in Fig. 34.



Fig. 34. Arrangement of Swivels when Risers are Located on the Same Wall as Radiator.

Radiators on the first floor have their connections made by angle valves with the pipes in the basement, to avoid running along the base-board. It is well to take the branch to the first-floor radiators from riser connections in the basement, rather than to cut into the mains for these branches. See Fig. 35.

COMPUTING RADIATION

Computing Direct Radiation. It is a perfectly simple matter to compute the amount of radiation required to heat a room, by finding the probable loss of heat per hour, and dividing this by the heat given off by a square foot of radiating surface in the same time.



Fig. 35. Branch from Riser Connection in Basement.

Numerous tests have shown that an ordinary cast-iron radiator gives off approximately 1.6 heat units per hour per degree difference in temperature between the steam and the surrounding air. With low-pressure heating a square foot of direct radiation is commonly rated at about 250 H. U. Glass transmits about 85 heat units per square foot per hour, with 70° inside and 0° out; and walls of ordinary thickness may be reckoned as transmitting one-fourth as much heat.

The heat losses stated should be increased about 25 per cent for a north or west exposure, and about 15 per cent for an easterly exposure.

An allowance should be made for reheating rooms that are allowed to cool down slightly at night. This may be done most con-

veniently by adding to the loss of heat through walls and glass a number of heat units equal to 0.3 of the cubic contents of a room with two exposures, and 0.6 the contents of a room with a single exposed wall.

The way this works out may best be shown by a couple of examples:

Suppose we have a room 16 feet square and 10 feet high, with two exposed walls facing respectively north and west, each having a window three feet 6 inches by 6 feet.

Exposure of room = (16 + 16) × 10 =	320 sq. ft.
Glass surface = 2 × 21 sq. ft. =	42 " "
Net wall	278 sq. ft.
Equivalent glass surface (E. G. S.) of net wall = 278 ÷ 4 = Approximately	70 sq. ft.
Actual glass surface =	42 " "
Total E. G. S. Approximately	112 sq. ft.
Heat transmitted = 112 sq. ft. × 85 heat units × 1.25 factor =	11,890 H. U.
Allowance for reheating = 0.3 × cubic contents of 2,560 cu. ft. =	768 " "
Total heat loss to be made good by direct radiation	12,658 H. U.

This 12,658 heat units, divided by 250, the amount given off by one square foot of radiation in one hour, = 50 sq. ft. approximately, giving a ratio of 1 sq. ft. of radiating surface to 53 cubic feet of space.

Take as a second example a room with one exposure toward the east, the dimensions of the room being 14 by 14 by 10 feet, with one window 4 by 6 feet. Proceeding as before,

Exposure =	196 sq. ft.
Glass =	24 " "
Net wall	172 sq. ft.
E. G. S. of net wall = ¼ of same =	43 " "
Add actual glass =	24 " "
Total E. G. S.	67 sq. ft.
Heat loss per hour = 67 × 85 × 1.15 =	6,549 H. U.
Add 0.6 the contents to allow for reheating; 0.6 × 1,960 =	1,176 " "
Total heat loss	7,725 H. U.

This 7,725 heat units ÷ 250 = 31 sq. ft. radiation required, giving a ratio of 1 to 63 cubic ft.

The loss of heat through roofs and through ceilings to unheated attic spaces above may be allowed for conveniently, and with sufficiently close approximation to the actual heat loss, by dividing the area of the roof by 10, and that of the ceiling by 20, to give the E. G. S.

In the case of a well-constructed plank roof, with paper or other material above that will prevent the leakage of air, the roof area may safely be divided by 15 to ascertain the E. G. S.

It is hardly necessary, as a rule, to allow for the loss of heat through a first floor to the basement when the latter is well enclosed and contains steam and return mains or is otherwise kept at a moderate temperature.

Computing Direct-Indirect Radiation. The most common method of computing the amount of direct-indirect radiation required, is to ascertain, in the manner described, the direct radiating surface necessary, and add to it approximately 25 per cent; that is, if a direct radiator of 100 square feet were found to be necessary to heat a given room, a direct-indirect radiator of 125 square feet would be required.

Computing Indirect Radiation. To compute the amount of indirect radiation necessary to heat a given room, about the simplest method to grasp is to compute, first, the direct radiation required, as previously explained, and then add 50 per cent to this amount, since it happens that, under average conditions of 70° inside and 0° outside, practically 1½ times as much surface is required to heat a given space with indirect as with direct heating.

When a stated air supply is required, the loss of heat by ventilation must be computed, and a different method followed in ascertaining the amount of indirect radiation required. For example, take a 50-pupil schoolroom with the common compulsory allowance of 30 cubic feet of air per minute per pupil—equal to 1500 cubic feet per minute per room. Each cubic foot escaping up the vent flue at 70° F., when the outside temperature is zero, removes from the room 1¼ heat units; hence the total heat loss by ventilation per hour would be $60 \times 1500 \times 1\frac{1}{4}$ = 112,500 heat units. A standard schoolroom has about 720 square feet of exposure, of which not far from 180 square feet is glass, leaving a net wall of 540 square feet, which, divided by 4, gives 135 square feet equivalent glass surface. This, added to the actual glass, gives 315 square feet E. G. S., which, in turn, multiplied by 85 heat units × a factor of 1.25 for north or west, gives a total heat loss by transmission of 33,470 heat units approximately.

The combined loss of heat by transmission and ventilation amounts to 145,970 H. U.

With the greater air-flow through indirect heaters used in schools, the heat emitted per square foot per hour should exceed somewhat the amount given off by indirect radiators in residence work—namely, 400 H. U. To be on the safe side, allow 450 H. U. The total heat

loss from the room, divided by this number, gives approximately 300 square feet as the surface required.

DUCTS, FLUES, AND REGISTERS

Areas of Ducts and Flues. The area of the cold-air connections with the benches or stacks of indirect radiators, are generally based on 1 to 1¼ square inches of area to each square foot of surface in the radiators.

The flues to the first floor should have 1½ to 2 square inches area to each square foot of surface; those to the second floor, 1¼ to 1½ square inches; and those to floors above the second, 1 to 1¼ square inches per square foot of radiation.

The sides and back of warm-air flues in exposed walls should be protected from loss of heat by means of a nonconducting covering, preferably ½ inch thick.

Flue Velocities. A fair allowance for flue velocities with indirect steam heating is 275 feet per minute for the first floor, 375 feet for the second, 425 feet for the third, and 475 for the fourth.

Registers. The net area of registers should be 10 to 25 per cent in excess of the area of the flue with which they are connected. The net area of a register is commonly taken as ⅔ the gross area; that is, a 12 by 15-inch register would have a net area of 120 square inches.

Registers in shallow flues must either be of the convex pattern, or be set out on a moulding to avoid having the body project into the flue and cut off a portion of its area.

Aspirating Heaters and Coils. To cause a more rapid flow of air in ventilating flues in mild weather, steam coils or heaters are used. These should be placed as far below the top of the vent flue as possible, for the higher the column of heated air, the greater the chimney effect. The smaller the flue in proportion to the volume of air to be handled, the larger should be the heater. If cast-iron indirect radiators are used, they may be rated to give off about 350 heat units per square foot per hour; coils may be rated to give off nearly double that number of heat units.

To illustrate how to compute the size of coil to be used, assume for example that 1,500 cubic feet per minute are to be removed

through a ventilating flue, the air to be raised 10° in temperature. Then

$$\frac{1{,}500 \text{ cu. ft. per min.} \times 60 \text{ min. per hour} \times 10° \text{ rise in temp.}}{55 \text{ heat units} \times 650 \text{ heat units per hour per sq. ft. of coil}} = 25.+ \text{ sq. ft. of coil required.}$$

(The number 55 is the number of cubic feet of air at 70° that 1 heat unit will raise 1° F.)

In order to work out important problems of this nature, it is necessary to consult a table giving flue velocities for different heights and for excesses of temperature of air in the flue over that out of doors. From such a table, knowing the height of the flue, its size, and the volume of air to be moved, it is readily seen how many degrees the air must be heated. The size of coil is then determined as above. The arrangement of an aspirating heater in a flue is shown in Fig. 36.



Fig. 36. Aspirating Regulator in Flue.

EXHAUST-STEAM HEATING

Buildings having their own power and lighting plant should be heated by exhaust steam, about 90 per cent of the steam that passes through the engines and pumps being available for this purpose.

A portion of this steam is used for heating the feed-water to the boilers. In a properly arranged system, very little fresh water need be supplied, since the condensation from the radiators, properly purified, is returned to the boilers.

To accomplish this purification, and to rid the steam of oil in order to prevent its coating the pipes and radiators, the steam is passed through a separator attached to the heater when all the steam is allowed to enter it, or through an independent separator when only a portion of the steam passes through the feed-water heater. Only about one-sixth of the exhaust steam in a given plant is required to heat the feed-water that must be supplied to the boilers to take the place of the steam used in the engines, therefore all the exhaust need

not enter the heater for the purpose of keeping up the proper temperature of the feed-water.

A type of heater with a coke fitter is shown in Fig. 37; while Figs. 38 and 39 show two methods of making connections, the first when all



Fig. 37. Heater with Coke Fitter.

the steam is allowed to pass through the heater, the latter when only a portion of the exhaust from the engines is allowed to enter.

A very essential appliance used with exhaust-steam heating is the *pressure-reducing valve*, which makes good with live steam any de-

ficiency in exhaust that may occur. By adjusting the weight, any desired pressure, within limits, may be obtained.



Fig. 38. Method of Making Connections when All the Steam is Allowed to Pass Through the Heater.

A *back-pressure valve* must be used with exhaust-steam heating, to regulate the pressure to be carried. It also acts as a safety-valve in case of over-pressure from any cause.



Fig. 39. Method of Making Connections when Only a Portion of Exhaust from Engine is Allowed to Enter.

Heating systems are sometimes arranged by bringing to them live steam to be reduced in the building to any desired pressure by a reduc-

ing valve. In such cases there is no back-pressure valve; therefore a safety-valve should be placed on the main to act in case of trouble with the reducing valve and prevent too great a pressure on the radiators.

A by-pass should be used in connection with all pressure-reducing valves, to provide for overhauling them. A steam gauge connected not less than 6 feet from the valve on the low pressure side is a necessary attachment.

With exhaust-steam heating, an exhaust head should be placed at the top of the vertical exhaust main, to condense, as far as possible, the steam passing through it.

The drip pipe from the exhaust should be connected with the drip tank; or, if the exhaust has been passed through a first-class separator, it may, if desired, be returned to the feed-water heater.

When a closed type feed-water heater is used (see Fig. 40), a separate tank must be provided for the returns from the heating systems. High-pressure drips are trapped to this tank. In the case of the heater shown in Fig. 37, the live-steam returns are trapped to it. A common type of trap is shown in section in Fig. 41. In the position shown, the float or bucket hinged as shown, is held up by the buoyancy of the water, and keeps the valve at the upper end of the spindle in contact with the seat, preventing the escape of steam entering with the water through the inlet. The water, rising around the bucket, overflows it and overcomes its buoyancy, causing it to fall and open the valve, the steam pressure on the water then forcing it out of the bucket until a point is reached where



Fig. 40. Closed Type Feed Water Heater.

the buoyancy of the bucket again comes into play and closes the valve until the action is again repeated.

An extremely simple form of float trap is shown in Fig. 42, the



Fig. 41. Common Type of Trap.



Fig. 42. Float Trap.

hollow float raising the spindle and valve, permitting water to escape, but falling and thus closing the outlet when the water level reaches a point too low to cause the ball to float, thus preventing the escape of steam.

Special forms of traps known as *return traps* are used in small



Fig. 43. Dimensioned Sketches for Cutting Pipe.

plants for returning to the boiler the condensation from the heating system.

MODIFIED SYSTEMS OF STEAM HEATING

It is beyond the scope of this course to go into the details of the various modified or patented systems of steam circulation, yet it seems

advisable to point out the essential features of certain of these systems. The Webster and Paul Systems will be found described in Part III of the Instruction Paper on Heating and Ventilation.

Thermograde System. With this two-pipe system air valves are omitted; the supply valve on each radiator is of a special construction designed to be set to admit quantities of steam under different conditions—to fill the radiator $\frac{1}{4}$, $\frac{1}{2}$, $\frac{3}{4}$, or entirely full of steam. On the return end of each radiator is placed a so-called *auto-valve*, designed to permit the escape of air and water into a return pipe open to the atmosphere at the top. In the case of large buildings the water flows by gravity to a tank, from which it is pumped to the boilers.



Fig. 44. Hanger.



Fig. 45. Adjustable Hanger for Large Pipe.



Fig. 46. Sleeve for Encasing Pipe.

Some of the advantages claimed for this system are:—Absence of air-valves and air-lines; control of the heat emitted, by means of the special controlling valve at the supply end of each radiator. The piping is the same as for ordinary gravity systems.

Vapor System. This system is designed, as its name implies

to work on a very low pressure. The radiators, preferably of the hot-water type, must have considerably more surface than with low-pressure steam heating. A special valve is placed at the supply end of each radiator, designed to admit any desired volume of steam.



Fig. 47. Globe Valve.

A little trap or water-seal fitting is connected with the return end of each radiator, a small hole being provided above the water line to permit the escape of air. All returns are joined in the basement and discharge to an open water column alongside the boiler, any steam in the returns being condensed by passing into a coil provided for the purpose.

No safety valve is required with this system. In case of an excess of pressure in the boiler, the water is backed out into the column above mentioned; a float is raised; and dampers are closed.



Fig. 48. Gate Valve.

The advantages claimed are:—Complete control of the heat given off by the radiators by means of the special regulating valve on each; absolute safety; small pipes; absence of air-valves.



Fig. 49. Iron Body Globe Valve.

Mercury Seal Vacuum Systems. In one of these systems, commonly used with gravity-return apparatus, air-valves similar to those shown in Fig. 55 are placed on the radiators, and the air-lines connected with a main line discharging through a mercury seal or column, the function of which is to seal the end of the pipe and prevent the entrance of air after the air from the system has been expelled by

raising the steam pressure. In another mercury seal system, air-valves are omitted and "retarders"—so called—are placed at the return ends of radiators.

With a tight job of piping when the air in the system has once been got rid of, the plant may be run for some time—or until air leaks in again—at a pressure less than the atmosphere and with radiators at temperatures corresponding to those of hot-water radiators.

Among the claims made for this system are:—Wide range of temperature in the radiators, secured by varying the degree of vacuum; the advantage of a hot-water heating system without large radiators, since steam under pressure can be carried in the radiators in cold weather.



Fig. 50. Radiator Angle Valve.


Fig. 52. Radiator Offset Valve.


Fig. 51. Radiator Straightway Valve

PIPE AND FITTINGS

Pipe. Pipe for heating systems should be made of wrought iron or mild steel. Sizes up to 1¼ inches diameter inclusive, are butt-welded and proved to 300 pounds' pressure; above that size they are lap-welded and tested to 500 pounds' pressure.

TABLE VIII

Standard Weight Pipe Dimensions and Data

Diameters (Inches)			Areas (Square Inches)			Miscellaneous					
Nominal Diameter	Actual External Diameter	Actual Internal Diameter	External Area	Internal Area	Area of Metal	Thickness of Metal	Linear Feet per Square Foot of External Surface	Linear Feet to Contain One Cubic Foot	Pounds of Water per Linear Foot	Nominal Weight of Pipe per Foot (Pounds)	Threads per Inch	Taper of Threads per Inch of Screw
⅛	.405	.269	.1288	.0568	.0720	.068	9.44	2.500	.024	.241	27	¾
¼	.540	.364	.2290	.1041	.1249	.088	7.075	1.385	.044	.42	18	¾
⅜	.675	.493	.3578	.1909	.1669	.091	5.657	.731.5	.083	.559	18	¾
½	.840	.622	.5542	.3039	.2503	.109	4.502	472.4	.132	.837	14	¾
¾	1.050	.824	.8659	.5333	.3326	.113	3.637	270	.23	1.115	14	¾
1	1.315	1.047	1.3581	.8609	.4972	.134	2.908	166.9	.373	1.668	11½	¾
1¼	1.660	1.380	2.1642	1.4957	.6685	.140	2.301	96.25	.648	2.244	11½	¾
1½	1.900	1.610	2.8353	2.0358	.7995	.145	2.01	70.65	.893	2.675	11½	¾
2	2.375	2.067	4.4301	3.3558	1.074	.154	1.611	42.36	1.454	3.609	11½	¾
2½	2.875	2.467	6.4918	4.7800	1.712	.204	1.328	30.11	2.073	5.739	8	¾
3	3.500	3.066	9.6211	7.3827	2.238	.217	1.091	19.49	3.202	7.536	8	¾
3½	4.000	3.548	12.566	9.886	2.680	.226	.955	14.56	4.285	9.001	8	¾
4	4.500	4.026	15.904	12.730	3.174	.237	.849	11.31	5.517	10.665	8	¾
4½	5.000	4.508	19.635	15.960	3.675	.246	.765	9.08	6.908	12.34	8	¾
5	5.563	5.045	24.306	19.985	4.321	.259	.689	7.20	8.668	14.502	8	¾
6	6.625	6.065	34.472	28.896	5.586	.280	.577	4.98	12.52	18.762	8	¾
7	7.625	7.023	45.664	38.743	6.921	.301	.501	3.72	16.79	23.271	8	¾
8	8.625	7.981	58.426	50.021	8.405	.322	.444	2.88	21.68	28.177	8	¾
10	10.750	10.018	90.763	78.822	11.94	.366	.355	1.80	34.17	40.065	8	¾
12	12.750	12.000	127.68	118.09	14.59	.375	.293	1.235	49.02	48.985	8	¾

Circumference = Diameter × 3.1416.
1 cu. ft. = 7½ gallons.
1 gallon = 231 cu. inches.

1 cu. ft. of water weighs 62.4 lbs.
1 gallon of water weighs 8⅓ lbs.

Pipe is shipped in lengths of 16 to 20 feet, threaded on both ends and fitted with a coupling at one end.

It is well, as a rule, to have pipes $2\frac{1}{2}$ inches in diameter and larger cut in the shop from sketches. These should give the distances from end to center, or center to center, and should state the size and kind of valves, whether flanged or screwed fittings are to be used, and in a general way should follow Fig. 43.

The dimensions of standard pipe are given in Table VIII.

NOTES ON WROUGHT-IRON PIPE

(Furnished by the Crane Company, Chicago, Ill.)

WROUGHT-IRON PIPE:—This term is now used indiscriminately to designate all butt- or lap-welded pipe, whether made of iron or steel.

MERCHANT PIPE:—This term is used to indicate the regular wrought pipe of the market, and such orders are usually filled by the shipment of soft steel pipe. The weight of merchant pipe will usually be found to be about five per cent less than card weight, in sizes $\frac{1}{8}$-inch to 6-inch, inclusive; and about ten per cent less than card weight, in sizes 7-inch to 12-inch, inclusive.

FULL-WEIGHT PIPE:—This term is used where pipe is required of about card weight. All such pipe is made from plates which are expected to produce pipe of card weight; and most of such pipe will run full card to a little above card, but, owing to exigencies of manufacture, some lengths may be below card, but never more than five per cent.

LARGE O. D. PIPE:—A term used to designate all pipe larger than 12-inch. Pipe 12-inch and smaller is known by the nominal internal diameter, but all larger sizes by their external (outside) diameter, so that "14-inch pipe," if $\frac{3}{8}$ inch thick, is $13\frac{1}{4}$-inch inside, and "20-inch pipe" of same thickness is $19\frac{1}{4}$-inch inside.

The terms "Merchant," or "Standard pipe," are not applicable to "Large O. D. pipe," as these are made in various weights, and should properly be ordered by the thickness of the metal.

When ordering large pipe threaded, it must be remembered that $\frac{1}{4}$-inch metal is too light to thread, $\frac{5}{16}$-inch being minimum thickness.

Orders for large outside diameter pipe, wherein the thickness of metal is not specified, are filled as follows:

Fourteen, fifteen, and sixteen inch, O. D., $\frac{5}{16}$-inch or $\frac{3}{8}$-inch metal.

Larger sizes, $\frac{3}{8}$-inch metal.

This pipe is shipped with plain ends, unless definitely ordered "threaded."

EXTRA STRONG PIPE:—This term designates a heavy pipe, from $\frac{1}{8}$-inch to 8-inch only, made of either puddled wrought iron or soft steel. Unless directed to the contrary, steel pipe is usually shipped. If wrought-iron pipe is required, use the term, "Strictly Wrought-Iron Extra Strong Pipe." Extra strong pipe is always shipped with plain ends and without couplings, unless instructions are received to thread and couple, for which there is an extra charge.

This term, when applied to pipe larger than 8-inch, is somewhat indefi-

nite, as 9-, 10-, and 12-inch is made both $\frac{7}{16}$ and $\frac{1}{2}$ inch thick. Pipes $\frac{1}{2}$ inch thick are carried in stock, and furnished on open order.

DOUBLE EXTRA STRONG PIPE:—This pipe is approximately twice as heavy as extra strong, and is made from $\frac{1}{2}$ to 8 inches, in both iron and steel. It is difficult, however, to find any quantity in "Strictly Wrought-Iron," and the stock carried is usually soft steel. This pipe is shipped with plain ends, without couplings, unless ordered to thread and couple, for which there is an extra charge.

Fittings. For low-pressure heating systems, standard weight cast-iron screwed fittings are used on pipes up to 7 inches or 8 inches diameter. On larger pipes it is customary to use standard flanged fittings. Flange unions should be placed at intervals in the pipes when screwed fittings are used, to provide for readily disconnecting them in case of alterations or repairs.



Fig. 53. Radiator Valve.

Pipe grease or various compounds are used in "making up" the joints. This material should be applied to the male threads only. When the threads of the fittings are coated with it, as is commonly done, the compound is pushed into the fitting when the pipe is screwed in, and, becoming disengaged, is likely to cause trouble later by clogging pipes, etc. For flange fittings it is the practice with many fitters to use inside gaskets, so called, cut to come just inside the bolts.



Fig. 54. Swing Check Valve.



Fig. 55. Air Valve.

To describe a tee, always give the dimensions of the "run" first and the outlet last; for example, a tee 6 inches at one end, 5 inches at the other, with an outlet at the side $3\frac{1}{2}$ inches, would be known as a 6 by 5 by $3\frac{1}{2}$ tee.



Fig. 56. Air Valve.

A tee with the outlet larger than the openings on the run, is known

as a *bullhead* tee. Tees with all three openings of the same size are known as *straight* tees.

It is far better to use reducing sockets or reducing elbows and tees, in place of straight tees with bushings.

Hangers. Pipes up to 4 inches diameter inclusive are commonly suspended by malleable-iron hangers, one type of which is shown in Fig. 44, with a gimlet point on the rod, a beam clamp being substituted when I-beams are used in place of floor timbers. One form of adjustable hanger for large pipes is shown in Fig. 45.



Fig. 57. Pipe Vise.



Fig. 58. Flat Jaw Vise.

Sleeves, etc. Where pipes pass through floors and partitions, they are encased in tubes with plates at floor and ceiling or at walls, as the case may be. One type of these sleeves is shown in Fig. 46.



Fig. 59. Combination Vise.

Where branches from risers pass through partitions, it is often necessary to use sleeves of elliptical shape to provide for the expansion

of the risers. . Sleeves for mains passing through basement walls are generally made of pieces of wrought-iron pipe of the proper length, the diameter of the sleeves to be not less than ½ inch greater than the pipe diameter if covering is omitted in walls, and 2¼ inches greater if covering is continuous along the pipe.



Fig. 60. Pipe Cutter.

When sleeves are placed in plastered walls, they should project a slight distance beyond the face of the plaster. When ceiling plates are made fast to risers, they should be placed at least ⅜ inch down from the ceilings, so that, when the riser expands, the ceiling plate will not be forced into the plaster.



Fig. 61. Pipe Cutter.

Valves. Valves for basement piping are commonly *globe* or *gate* pattern, with rough bodies and plain iron wheels (Figs. 47 and 48). Brass or composition body valves, with screwed tops, are generally used up to 2-inch size inclusive; and iron body valves, with bolted tops, above that size (see Figs. 48 and 49). Both are made with renewable discs or seats.



Fig. 62. Solid Die.

It is largely a matter of preference which type of valve shall be used, though of course the straightway gate valves interpose the least resistance to the flow of steam or water.

When the radiators are but little above the water line in the boiler, gate valves are frequently used on the returns to insure an easy flow of the water.

It seems hardly necessary to point out that a globe valve should be connected in the pipe with its stem horizontal, to avoid the water pocket which occurs when the stem is vertical; nevertheless fitters frequently overlook this point.

Several patterns of radiator valves are shown in Figs. 50, 51,

52, and 53. These valves are of brass or composition, rough body nickel-plated, have wood wheels, and are provided with a union. The angle valves are commonly used on first-floor radiators, those on floors



Fig. 63. Stock for Solid Dies.

above having offset or corner offset, offset globe, or straightway gate valves, according to the type of radiator and the arrangement of connections to provide for expansion.

In public buildings, the wheels are often omitted and lock-shields substituted, the valves being operated by a key.

A *swinging-check* valve is shown in Fig. 54. This type, if prop-



Fig. 64. Adjustable Die and Stock.

erly designed, works the easiest of any, and should be used in preference to other types when radiators are placed but little above the water line in the boiler.

Air-Valves. Numerous patterns of air-valves are on the market, some, like Fig. 55, in a general way, being fitted with a union for air-line connections leading to a convenient point of discharge in the basement. Such valves prevent the escape of steam, because of the expansion of the composition plug, which closes the opening when steam

comes in contact with it. Air and cold water, however, are permitted to escape.

The general type of air-valve shown in Fig. 56 is frequently used, many modifications of this valve having been manufactured. These



Fig. 65. Adjustable Die and Stock.

valves, as a rule, have no air-line connections, but discharge their air into the rooms; a somewhat objectionable feature. They close when steam enters them; and if water finds its way in, the float is raised and closes the outlet.

Air-valves for direct radiators have a very small opening for the



Fig. 66. Hand Power Pipe Machine.



Fig. 67. Belt Power Pipe Machine.

discharge of air, scarcely larger than a pin-hole; and while these do very well for small units, they are not satisfactory for large coils or for

large groups of indirect radiators, because of the excessive time required to relieve them from air. For such heating surfaces, a type of air-valve with a much larger opening should be selected, to provide for venting the radiators or coils more quickly.

Several types of vacuum air-valves have been invented, designed to permit the escape of air from the radiators, but to prevent its reentry. If they remain tight, the steam heating system may be run in mild weather with a pressure below that of the atmosphere, and the radiator kept at a temperature below 200°.



Fig. 68 *a*. Hand Power Pipe Machine.

Pipe-Fitting Tools.—Vise and Bench. When a job is started, the first things needed are vise and bench. The latter should be firmly constructed, and rigidly held in place, the vise to be firmly secured to it by through bolts.

On a good-sized piece of work, it is well to have both a *pipe vise* and a *flat-jaw vise*, these being illustrated in Figs. 57 and 58. A heavy cover should be furnished over the screw of the flat-jaw vise, to provide a bearing for bending pipe, the end of which is passed through a ring bolted to the bench.

Fig. 59 illustrates a combination of the two vises shown in Figs. 57 and 58, making a very useful tool.

Pipe Cutters. There are several kinds of pipe cutters on the market, made with one or more cutting wheels held in a frame. All makes of cutters are operated in practically the same way, by forcing the cutting wheels into the pipe by means of a screw handle. One- and three-wheel cutters are shown in Figs. 60 and 61. The one-wheel

cutters are made in sizes for $\frac{1}{8}$-inch to 3-inch pipe; and the three-wheel cutters, for $\frac{1}{8}$-inch to 8-inch pipe.

Stocks and Dies. The several forms of dies and stocks on the market may be divided into two classes—the *solid die* and the *adjustable die.* The solid die is shown in Fig. 62, and is used for cutting both right-hand and left-hand threads. The stock in which solid dies are used is shown in Fig. 63. Adjustable dies and stocks are shown in Figs. 64 and 65. These dies may be adjusted to cut a deep or a shallow thread. It is necessary at times to cut such threads, as the fittings made by different manufacturers are not always tapped alike. To make good joints, the threads must make up tight when they are screwed into the fitting.



Fig. 68 *b.* Hand Power Pipe Machine.

Table IX shows the approximate distance pipes must be screwed into fittings to make a tight joint.

TABLE IX

Proper Distance to Screw Pipes into Fittings

$\frac{1}{4}$, $\frac{3}{8}$, and	$\frac{1}{2}$	inch	pipe	should	be	screwed	into	fittings	approximately	$\frac{3}{8}$	in.
	$\frac{3}{4}$	"	"	"	"	"	"	"	"	$\frac{1}{2}$	"
	1	"	"	"	"	"	"	"	"	$\frac{11}{16}$	"
$1\frac{1}{4}$ and	$1\frac{1}{2}$	"	"	"	"	"	"	"	"	$\frac{5}{8}$	"
	2	"	"	"	"	"	"	"	"	$\frac{3}{4}$	"
$2\frac{1}{2}$ and	3	"	"	"	"	"	"	"	"	$\frac{7}{8}$	"
$3\frac{1}{2}$ and	4	"	"	"	"	"	"	"	"	1	"
5 and	6	"	"	"	"	"	"	"	"	$1\frac{1}{8}$	"
	7	"	"	"	"	"	"	"	"	$1\frac{1}{4}$	"
8 and	9	"	"	"	"	"	"	"	"	$1\frac{3}{8}$	"
10 and	12	"	"	"	"	"	"	"	"	$1\frac{1}{2}$	"

In all forms of stocks, whether for solid or adjustable dies, a bushing or guide must be used in the stocks to guide the dies straight onto the pipe. It is necessary that the guides for the different sizes of pipe should fit each size of pipe as closely as will allow the guide to revolve on the pipe freely. The guides should fit the stock as tightly as possible, or a crooked thread will very likely be cut.



Fig. 69. Pipe Tongs.



Fig. 70. Adjustable Pipe Tongs.

Plenty of good lard oil or cotton-seed oil should be used when cutting pipe. The dies must be sharp, to make good joints; and when they are changed in the stocks from one size to another, all chips of iron and dirt should be cleaned off the dies and out of the stocks, as a small chip under dies, especially under one of a set of adjustable dies, will either cut a crooked thread or strip it.



Fig. 71. Chain Tongs.

Stocks are made in sizes from $\frac{1}{8}$ inch to 4 inches. The small-size stocks and dies commonly carried in pipe-fitters' kits are made to thread pipe from $\frac{1}{8}$ inch to 1 inch inclusive, right-and left-hand; and a larger size to thread pipe from 1 inch to 2 inches inclusive, right- and left-hand. A larger-size stock is used to cut pipes over 2 inches in diameter.

There are a number of hand-power pipe machines on the market,



Fig. 72. Chain Tongs.

which are very convenient especially for cutting and threading pipe $2\frac{1}{2}$ inches and over. Several makes are shown in Figs. 66, and 68 *a* and 68 *b*.

Pipe Tongs. Plain tongs, like all other tools, must be kept sharp and in good order, to do good work. Many fitters object to tongs because they have to be sharpened very often, and also because they

have to carry at least one pair of tongs for each size of pipe; they prefer an adjustable wrench which will fit several different sizes of pipe. There is one advantage in the tongs; that is, they can be worked in places where it would be impossible to use a wrench, such as making up pipe in coils, close corners, etc. Tongs should be made in such a way that when they are on the pipe, the handles will come close enough together to allow them to be gripped in one hand (see Fig. 69).



Fig. 73. Pipe Wrench.



Fig. 74. Pipe Wrench.

Adjustable tongs (Fig. 70) are made to fit several sizes of pipe, the most common sizes used being for ⅜-inch to 1-inch to 2-inch, and for 2½-inch to 4-inch.

Fig. 75. Wrench for Brass or Nickle-Plated Pipe.

Chain tongs are made in all sizes and in several forms for from 1-inch up to 16-inch pipe. Some makers furnish tongs with the handle and jaws in one piece. Others have the jaws removable. Still others have the jaws so arranged that they can be removed and reversed. See Figs. 71 and 72.

Fig. 76. Wrench for Brass or Nickle-Plated Pipe.

Pipe Wrenches. Several types of adjustable wrenches are shown in Figs. 73 and 74. These wrenches will do good work if used as wrenches on the size pipe they are intended for. Some men who have little regard for tools use on a 2-inch pipe, for example, a wrench which is made to take, say, not over 1-inch pipe, the jaw of the wrench being extended as far as possible, and probably being held by only a few threads of the adjusting screw, a piece of pipe 2 or 3 feet long often being used on the handle of the wrench to



Fig. 77. Monkey Wrench.

increase the leverage. After such usage, the wrench is of little value. At times men will use wrenches in such a way as to make the strain come on the side, with the result that the wrench is badly strained if not broken.



Fig. 78. Open-End Wrench.

The above described wrenches are used on wrought-iron pipe. For brass or nickel-plated pipe, wrenches like those shown in Figs. 75 and 76 should be used; otherwise the pipe will be marred and rendered unfit for use in connection with first-class work.

One of the handiest all-round tools is the *monkey wrench*, shown in Fig. 77. *Open-end* wrenches, illustrated in Figs. 78 and 79, are very handy tools, especially for use on flange fittings. Wrenches for lock-nuts are made about the same as above, only they are larger.



Fig. 79. Open-End Wrench.

The *return-bend wrench* is a very handy tool, and can be made by any good blacksmith. It is used principally on coil work, and is made of heavy bar iron, as shown in Figs. 80 and 81, in which two forms of this type of this wrench are shown.

Another handy tool is what is sometimes called, for want of a better name, a *spud wrench*. This is simply a piece of flat iron about



Fig. 80. Return-Bend Wrench.



Fig. 81. Return-Bend Wrench.

10 inches long and made to fit the spuds of the unions of different sizes of union radiator valves and elbows (see Fig. 82).

Pliers. For small work, pliers may be used to advantage. Common and adjustable types are shown in Figs. 83 and 84.



Fig. 83. Spud Wrench.

Drills, Reamers, and Taps. Pipe drills, illustrated in Fig. 85, are made slightly smaller for a given size than the taps illustrated in Fig. 86. A reamer like the one shown in Fig. 87 should be used to

start the tap, which should never be hammered in order to start the threads.

Fig. 88 shows a combined drill, reamer, and tap. Fig. 89 shows a pipe reamer for taking the burr from the ends of pipes.



Fig. 83. Common Pliers.

Fig. 84. Adjustable Pliers.

A *ratchet drill* is illustrated in Fig. 90 and a *breast drill* in Fig. 91. Fig. 92 shows a handy tool for drilling pipe flanges which from any cause cannot be drilled in the shop.

Fig. 85. Pipe Drill.

Figs. 93, 94, 95, and 96 show *cold, cape, diamond point,* and *round-nose* chisels respectively.

A good pattern *pean hammer* is shown in Fig. 97 *a*; and a *brick hammer* is represented by Fig. 97 *b*.

Miscellaneous. Every fitter's kit should contain inside and outside *calipers*; a good set of *bits* ¼-inch to 1-inch; *bit stock*; *augers* 1¼-inch to 2-inch; *saws*; *files*; *plumb-bob*; *gimlet*; *lamp*; *oil can*; *steel square*; *tape measure*; etc.

HOT-WATER HEATING

Heaters. Hot-water heaters—or "boilers," as they are sometimes miscalled—are so nearly like the cast-iron steam boilers previously illustrated, that it is unnecessary further to describe them here.

Some makers use the same patterns for both steam boilers and hot-water heaters, while others use a higher boiler for steam, giving more space above the water line.



Fig. 86. Pipe Tap.

Practically the same rules should be followed in selecting a hot-water heater as those laid down for steam boilers. Although a hot-water heater is a trifle more efficient than a steam boiler—that is, more of the heat in the coal is transferred to the water, owing to the temperature of the latter being 40 degrees or more lower than in a steam boiler—nevertheless, practically the

same size of hot-water heater or steam boiler is required to heat a given space.

It is well to equip the heater with a regulator, of which a number of good ones are manufactured, in order to control the drafts by variations in the temperature of the water, the regulator being set to maintain any desired temperature in the flow pipe.



Fig. 87. Reamer.

Capacity of Heaters. Hot-water heater capacities are based, as a rule, on an average water temperature of 160° in the radiators, when placed in rooms to be kept at 70° F.



Fig. 88. Combined Drill, Reamer and Tap.

If the *closed-tank system* is used, the radiator temperatures may be 220° to 230° or more; hence, if any attention is to be given to the manufacturers' heater rating, the radiation must be reduced to the equivalent radiation in heat-emitting capacity of radiators at 160°.

This is very easily computed, since the heat given off by a radiator is proportional to the difference in temperature between the water in the radiator and the air surrounding it. This, in the first case, is 160° less 70°,



Fig. 89. Pipe Reamer for Taking the Burr from Ends of Pipe.



Fig. 90. Ratchet Drill.

or 90°; and in the other case, say, 225° less 70°, or 155°; that is, one foot of radiating surface at 225° will give off $\frac{155}{90}$ of the heat given off at 160°; therefore, a job with 900 square feet, for example, at 225° would be equivalent in heating power to $\frac{155}{90} \times 900 = 1550$ square feet at 160°, and a boiler with the higher rating would be required

It is always well to check the boiler rating as explained under "Steam Heating," except that in hot-water heating only 150 heat units are allowed per hour per square foot of radiating surface.



Fig 91. Breast Drill.

Of the heat given off by the coal, it is safe to assume that 8000 heat units per pound are transferred to the water in the heater.

Suppose there are 900 square feet of radiation on the job. Add $\frac{1}{3}$ to cover the loss of heat from pipes; total = 1200 square feet. Assume that in coldest weather 5 pounds of coal are burned per hour on each square foot of grate; that is, $5 \times 8000 = 40{,}000$ heat units are transferred to the water in the heater. The heat given off per hour by the radiators and pipes is $1200 \times 150 = 180{,}000$ heat units. This, divided by 40,000, the heat utilized per square foot of grate, equals $4\frac{1}{2}$ square feet of grate required.



Fig. 92. Tool for Drilling Pipe Flanges.

Some judgment is necessary in assuming the rate of combustion; but this varies from about 3 pounds per square foot of grate per hour in small heaters, to 7 or 8 in larger ones, operated by a regular attendant.

HOT-WATER RADIATORS AND VALVES

Hot-water radiators have top and bottom nipple connections, as shown in Fig. 31, Part II (Heating and Ventilation). A hot-water



Fig. 93. Cold Chisel.

radiator may be used for steam, but a steam radiator cannot be used for hot water. The valve may be placed at the top or the bottom—it

matters little which; it is, however, more convenient, though more unsightly, at the top. The circulation will be practically as good when the valve is located at the bottom. One valve is all that is necessary,



Fig. 94. Cape Chisel.

and this may best be of the quick-opening pattern, a partial turn being all that is necessary to open or close it (see Figs. 44 and 45, Part II, Heating and Ventilation).



Fig. 95. Diamond-Point Chisel.

A union elbow is generally connected with the return end of a radiator (see Fig. 46, Part II, Heating and Ventilation).

Key-pattern air-valves are more frequently adopted in hot-water



Fig. 96. Round-Nose Chisel.

heating than are any types of automatic valves. They do not have to be operated often; hence the popularity of the simple and reliable air-cocks like those shown by Fig. 98.



Fig. 97 *a*. Pean Hammer.



Fig. 97 *b*. Brick Hammer.

Direct-indirect hot-water radiators are seldom used, owing to the danger from freezing in case they are thoughtlessly shut off.

Indirect radiators should be of a deep pattern—say, 10 to 12 inches, or even more for use with outdoor air in a severe climate. These radiators give off far less heat per square foot than is emitted by steam radiators; hence they should be deeper, to bring the air up to proper temperature.



Fig. 98. Air Cock.

HOT-WATER PIPING

Heater Connections. Where only one heater is used, the connections are practically the same as for steam heating, except that no check-valves are used.

Where two boilers are to be connected and arranged to be run independently or together, valves must be inserted somewhat as shown



Fig. 99. Arrangement of Valves for Two Boilers which are to Run Independently or Together.

by the plan view represented in Fig. 99. It is important that safety-valves be used with this arrangement, as, in case one boiler is shut down and then fired up without opening the stop-valves, the pressure due to the expanding water will burst the heater.

Single-Main System. The single-main system, arranged some-

what like the circuit system in steam heating, is sometimes employed for hot-water heating. Fig. 100 shows the arrangement of this system. The supply branches are taken from the top of the main, where the water is hottest; and the returns are connected at the side, the cooler water passing along the lower portion of the pipe back to the heater. On systems of considerable size, this arrangement of piping causes the water in the supply main to cool more rapidly as the distance from the heater increases than in systems where the supply and return water are kept separate.



Fig. 100. Single Main System.

Two-Pipe Up-Feed System. With the two-pipe up-feed system, the pipes should be pitched up from the boiler 1 inch in 10 feet, if possible. Pockets in which air can collect must be avoided, as air will cut off the flow as much as a solid substance in the pipe would do.

In the basement, the branches near the boiler should be taken from the side of the flow main, in order to favor the branches farther



Fig. 101. Two-Pipe Up-Feed System.

away, which should be taken from the top of the main. First-floor radiators should be given the preference, as to ease of flow in their connections, over riser connections with the floors above. If possible, feed the last first-floor radiator on a line before branching to riser. Fig. 101 illustrates the above points.

Keep the mains near the ends of long runs ample in size, even if somewhat larger than stated in the table, if runs are long and crooked. No chances should be taken in regard to insuring the proper circulation of water in the system. Use no horizontal pipe smaller than 1¼-inch.

Return mains pitch in the same direction as the flow pipes, and



Fig. 102. Connections for Return Mains.



Fig. 103. Distributing Fitting.

are generally paired with them, the connections being made on the side as shown in Fig. 102, or at an angle of 45 degrees.

The risers should be arranged to favor the radiators on the lower floors, since the water tends to rise and pass by the lower radiators.



Fig. 104. Arrangement of Pipes.

Distributing fittings, as shown in Fig. 103, are often used for this purpose, or the pipes may be arranged as shown in Fig. 104. Some labor is saved by the use of the special fittings described.

Overhead-Feed System. Where attic space is available, the overhead-feed system presents certain advantages over the two-pipe up-feed method of piping. In residences, single risers are used, these serving for both supply and return, the water entering the top of the radiator and flowing back into the same riser from the lower opening in the radiator. No air-valves are necessary, all air passing up the risers and out through the vent, on the expansion tank. The overhead mains are connected with a rising main large enough to



SECTIONAL VIEW OF CAST IRON HOT WATER HEATER

supply all the surface; these mains may be run around the building near the walls, as in the one-pipe steam circuit system; or may be carried down the middle of the building, with long branches extending to the risers near the walls, it being assumed that the radiators will be located near the exposed parts of the building.

The mains and branches should pitch down toward the risers, permitting the air to escape freely to the expansion tank (see Fig. 105).

Special care should be used in hot-water heating, to secure an easy flow. The ends of the pipes should be reamed, and long-turn



Fig. 105. Showing the Mains and Branches Pitched Down Towards the Risers.

fittings used for first-class work, although, if the piping is generously proportioned, standard fittings will answer. A hot-water thermometer should always be placed on the boiler or near it, in the flow-main.

Radiator Connections. For direct radiators, the connections are commonly 1-inch for sizes up to 40 square feet; 1¼-inch, for sizes of 72 square feet; 1½-inch to 2-inch for sizes larger than 72 square feet. On floors above the first, the connections may be made smaller if the horizontal runs are short, the sizes to conform to table.

Expansion-Tank Connections. About the simplest arrangement of expansion-tank connections is shown in Fig. 106. The expansion pipe is commonly connected with a return line in the basement, there being

less likelihood of the water boiling over in case of a hot fire with this arrangement than when the expansion pipe is merely an extension of a supply riser. There must be no valve on this pipe, as its closure would almost certainly result in a bursting of some part of the system.

Great pains must be taken to guard against the freezing of the expansion pipe. If there is any danger whatever, a circulating pipe should be added, as shown, this pipe being connected with one of the flow-pipes or supply risers, to insure a continuous circulation.



Fig. 106. Expansion Tank Connections.

Open-Tank versus Pressure System. The open-tank system, although having its disadvantages, is generally to be preferred to the pressure or closed-tank system. With the open-tank system, the water cannot get much above 212° at the heater, without boiling in the expansion tank and blowing part of the water out of the system, causing, meanwhile, objectionable noises in the system. On the other hand, the open expansion tank into which the water can freely expand when heated is the best possible safety device to prevent overpressure.

With the closed-tank system, a safety-valve is used. If it operates properly, well and good; otherwise an element of danger is introduced, and, in case an excessive pressure is developed, the heater becomes far more dangerous than a steam boiler, owing to the much greater volume of water in the system.

With this system, two safety-valves with non-corrosive seats should be used, unless some well-tested device of demonstrated merit designed especially for this purpose is adopted.

The advantage of the closed-tank system is that smaller radiators may be used, since they can be heated as hot with water under pressure as they would be if heated with steam.

When full street pressure is applied to a system, and no expansion tank is used, the radiators are subjected to an unnecessary

strain; and in case of rupture in any part of the system, much greater damage results than would be the case with an open-tank system.

System of Forced Circulation. In extensive systems the water is kept in circulation by pumps, which are capable of producing a much higher velocity in the pipes than could be secured by gravity. This system is used principally in connection with power plants, the water being heated in tubular heaters, by means of the exhaust steam from the engines. Much smaller supply mains may be used in this system than with steam heating, because of the greater capacity of water for carrying heat. On the other hand steam returns are smaller.

Table X gives the capacities of expansion tanks:

TABLE X

Radiation Capacities of Expansion Tanks

Capacity of Tank	Direct Radiating Surface to which Tank is Adapted
5 gallons	200 sq. ft.
10 "	450 " "
15 "	700 " "
20 "	1000 " "
30 "	1400 " "
40 "	1900 " "
50 "	2400 " "
60 "	2900 " "

COMPUTING RADIATION

Computing Direct Radiation. The process of computing hot-water radiating surface is precisely the same as that explained for ascertaining the amount of steam radiation required for a given case, with this important exception: the hot-water radiators give off only about $\frac{3}{5}$ as much heat per square foot as is emitted by a steam radiator; hence calculations must be based on an allowance of 150 heat units per square foot of direct radiating surface per hour, instead of 250 heat units used in connection with steam-heating work.

It has been stated that direct-indirect hot-water radiators are rarely used. In case, however, it is desired to compute the amount of this class of radiation for a given service, proceed as explained for steam heating, but allow only $\frac{3}{5}$ as much heat emitted per square foot as that given off by steam radiators.

Computing Indirect Radiation. With indirect hot-water radia-

tion in connection with the open-tank system, the radiators must be deeper than for steam heating, in order properly to heat the air.

The greater depth retards the flow of air; and since the water is at a much lower temperature than steam, the heating capacity of indirect extended-surface hot-water radiators should be taken at not far from 300 heat units per square foot per hour, as against 400 or more heat units for indirect steam radiation.

To compute the amount of radiation required, proceed as explained for indirect steam heating; that is, compute the amount of direct radiation as pointed out under the preceding heading, then add not less than 60 per cent to this amount, to ascertain the indirect radiating surface required.

This method, though perhaps crude, has the advantages of being simple and of affording a check on the work, since one soon knows by experience about what the ratio should be to heat a room of given size by direct radiation. For example, take a room with 3000 cubic feet, to heat which the ratio for direct radiation should be, say, 1 square foot to 30 cubic feet, giving a 100-square foot radiator. Adding 60 per cent for indirect radiation, gives 160 square feet, or a ratio of 1 square foot to a little less than 20 cubic feet of space.

Indirect hot-water radiators with extended pins or ribs will, with the open-tank system, give off not far from 250 to 300 heat units per hour per square foot of extended surface.

DUCTS AND FLUES

Areas of Ducts and Flues. When indirect radiation is installed primarily for heating, ventilation being a secondary consideration, it is desirable to make the flues somewhat smaller in proportion to the heating surface than is done with steam heating. If the flues are made too large, the flow through the radiators will be too rapid, and the air will not get hot enough. It costs far more in fuel to heat with a large volume of moderately warmed air than with a smaller volume of hotter air.

Duct and flue proportions for hot-water heating should be approximately as follows:—Cold-air ducts, $\frac{3}{4}$ to 1 sq. in. per sq. ft. of indirect radiating surface; first-floor flues, $1\frac{1}{4}$ to $1\frac{1}{2}$ sq. in. per sq. ft.; second-floor flues, 1 to $1\frac{1}{4}$ sq. in. per sq. ft.; third-floor flues and above, $\frac{3}{4}$ to 1 sq. in. per sq. ft. of surface.

The backs and sides of flues in exposed walls should be covered with non-conducting material.

Flue Velocities. The flue velocities will be somewhat lower than with steam heating, because of the lower temperature of the air. Reasonable allowance would be 250, 350, 400, and 450 feet per minute for the first, second, third, and fourth floors respectively.

Heating Water. The size of heater or steam coil necessary to heat water may be very readily determined on the heat-unit basis, if one knows the volume of water to be heated, the number of degrees its temperature is to be raised, and the time during which the heating must be done.

For example, what size of heater would be required to heat 300 gallons of water in 6 hours from 60° to 160°?

In one hour 50 gals. would be heated 100° F.; and since one gal. weighs $8\frac{1}{3}$ lbs., $50 \times 8\frac{1}{3} \times 100 = 41{,}667$ heat units would be required.

Small heaters may be counted on to transmit to the water about 7000 heat units per pound of coal burned. The rate of combustion should be assumed to be from 3 to 6 pounds per square foot of grate per hour, according to the amount of attendance it is convenient to give.

With a 4-pound rate, 28,000 heat units would be furnished per square foot of grate surface per hour for heating the water. Therefore the heat units per hour necessary to raise the temperature of the water—*viz.*, 41,667—divided by 28,000, gives the number of square feet of grate surface required, which is equal to about $1\frac{1}{2}$ corresponding to a diameter of $16\frac{1}{2}$ inches.

To determine the size of steam boiler and coil required to heat a large volume of water in a tank, proceed as follows: Take, for example, a 24,000-gallon tank, the water in which is to be heated from 45° to 75° in 10 hours. Now 24,000 gals. $\times$ $8\frac{1}{3}$ pounds $\times$ 30° rise in temperature = 6,000,000 heat units, or 600,000 heat units per hour.

Assuming 8000 heat units to be utilized per pound of coal burned at, say, a $7\frac{1}{2}$-pound rate, one square foot of grate will supply 60,000 heat units per hour; hence, 10 square feet of grate surface will be required.

There will, however, be a certain loss of heat from the tank by radiation, conduction, and evaporation; therefore, not less than, say, 12 square feet should be used in order to provide a reasonable margin.

As to the size of steam coil required, a square foot of pipe surface

surrounded by circulating water may be assumed to transmit to the water not far from 100 heat units per degree difference in temperature between the steam and the water in contact with the pipe.

Assume the steam temperature to be 230°, corresponding to a trifle more than 5 pounds gauge pressure. When the water in the tank is cold, the condensation of steam in the coil will be much more rapid than when the surrounding water becomes warmer. The average temperature of the water during the 10-hour period is 60°; but the water leaving the pipe and in contact with the upper half of its surface is at a considerably higher temperature than the main body of water in the tank; therefore, with natural circulation, it is well to make ample allowance for the effect of this skin of warm water surrounding the steam coils, and to assume that they will not give off more than $\frac{2}{3}$ as much heat as that corresponding to the difference in temperature between the steam and the water in the tank, based on 100 heat units per degree difference as stated above.

In other words, allow only $66\frac{2}{3}$—or, in round numbers, 70—heat units per hour per degree difference in temperature between the steam and the water in the tank.

If the difference in temperature is $230° - 70° = 160°$, on the basis stated, one square foot of coil would give off $70 \times 160 = 11{,}200$ heat units per square foot per hour; and since 600,000 heat units must be supplied to the water, a 53-square foot coil or slightly larger would be required, equal to about 122 ft. of $1\frac{1}{4}$-inch pipe.

SIMPLE COMBINATION GAS AND ELECTRIC FIXTURE IN A DINING ROOM

ELECTRIC WIRING

METHODS OF WIRING

The different methods of wiring which are now approved by the National Board of Fire Underwriters, may be classified under four general heads, as follows:

1. Wires Run Concealed in Conduits.
2. Wires Run in Moulding.
3. Concealed Knob and Tube Wiring.
4. Wires Run Exposed on Insulators.

WIRES RUN CONCEALED IN CONDUITS

Under this general head, will be included the following:

(*a*) Wires run in rigid conduits.
(*b*) Wires run in flexible metal conduits.
(*c*) Armored cable.

Wires Run in Rigid Conduit. The form of rigid metal conduit now used almost exclusively, consists of plain iron gaspipe the interior surface of which has been prepared by removing the scale and by removing the irregularities, and which is then coated with flexible enamel. The outside of the pipe is given a thin coat of enamel in some cases, and, in other cases, is galvanized. Fig. 1 shows one make of enameled (unlined) conduit.



Fig. 1. Rigid Enameled Conduit, Unlined.
Courtesy of American Conduit Mfg. Co., Pittsburg, Pa.

Another form of rigid conduit is that known as the *armored conduit*, which consists of iron pipe with an interior lining of paper impregnated with asphaltum or similar compound. This latter form of conduit is now rapidly going out of use, owing to the unlined pipe being cheaper and easier to install, and owing also to improved methods of protecting the iron pipe from corrosion, and to the introduction of additional braid on the conductors, which partly compensates for the

pipe being unlined. The introduction of improved devices—such as outlet insulators, for protecting the conductors from the sharp edges of the pipe, at outlets, cut-out cabinets, etc.—also decreases the necessity of the additional protection afforded by the interior paper lining.

Rigid conduits are made in gaspipe sizes, from one-half inch to three inches in diameter. The following table gives the various data relating to rigid, enameled (unlined) conduit:

TABLE I
Rigid, Enameled Conduit—Sizes, Dimensions, Etc.

Standard Pipe Size	Thickness	Nominal Weight per 100 Feet	Number of Threads per Inch of Screw	Actual Outside Diameter. Inches	Nominal Inside Diameter. Inches
½	.109	84	14	.84	.62
¾	.113	112	14	1.05	.82
1	.134	167	11½	1.31	1.04
1¼	.140	224	11½	1.66	1.38
1½	.145	268	11½	1.90	1.61
2	.154	361	11½	2.37	2.06
2½	.204	574	8	2.87	2.46
3	.217	754	8	3.50	3.06

Tables II, III, and IV give the various sizes of conductors that may be installed in these conduits. Caution must be exercised in

TABLE II
Single Wire in Conduit

Size Wire, B. & S. G.	Loricated Conduit, Unlined; D. B. Wire
No. 14-4	½ inch
" 2	¾ "
" 1	¾ "
" 0	¾ inch or 1 "
" 00	1 "
" 000	1 "
" 0000	1 "
250,000 C. M.	1¼ "
300,000 C. M.	1¼ "
350,000 C. M.	1¼ "
400,000 C. M.	1¼ " or 1½ "
450,000 C. M.	1½ "
500,000 C. M.	1½ "
600,000 C. M.	1½ " or 2 "
700,000 C. M.	2 "
800,000 C. M.	2 "
900,000 C. M.	2 "
1,000,000 C. M.	2 " or 2½ "
1,500,000 C. M.	2½ "
1,700,000 C. M.	3 "
2,000,000 C. M.	3 "

TABLE III
Two Wires in One Conduit

Size Wire, B. & S. G.	Loricated Conduit, Unlined; D. B. Wire
No. 14	½ inch.
" 12	½ inch or ¾ "
" 10	¾ "
" 8	1 "
" 6	1 "
" 5	1 " or 1¼ "
" 4	1¼ "
" 3	1¼ "
" 2	1¼ " or 1½ "
" 1	1½ "
" 0	1½ "
" 00	1½ " or 2 "
" 000	2 "
" 0000	2 "
250,000 C. M.	2 " or 2½ "
300,000 C. M.	2½ "
350,000 C. M.	2½ "
400,000 C. M.	2½ " or 3 "
450,000 C. M.	3 "
500,000 C. M.	3 "
600,000 C. M.	3 "
700,000 C. M.	3 "

TABLE IV
Three Wires in One Conduit

Size Wire, B. & S. G.		Loricated Tube, Unlined; D. B. Wire
Outside	Center	
No. 14	No. 12	¾ inch
" 12	" 10	¾ "
" 10	" 8	1 "
" 8	" 6	1 "
" 6	" 4	1¼ "
" 5	" 2	1¼ "
" 4	" 1	1¼ inch or 1½ "
" 3	" 0	1½ "
" 2	" 2/0	1½ " or 2 "
" 1	" 3/0	2 "
" 0	" 4/0	2 "
" 2/0	250 M.	2 " or 2½ "
" 3/0	300 M.	2½ "
" 4/0	400 M.	2½ "
250 M.	450 M.	2½ " or 3 "
250 M.	500 M.	3 "
300 M.	600 M.	3 "
350 M.	700 M.	3 "
400 M.	800 M.	3 "
450 M.	900 M.	3 "

using these tables, for the reason that the sizes of conductors which may be safely installed in any run of conduit depend, of course, upon the length of and the number of bends in the run. The tables are based on average conditions where the run does not exceed 90 to 100 feet, without more than three or four bends, in the case of the smaller sizes of wires for a given size of conduit; and where the run does not exceed 40 to 50 feet, with not more than one or two bends, in the case of the larger sizes of wires, for the same sizes of conduit.

Unlined conduit can be bent without injury to the conduit, if the conduit is properly made and if proper means are used in making the bends. Care should be exercised to avoid flattening the tube as a result of making the bend over a sharp curve or angle.

In installing iron conduits, the conduits should cross sleepers or beams at right angles, so as to reduce the amount of cutting of the beams or sleepers to a minimum.

Where a number of conduits originate at a center of distribution, they should be run at right angles for a distance of two or three feet from the cut-out box, in order to obtain a symmetrical and workmanlike arrangement of the conduits, and so as to have them enter the cabinet in a neat manner. While it is usual to use red or white lead at the joints of conduits in order to make them water-tight, this is frequently unnecessary in the case of enameled conduit, as there is often sufficient enamel on the thread to make a water-tight joint.

When iron conduits are installed in ash concrete, in Keene cement, or, in general, where they are subject in any way to corrosive action, they should be coated with asphaltum or other similar protective paint to prevent such action.

While the cost of circuit work run in iron conduits is usually greater than any other method of wiring, it is the most permanent and durable, and is strongly recommended where the first cost is not the sole consideration. This method of wiring should always be used in fireproof buildings, and also in the better class of frame buildings. It is also to be recommended for exposed work where the work is liable to disturbance or mechanical damage.

Wires Run in Flexible Metal Conduit. This form of conduit, shown in Fig. 2, is described by the manufacturers as a conduit composed of "concave and convex metal strips wound spirally upon each other in such a manner as to interlock several concave surfaces and

present their convex surfaces, both exterior and interior, thereby securing a smooth and comparatively frictionless surface inside and out."

The field for the use of this form of conduit is rapidly increasing. Owing to its flexibility, conduit of this type can be used in numerous cases where the rigid conduit could not possibly be employed. Its use is to be recommended above all the other forms of wiring, except that installed in rigid conduits. For new fireproof buildings, it is not so durable as the rigid conduit, because not so water-tight; and it is very difficult, if not impossible, to obtain as workmanlike a conduit system with the flexible as with the rigid type of conduit. For completed or old frame buildings, however, the use of the flexible conduit is superior to all other forms of wiring.



Fig. 2. Flexible Steel Conduit.
Courtesy of Sterling Electric Co., Troy, N. Y.

Table V gives the inside diameter of various sizes of flexible conduit, and the lengths of standard coils. inside diameter of this conduit is the same as that of the rigid conduit; and the table given for the maximum sizes of conductors which may be installed in the various sizes of conduits, may be used also for flexible steel conduits, except that a little more margin should be allowed for flexible steel conduits than for the rigid conduits, as the stiffness of the latter makes it possible to pull in slightly larger sized conductors.

TABLE V

Greenfield Flexible Steel Conduit

Inside Diameter	Approximate Feet in Coil
$\frac{6}{8}$ inch	200
$\frac{3}{8}$ "	200
$\frac{1}{2}$ "	100
$\frac{3}{4}$ "	50
1 "	50
$1\frac{1}{4}$ inches	50
$1\frac{1}{2}$ "	50
2 "	Random Lengths
$2\frac{1}{2}$ "	" "
3 "	" "

This conduit should, of course, be first installed without the conductors, in the same manner as the rigid conduit. Owing to the flexibility of this conduit, however, it is absolutely essential to fasten it securely at all elbows, bends, or offsets; for, if this is not done, considerable difficulty will be experienced in drawing the conductors in the conduit.

Fig. 3. Use of Elbow Clamp for Fastening Flexible Conduit in Place.

The rules governing the installation of this conduit are the same as those covering rigid conduits. Double-braided conductors are required, and the conduit should be grounded as required by the *Code Rules*. As already stated, the conduit should be securely fastened (in not less than three places) at all elbows; or else the special elbow clamp made for this purpose, shown in Fig. 3, should be used.

In order to cut flexible steel conduit properly, a fine hack saw should be employed. Outlet-boxes are required at all outlets, as well as bushing and wires to rigid conduit. Fig. 4 shows a coil of flexible steel conduit. Figs. 5, 6, and 7 show, respectively, an outlet box and cover, outlet plate, and bushing used for this conduit.

Fig. 4. A 100-Foot Coil of Flexible Steel Conduit. *Courtesy of Sprague Electric Co., New York, N. Y.*

Armored Cable. There are many cases where it is impossible to install a conduit system. In such cases, probably the next best results may be obtained by the use of *steel armored cable*. The rules governing the installation of armored cable are given in the *National Electric Code*, under Section 24-A, and Section 48; also in 24–S. This cable is shown in Fig. 8.

Steel armored cable is made by winding formed steel strips over the insulated conductors. The steel strips are similar to those used

for the steel conduit. Care is taken in forming the cable, to avoid crushing or abraiding the insulation on the conductors as the steel



Fig. 5. Outlet Box for Flexible Steel Conduit.

strips are fed and formed over the same. In the process of manufacture, the spools of steel ribbon are of irregular length, and when a



Fig. 6. Outlet Plate for Flexible Steel Conduit.



Fig. 7. Outlet Bushing.
Courtesy of Sprague Electric Co., New York, N. Y.

spool is empty, the machine is stopped, and the ribbon is started on the next spool, the process being continued. There is no reason why

Fig. 8. Flexible Armored Cable. Twin Conductors.
Courtesy of Sprague Electric Co., New York, N. Y.

the conduit cables could not be made of any length; but their actual lengths as made are determined by convenience in handling. Armored

cable is made in *single conductors* from No. 1 to No. 10 B. & S. G.; in *twin conductors*, from No. 6 to No. 14 B. & S. G.; and *three-conductor* cable, from No. 10 to No. 14 B. & S. G. Table VI gives various data relating to armored conductors:

TABLE VI

Armored Conductors—Types, Dimensions, Etc.

Size B. & S Gauge	Type and Number of Conductors	Outside Diameter (Inches)
No. 14	BX twin conductor	.63
" 12	" " "	.685
" 10	" " "	.725
" 8	" " "	.875
" 6	" " "	1.3125
" 14	BM twin conductor (for marine work—ship wiring)	.725
" 12	" " "	.725
" 10	" " "	.73
" 14	BX3 three conductor	.71
" 12	" " "	.725
" 10	" " "	.73
" 14	BXL twin conductor, leaded	.725
" 12	" " " "	.725
" 10	" " " "	.87
" 14	BXL3 three conductor, leaded	.90
" 12	" " " "	.90
" 10	" " " "	.94
" 10	Type D single conductor, stranded	.550
" 8	" " " " "	.550
" 6	" " " " "	.575
" 4	" " " " "	.700
" 2	" " " " "	.900
" 1	" " " " "	.965
" 10	Type DL single conductor, stranded, leaded	.625
" 8	" " " " " "	.710
" 6	" " " " " "	.700
" 4	" " " " " "	.760
" 2	" " " " " "	.920
" 1	" " " " " "	.910
	Steel Armored Flexible Cord	
" 18	Type E twin conductor	.40
" 16	" " " "	.40
" 14	" " " "	.47
" 18	Type EM twin conductor, re-inforced	.575
" 16	" " " " "	.585
" 14	" " " " "	.595

In Table VI, Tvpes D (single), BX (twin), and BX3 (3 conduc-

ELECTRICAL KITCHEN IN EDISON BUILDING, CHICAGO

tors) are armored cable adapted for ordinary indoor work. Type BM (twin conductors) is adapted for marine wiring. Types DL (single), BXL (twin), and BXL 3 (3 conductors) have the conductors lead-encased, with the steel armor outside, and are especially adapted for damp places, such as breweries, stables, and similar places.

Type E is used for flexible-cord pendants, and is suitable for factories, mills, show windows, and other similar places. Type EM is the same as Type E; but the flexible cord is reinforced, and is suitable for marine work, for use in damp places, and in all cases where it will be subject to very rough handling.

While this form of wiring has not the advantage of the conduit system—namely, that the wires can be withdrawn and new wires inserted without disturbing the building in any way whatever—yet it has many of the advantages of the flexible steel conduit, and it has some additional advantages of its own. For example, in a building already erected, this cable can be fished between the floors and in the partition walls, where it would be impossible to install either rigid conduit or flexible steel conduit without disturbing the floors or walls to an extent that would be objectionable.

Armored conductors should be continuous from outlet to outlet, without being spliced and installed on the loop system. Outlet boxes should be installed at all outlets, although, where this is impossible, outlet plates may be used under certain conditions. Clamps should be provided at all outlets, switch-boxes, junction-boxes, etc., to hold the cable in place, and also to serve as a means of grounding the steel sheathing.

Armored cable is less expensive than the rigid conduit or the flexible steel conduit, but more expensive than cleat wiring or knob and tube wiring, and is strongly recommended in preference to the latter.

WIRES RUN IN MOULDING

Moulding is very extensively used for electric circuit work, in extending circuits in buildings which have already been wired, and also in wiring buildings which were not provided with electric circuit work at the time of their erection. The reason for the popularity of moulding is that it furnishes a convenient and fairly good-looking runway for the wires, and protects them from mechanical injury.

It seems almost unwise to place conductors carrying electric current, in wood casing; but this method is still permitted by the *National Electric Code*, although it is not allowed in damp places or in places where there is liability to dampness, such as on brick walls, in cellars, etc.



Fig. 9. Two-Wire Wood Moulding.

The dangers from the use of moulding are that if the wood becomes soaked with water, there will be a liability to leakage of current between the conductors run in the grooves of the moulding, and to fire being thereby started, which may not be immediately discovered. Furthermore, if the conductors are overloaded, and consequently overheated, the wood is likely to become charred and finally ignited. Moreover, the moulding itself is always a temptation as affording a good "round strip" in which to drive nails, hooks, etc. However, the convenience and popularity of moulding cannot be denied; and until some better substitute is found, or until its use is forbidden by the *Rules*, it will continue to be used to a very great extent for running circuits outside of the walls and on the ceilings of existing buildings. Figs. 9, 10, 11, and 12 show two- and three-wire moulding respectively; and Table VII gives complete data as to sizes of the moulding required for various sizes of conductors.

While the *Rules* recommend the use of hardwood moulding, as a matter of fact probably 90 per cent of the moulding used is of whitewood or other similar cheap, soft wood. Georgia pine or oak ordinarily



Fig. 10. Two-Wire Wood Moulding.

costs about twice as much as the soft wood. In designing moulding work, if appearance is of importance, the moulding circuits should be laid out so as to afford a symmetrical and complete design. For

example, if an outlet is to be located in the center of the ceiling, the moulding should be continued from wall to wall, the portion beyond the outlet, of course, having no conductors inside of the moulding. If four outlets are to be placed on the ceiling, the rectangle of moulding should be completed on the fourth side, although, of course, no con-



Fig. 11. Three-Wire Wood Moulding.

ductors need be placed in this portion of the moulding. Doing this increases the cost but little and adds greatly to the appearance.

Moulding is frequently used in combination with other methods of wiring, including armored cable, flexible steel tubing, and fibrous tubing. In many instances, it is possible to fish tubing between beams or studs running in a certain direction; but when the conductors are to run in another direction or at right angles to the beams or studs, exposed work is necessary. In such cases, a junction-box or outlet-box must be placed at the point of connection between the moulding and the armored cable or steel tubing.

Where circuits are run in moulding, and pass through the floor, additional protection must be provided, as required by the *Code Rules*,



Fig. 12. Three-Wire Wood Moulding.

to protect the moulding. As a rule, it is better to use conduit for all portions of moulding within six feet of the floor, so as to avoid the possibility of injury to the circuits. Where a combination of iron conduit or flexible steel tubing is used with moulding, it is well to use double-braided conductors throughout, because, although only single-

TABLE VII

Sizes of Mouldings Required for Various Sizes of Conductors

FIG. No.	TYPE OF MOULDING	NUMBER OF WIRES	MAXIMUM SIZE OF WIRE B AND S. GAUGE		DIMENSIONS IN INCHES									
			SOLID	STRANDED	A	Aa	Ab	Ac	B	Ba	Bb	Bc	C	Ca
9	A-2	2	12	14	1 1/2	1/2	1/4	1/4	27/32	5/8	7/32	1/4	1 1/8	3/16
9	A-4	2	8	10	1 11/16	1/2	5/16	9/32	29/32	11/16	7/32	5/16	1 5/16	3/16
9	A-6	2	4	5	2	1/2	7/16	5/16	1 1/16	13/16	1/4	7/16	1 9/16	7/32
9	A-8	2	1	2	2 3/8	1/2	9/16	3/8	1 3/16	15/16	1/4	9/16	1 13/16	9/32
9	A-9	2	—	3/0	3	5/8	3/4	7/16	1 13/32	1 1/8	9/32	3/4	2 7/16	9/32
10	A-10	2	—	250,000 C.M.	3 15/16	11/16	7/8	3/4	1 11/16	1 3/8	5/16	7/8	—	—
10	A-11	2	—	400,000 C.M.	4 7/8	15/16	1	31/32	2 3/16	1 7/8	5/16	1	—	—
11	B-2	3	12	14	2 3/16	7/16	1/4	9/32	27/32	5/8	7/32	1/4	1 13/16	3/16
11	B-4	3	8	10	2 1/2	15/32	5/16	5/16	29/32	11/16	7/32	5/16	2 1/8	3/16
11	B-6	3	4	5	2 7/8	13/32	7/16	3/8	1 1/16	13/16	1/4	7/16	2 3/8	1/4
11	B-8	3	1	2	3 5/8	19/32	9/16	3/8	1 3/16	15/16	1/4	9/16	3 1/16	9/32
11	B-9	3	—	3/0	4 5/16	9/16	3/4	15/32	1 13/32	1 1/8	9/32	3/4	3 3/4	9/32
12	B-10	3	—	250,000 C.M.	5 1/2	23/32	7/8	23/32	1 11/16	1 3/8	5/16	7/8	—	—
12	B-11	3	—	400,000 C.M.	6 3/4	15/16	1	15/16	2 3/16	1 7/8	5/16	1	—	—

braided conductors are required with moulding, double-braided conductors are required with unlined conduit, and if double-braided conductors were not used throughout, it would be necessary to make a joint at the outlet-box where the moulding stopped and the conduit work commenced. Where the conductors pass through floors, in moulding work, and where iron conduit is used, the inspection authorities, in order to protect the wire, usually require that a fibrous tubing be used as additional protection for the conductors inside of the iron pipe, although, if double-braided wire is used, this will not usually be required. Fig. 13 shows a fuseless cord rosette for use with moulding work. Fig. 14 shows a device for making a *tap* in moulding wiring.

Moulding work, under ordinary conditions, costs about one-half as much as circuit run in rigid conduit, and about 75 per cent, under

ordinary conditions, of the cost of armored cable. Where the latter method of wiring or the conduit system can be employed, one or the other of these two methods should be used in preference to moulding,



Fig. 13. Fuseless Cord Rosette.
Courtesy of Crouse-Hinds Co., Syracuse, N. Y.



Fig. 14. Device for Making "Tap" in Moulding.
Courtesy of H. T. Paiste Co., Philadelphia, Pa.

as the work is not only more substantial, but also safer. Various forms of metal moulding have been introduced, but up to the present time have not met with the success which they deserve.

CONCEALED KNOB AND TUBE WIRING

This method of wiring is still allowed by the *National Electric Code*, although many vigorous attempts have been made to have it abolished. Each of these attempts has met with the strongest opposition from contractors and central stations, particularly in small towns and villages, the argument for this method being, that it is the cheapest method of wiring, and that if it were forbidden, many places which are wired according to this method would not be wired at all, and the use of electricity would therefore be much restricted, if not entirely done away with, in such communities. This argument, however, is only a temporary makeshift obstruction in the way of inevitable progress, and in a few years, undoubtedly, the concealed knob and tube method will be forbidden by the *National Electric Code*.

The cost of wiring according to this method is about one-third of the cost of circuits run in rigid conduit, and about one-half of the cost of circuits run in armored cable. The latter method of wiring

is rapidly replacing knob and tube wiring, and justly so, wherever the additional price for the latter method of wiring can be obtained. As the name indicates, this method of wiring employs *porcelain knobs*



Fig. 15. Knob and Tube Wiring.

and tubes, the circuit work being run *concealed* between the floor beams and studs of a frame building. The knobs are used when the circuits run parallel to the floor beams; and the porcelain tubes are used when the circuits are run at right angles to the floor beams.

Fig. 15 shows an example of knob and tube wiring. In concealed knob and tube wiring, the wires must be separated at least ten inches from one another, and at least one inch from the surface wired over, that is, from the beams, flooring, etc., to which the insulator is fastened. Fig. 16 shows a good type of porcelain knob for this class of wiring. For knob and tube wiring, it will be noted that, owing to the fact that the wiring is concealed, the conductors must be kept further apart than in the case of exposed or open wiring on insulators, where, except in damp places, the wires may be run on cleats or on insulators only one-half inch from the surface wired over.



Fig. 16. Porcelain Knob.

Fibrous Tubing. Fibrous tubing is frequently used with knob and tube wiring, and the regulations governing its use are given in Rule 24, Section S, of the *National Electric Code.* This tubing, as stated in this *Rule,* may be used where it is impossible and impracticable to employ knobs and tubes, provided the difference in potential between the wires is not over 300 volts, and if the wires are not sub-



Fig. 17. Flexible Tubing, "Flexduct" Type.
Courtesy of National Metal Molding Co., Pittsburg, Pa.

ject to moisture. The cost of wiring in flexible fibrous tubing is approximately about the same as the cost of knob and tube wiring. Duplex conductors, or two wires together are not allowed in fibrous tubing.

Fibrous tubing is required at all outlets where conduit or armored cable is not used (as in knob and tube wiring); and, as required by the *Rules,* it must extend back from the last porcelain support to one inch beyond the outlet. Fig. 17 shows one make of fibrous tubing.

Table VIII gives the maximum sizes of conductors (double-braided) which may be installed in fibrous conduit.

TABLE VIII

Sizes of Conductors in Fibrous Conduit

Outside Diameter	Inside Diameter	One Wire in Tube
$\frac{17}{32}$ inch	$\frac{1}{4}$ inch	No. 12
$\frac{21}{32}$ "	$\frac{3}{8}$ "	" 8
$\frac{25}{32}$ "	$\frac{1}{2}$ "	" 6
$\frac{15}{16}$ "	$\frac{5}{8}$ "	" 1
$1\frac{3}{32}$ "	$\frac{3}{4}$ "	" 2/0
$1\frac{5}{16}$ "	1 "	250,000 C. M.
$1\frac{9}{16}$ "	$1\frac{1}{4}$ "	400,000 C. M.
$1\frac{13}{16}$ "	$1\frac{1}{2}$ "	750,000 C. M.
$2\frac{1}{16}$ "	$1\frac{3}{4}$ "	1,000,000 C. M.
$2\frac{3}{16}$ "	2 "	1,500,000 C. M.
$2\frac{5}{8}$ "	$2\frac{1}{2}$ "	2,000,000 C. M.

WIRES RUN EXPOSED ON INSULATORS

This method of wiring has the advantages of cheapness, durability, and accessibility.

Cheapness. The relative cost of this method of wiring as compared with that of the concealed conduit system, is about fifty per cent of the latter if rubber-covered conductors are used, and about forty per cent of the latter if weatherproof slow-burning conductors are used. As the *Rules* of the Fire Underwriters allow the use of weatherproof slow-burning conductors in dry places, considerable saving may be effected by this method of wiring, provided there is no objection to it



Fig. 18. Large Feeders Run Exposed on Insulators.

from the standpoint of appearance, and also provided that it is not liable to mechanical injury or disarrangement.

Durability. It is a well-known fact that rubber insulation has a relatively short life. Inasmuch as in this method of wiring, the insulation does not depend upon the insulation of the conductors, but on the insulators themselves, which are of glass or porcelain, this system is much more desirable than any of the other methods. Of course, if the conductors are mechanically injured, or the insulators broken, the insulation of the system is reduced; but there is no gradual deterioration as there is in the case of other methods of wiring, where

rubber is depended upon for insulation. This is especially true in hot places, particularly where the temperature is 120° F. or above. For such cases, the weatherproof slow-burning conductors on porcelain or glass insulators are especially recommended.

Accessibility. The conductors being run exposed, they may be readily repaired or removed, or connections may be made to the same.



Fig. 19. Two-Wire Cleat.

This method of wiring is especially recommended for mills, factories, and for large or long feeder conductors. Fig. 18 shows examples of exposed large feeder conductors, installed in the New York Life Insurance Building, New York City. For small conductors, up to say No. 6 B. & S. Gauge each, porcelain cleats may be used to support one, two, or three conductors, provided the distance between the conductors is at least 2½ inches in a two-wire system, and 2½ inches between the two outside conductors in a three-wire system where the potential between the outside conductors is not over 300 volts. The cleat must hold the wire at least one-half inch from the surface to which the cleat is fastened; and in damp places the wire must be held at least one inch from the surface wired over. For larger conductors,



Fig. 20. One-Wire Cleat.



Fig. 21. Porcelain Insulator for Large Conductors.

from No. 6 to No. 4/0 B. & S. Gauge, it is usual to use single porcelain cleats or knobs. Figs. 19 and 20 show a good form of two-wire



Fig. 22. Iron Rack and Insulators for Large Conductors.
Courtesy of General Electric Co., Schenectady, N. Y.

cleat and single-wire cleat, respectively.

For large feeder or main conductors from No. 4/0 B. & S. Gauge upward, a more substantial form of porcelain insulator should be used, such as shown in Fig. 21. These insulators are held in iron racks or angle-iron frames, of which two forms are shown in Figs. 22 and 23. The latter form of rack is particularly desirable for heavy conductors and where a number of conductors are run together. In this form of rack, any length of conductor can be removed without disturbing the other conductors.

As a rule, the porcelain insulators should be placed not more than 4½ feet apart; and if the wires are liable to be disturbed, the distance between supports should be shortened, particularly for small conductors. If the beams are so far apart that supports cannot be obtained every 4½ feet, it is necessary to provide a running board as shown in Fig. 24, to which the porcelain cleats and knobs can be fastened. Figs. 25 and 26 show two methods of supporting small conductors. For conductors of No. 8 B. & S.



Fig. 23. Elevation and Plan of Insulators Held in Angle-Iron Frames.

Gauge, or over, it is not necessary to break around the beams, provided they are not liable to be disturbed; but the supports may be placed on each beam.



Fig. 24. Insulators Mounted on Running-Board across Wide-Spaced Beams.

Where the distance between the supports, however, is greater than $4\frac{1}{2}$ feet, it is usually necessary to provide intermediate supports, as shown in Fig. 27, or else to provide a running-board. Another method which may be used, where beams are further than $4\frac{1}{2}$ feet apart, is to



Fig. 25. Method of Supporting Small Conductors.



Fig. 27. Intermediate Support for Conductor between Wide-Spaced Beams.

run a main along the wall at right angles to the beams, and to have the individual circuits run between and parallel to the beams.



Fig. 26. Method of Supporting a Small Conductor.



Fig. 28. Conductors Protected by Wooden Guard Strips on Low Ceiling.

In low-ceiling rooms, where the conductors are liable to injury, it is usually required that a wooden guard strip be placed on each side of the conductors, as shown in Fig. 28.

Where the conductors pass through partitions or walls, they must

be protected by porcelain tubes, or, if the conductors be of rubber, by means of fibrous tubing placed inside of iron conduits.

All conductors on the walls for a height of not less than six feet from the ground, either should be boxed in, or, if they be rubber-covered, should (preferably) be run in iron conduits; and in conductors having single braid only, additional protection should be provided by means of flexible tubing placed inside of the iron conduit.

Where conductors cross each other, or where they cross iron pipes, they should be protected by means of porcelain tubes fastened with tape or in some other substantial manner that will prevent the tubes from slipping out of place.

TWO-WIRE AND THREE-WIRE SYSTEMS

As both the two-wire and the three-wire system are extensively used in electric wiring, it will be well to give some consideration to the advantages and disadvantages of each system, and to explain them somewhat in detail.

Relative Advantages. The choice of either a two-wire or a three-wire system depends largely upon the source of supply. If, for example, the source of supply will always probably be a 120-volt, two-wire system, there would be no object in installing a three-wire system for the wiring. If, on the other hand, the source of supply is a 120-240-volt system, the wiring should, of course, be made three-wire. Furthermore, if at the outset the supply were two-wire, but with a possibility of a three-wire system being provided later, it would be well to adapt the electric wiring for the three-wire system, making the neutral conductor twice as large as either of the outside conductors, and combining the two outside conductors to make a single conductor until such time as the three-wire service is installed. Of course, there would be no saving of copper in this last-mentioned three-wire system, and in fact it would be slightly more expensive than a two-wire system, as will be shortly explained.

The object of the three-wire system is to reduce the amount of copper—and consequently the cost of wiring—necessary to transmit a given amount of electric power. As a rule, the proposition is usually one of lighting and not of power, for the reason that by means of the three-wire system we are able to increase the potential at which the current is transmitted, and at the same time to take advantage of the

greater efficiency of the lower voltage lamp. If current for power (motors, etc.) only were to be transmitted, it would be a simple matter to wind the motors, etc., for a higher voltage, and thereby reduce the weight of copper. If, however, we increase the voltage of lamps, we find that they are not so efficient, nor is their life so long. With the standard carbon lamp, it has been found that the 240-volt lamp, with the same life, requires about 10 to 12 per cent more current than the corresponding 120-volt lamp. Furthermore, in the case of the more efficient lamps recently introduced (such as the Tantalum lamp, Tungsten lamp, etc.), it has been found impracticable, if not impossible, to make them for pressures above 125 volts. For this reason the three-wire system is employed, for by this method we can use 240 volts across the outside conductors, and by the use of a neutral conductor obtain 120 volts between the neutral and the outside conductor, and thereby be enabled to use 120-volt lamps. Furthermore, if a 240-volt lamp should ever be placed on the market that was as economical as the lower voltage lamp, the result would be that the 240-480-volt system would be introduced, and 240-volt lamps used. As a matter of fact, this has been tried in several cities—and particularly in Providence, Rhode Island. As a rule, however, the 120-volt lamp has been found so much more satisfactory as regards life, efficiency, etc., that it is nearly always employed.



Fig. 29. Three-Wire System, with Neutral Conductor between the Two Outside Conductors.



Fig. 30. Lamps Arranged in Pairs in Series, Dispensing with Necessity for Third or Neutral Conductor.

The two-wire system is so extremely simple that no explanation whatever is required concerning it.

The three-wire system, however, is somewhat confusing, and will now be considered.

Details of Three-Wire System. The three-wire system may be considered as a two-wire system with a third or neutral conductor placed between the two outside conductors, as shown in Fig. 29. This neutral conductor would not be required if we could always have the lamps arranged in pairs, as shown in Fig. 30. In this case, the two lamps would burn in series, and we could transmit the current at double the usual voltage, and thereby supply twice the number of lamps with one-quarter the weight of copper, allowing the same loss in pressure in the lamps. The reason for this is, that, having the lamps arranged in series of pairs, we reduce the current to one-half, and, as the pressure at which the current is transmitted is doubled, we can again reduce the copper one-half without increasing the loss in lamps. We therefore see that we have a double saving, as the current is reduced one-half, which reduces the weight of copper one-half, and we can again reduce the copper one-half by doubling the loss in volts without increasing the percentage loss. For example, if in one case we had a straight two-wire system transmitting current to 100 lamps at a potential of 100 volts, and this system were replaced by one in which the lamps were placed in series of pairs, as shown in Fig. 30, and the potential increased to 200 volts—100 lamps still being used—we should find, in the latter case, that we were carrying current really for only 50 lamps, as we would require only the same amount of current for two lamps now that we required for one lamp before. Furthermore, as the potential would now be 200 instead of 100 volts, we could allow twice as much loss as in the first case, because the loss would now be figured as a percentage of 200 volts instead of a percentage of 100 volts. From this, it will readily be seen that in the second case mentioned, we would require only one-quarter the weight of copper that would be required in the first case.

It will readily be seen, however, that a system such as that outlined in the second scheme having two lamps, would be impracticable for ordinary purposes, for the reason that it would always require the lamps to be burned in pairs. Now, it is for this very reason that the third or neutral conductor is required; and, if this conductor be added, it will no longer be necessary to burn the lamps in pairs. This, then, is the object of the three-wire system—to enable us to reduce the amount of copper required for transmitting current, without increasing the electric pressure employed for the lamps.

With regard to the size of the neutral conductor, one important point must be borne in mind; and that is, that the *Rules of the National Electric Code* require the neutral conductor in all interior wiring to be made at least as large as either of the two outside conductors. The reasons for this from a fire standpoint are obvious, because, if for any reason either of the outside conductors became disconnected, the neutral wire might be required to carry the same current as the outside conductors, and therefore it should be of the same capacity. Of course, the chances of such an event happening are slight; but, as the fire hazard is all-important, this rule must be complied with for interior wiring or in all cases where there would be a probability of fire. For outside or underground work, however, where the fire hazard would be relatively unimportant, the neutral conductor might be reduced in size; and, as a matter of fact, it is made smaller than the outside conductors.

The three-wire system is sometimes installed where it is desired to use the system as a two-wire, 125-volt system, or to have it arranged so that it may be used at any time also as a three-wire, 125-250-volt system. Of course, in order to do this, it is necessary to make the neutral conductor equal to the combined capacity of the outside conductors, the latter being then connected together to form one conductor, the neutral being the return conductor. This system is not recommended except in such instances, for example, as where an isolated plant of 125 volts is installed, and where there is a possibility of changing over at some future time to the three-wire, 125-250-volt system. In such a case as this, however, it would be better, where possible, to design the isolated plant for a three-wire, 125-250-volt system originally, and then to make the neutral conductor the same size as each of the two outside conductors.

The weight of copper required in a three-wire system where the neutral conductor is the same size as either of the two outside conductors, is $\frac{3}{8}$ of that required for a corresponding two-wire system using the same voltage of lamps.* It is obvious that this is true, because,

*Note.—If, in the two-wire system, we represent the weight of each of the two conductors by $\frac{1}{1}$, the weight of each of the outside conductors in a three-wire system would be represented by $\frac{1}{2}$; and if we had three conductors of the same size, we would have $\frac{1}{2} + \frac{1}{2} + \frac{1}{2} = \frac{3}{2}$ of the weight of copper required in a three-wire system, which would be required in a corresponding two-wire system having the same percentage of loss and using the same voltage of lamps.

If the neutral conductor were made $\frac{1}{2}$ of the size of each of the outside conductors, as is sometimes done in underground work, the total weight of copper required would be $\frac{1}{2} + \frac{1}{2} + \frac{1}{4} = \frac{5}{8}$ of that required in the corresponding two-wire system.

as the discussion proved concerning the arrangement shown in Fig. 30, where the lamps were placed in series of pairs, we found that the weight of copper for the two conductors was one-quarter the weight of the regular two-wire system. It is then of course true, that, if we had another conductor of the same size as each of the outside conductors, we increase theweight of copper one-half, or one-quarter plus one-half of one-quarter—that is, three-eighths.

In the three-wire system frequently used in isolated plants in which the two outside conductors are joined together and the neutral conductor made equal to their combined capacity, there is no saving of copper, for the reason that the same voltage of transmission is used, and, consequently, we have neither reduced the current nor increased the potential. Furthermore, though the weight of copper is the same, it is now divided into three conductors, instead of two, and naturally it costs relatively more to insulate and manufacture three conductors than to insulate and manufacture two conductors having the same total weight of copper. As a matter of fact, the three-wire system, having the neutral conductor equal to the combined capacity of the two outside ones, the latter being joined together, is about 8 to 10 per cent more expensive than the corresponding straight two-wire system.

In interior wiring, as a rule, where the three-wire system is used for the mains and feeders, the two-wire system is nearly always employed for the branch circuits. Of course, the two-wire branch circuits are then balanced on each side of the three-wire system, so as to obtain as far as possible at all times an equal balance on the two sides of the system. This is done so as to have the neutral conductor carry as little current as possible. From what has already been said, it is obvious that in case there is a perfect balance, the lamps are virtually in series of pairs, and the neutral conductor does not carry any current. Where there is an unbalanced condition, the neutral conductor carries the difference between the current on one side and the current on the other side of the system. For example, if we had five lamps on one side of the system and ten lamps on the other, the neutral conductor would carry the current corresponding to five lamps.

In calculating the three-wire system, the neutral conductor is disregarded, the outer wires being treated as a two-wire circuit, and the calculation is for one-half the total number of lamps, the per-

centage of loss being based on the potential across the two outside conductors.

The three-wire system is very generally employed in alternating-current secondary wiring, as nearly all transformers are built with three-wire connections.

While unbalancing will not affect the total loss in the outside conductors, yet it does affect the loss in the lamps, for the reason that the system is usually calculated on the basis of a perfect balance, and the loss is divided equally between the two lamps (the latter being considered in series of pairs). If, however, there is unbalancing to a great degree, the loss in lamps will be increased; and if the entire load is thrown over on one side, the loss in the lamps will be doubled on the remaining side, because the total loss in voltage will now occur in these lamps, whereas, in the case of perfect balance, it would be equally divided between the two groups of lamps.

CALCULATION OF SIZES OF CONDUCTORS

The formula for calculating the sizes of conductors for direct currents, where the length, load, and loss in volts are given, is as follows:

The size of conductor (in circular mils) is equal to the current *multiplied by* the distance (one way), *multiplied by* 21.6, *divided by* the loss in volts; or,

$$CM = \frac{C \times D \times 21.6}{V} \quad \ldots\ldots\ldots\ldots\ldots\ldots (1)$$

in which C = Current, in amperes;
D = Distance or length of the circuit (one way, in feet);
V = Loss in volts between the beginning and end of the circuit.

The constant (21.6) of this formula is derived from the resistance of a mil foot of wire of 98 per cent conductivity at 25° Centigrade or 77° Fahrenheit. The resistance of a conductor of one mil diameter and one foot long, is 10.8 at the temperature and conductivity named. We multiply this figure (10.8) by 2, as the length of a circuit is usually given as the distance one way, and in order to obtain the resistance of both conductors in a two-wire circuit, we must multiply by 2. The formula as above given, therefore, is for a two-wire circuit; and in calculating the size of conductors in a three-wire system, the calculation should be made on a two-wire basis, as explained hereinafter.

Formula 1 can be transformed so as to obtain the loss in a given circuit, or the current which may be carried a given distance with a stated loss, or to obtain the distance when the other factors are given, in the following manner:

Formula for Calculating Loss in Circuit when Size, Current, and Distance are Given

$$V = \frac{C \times D \times 21.6}{CM} \quad \ldots\ldots\ldots\ldots\ldots\ldots (2)$$

Formula for Calculating Current which may be Carried by a Given Circuit of Specified Length, and with a Specified Loss

$$C = \frac{CM \times V}{D \times 21.6} \quad \ldots\ldots\ldots\ldots\ldots\ldots (3)$$

Formula for Calculating Length of Circuit when Size, Loss, and Current to be Carried are Given

$$D = \frac{CM \times V}{C \times 21.6} \quad \ldots\ldots\ldots\ldots\ldots\ldots (4)$$

Formulæ are frequently given for calculating sizes of conductors, etc., where the load, instead of being given in amperes, is stated in lamps or in horse-power. It is usually advisable, however, to reduce the load to amperes, as the efficiency of lamps and motors is a variable quantity, and the current varies correspondingly.

It is sometimes convenient, however, to make the calculation in terms of watts. It will readily be seen that we can obtain a formula expressed in watts from Formula 1. To do this, it is advisable to express the loss in volts in percentage, instead of actual volts lost. It must be remembered that, in the above formulæ, V represents the volts lost in the circuit, or, in other words, the difference in potential between the beginning and the end of the circuit, and is not the applied E. M. F. The loss in percentage, in any circuit, is equal to the actual loss expressed in volts, *divided by* the line voltage, *multiplied by* 100; or,

$$P = \frac{V}{E} \times 100.$$

From this equation, we have:

$$V = \frac{P\,E}{100}.$$

If, for example, the calculation is to be made on a loss of 5 per cent, with an applied voltage of 250, using this last equation, we would have:

$$V = \frac{5 \times 250}{100} = 12.5 \text{ volts.}$$

Substituting the equation $V = \frac{P\,E}{100}$ in Formula 1, we have:

$$CM = \frac{C \times D \times 21.6}{\frac{PE}{100}}$$

$$= \frac{C \times D \times 21.6 \times 100}{PE}$$

$$= \frac{C \times D \times 2{,}160}{PE}.$$

This equation, it should be remembered, is expressed in terms of applied voltage. Now, since the power in watts is equal to the applied voltage *multiplied by* the current ($W = EC$), it follows that

$$C = \frac{W}{E}.$$

By substituting this value of C in the equation given above $\left(CM = \frac{C \times D \times 2{,}160}{PE}\right)$, the formula is expressed in terms of watts instead of current, thus:

$$CM = \frac{W \times D \times 2{,}160}{EPE}, \quad \text{.....(5)}$$

in which W = Power in watts transmitted;
D = Length of the circuit (one way)—that is, the length of one conductor;
P = Figure representing the percentage loss;
E*= Applied voltage.

All the above formulæ are for calculations of two-wire circuits. In making calculations for three-wire circuits, it is usual to make the calculation on the basis of the two outside conductors; and in three wire calculations, the above formulæ can be used with a slight modification, as will be shown.

In a three-wire circuit, it is usually assumed in making the calculation, that the load is equally balanced on the two sides of the neutral conductor; and, as the potential across the outside conductors is double that of the corresponding potential across a two-wire circuit, it is evident that for the same size of conductor the total loss in volts could be doubled without increasing the percentage of loss in lamps. Furthermore, as the load on one side of the neutral conductor, when the system is balanced, is virtually in series with the load on the third side, the current in amperes is usually one-half the sum of the current required by all the lamps. If C be still taken as the total

*Note. Remember that V in Formulæ 1 to 4 represents the volts lost, but that E in Formula 5 represents the applied voltage.

current in amperes (that is, the sum of the current required by all of the lamps) in Formula 1, we shall have to divide this current by 2, to use the formula for calculating the two outside conductors for a three-wire system. Furthermore, we shall have to multiply the voltage lost in the lamps by 2, to obtain the voltage lost in the two outside conductors, for the reason that the potential of the outside conductors is double the potential required by the lamps themselves. In other words, Formula 1 will become:

$$CM = \frac{C \times D \times 21.6}{2 \times V \times 2}$$

$$= \frac{C \times D \times 21.6}{4\,V}, \quad \ldots\ldots\ldots\ldots\ldots\ldots (6)$$

in which C = Sum of current required by all of the lamps on both sides of the neutral conductor;

D = Length of circuit—that is, of any one of the three conductors;

V = Loss allowed in the lamps, i. e., one-half the total loss in the two outside conductors.

In the same manner, all of the other formulæ may be adapted for making calculations for three-wire systems. Of course the calculation of a three-wire system could be made as if it were a two-wire system, by taking one-half the total number of lamps supplied, at one-half the voltage between the outside conductors.

It is understood, of course, that the size of the conductor in Formula 6 is the size of each of the two outside ones; but, inasmuch as the *Rules of the National Electric Code* require that for interior wiring the neutral conductor shall be at least equal in size to the outside conductors, it is not necessary to calculate the size of the neutral conductor. It must be remembered, however, that, in a three-wire system where the neutral conductor is made equal in capacity to the combined size of the two outside conductors, and where the two outside conductors are joined together, we have virtually a two-wire system arranged so that it can be converted into a three-wire system later. In this case the calculation is exactly the same as in the case of the two-wire circuits, except that one of the two conductors is split into two smaller wires of the same capacity. This is frequently done where isolated plants are installed, and where the generators are wound for 125 volts and it may be desired at times to take current from an outside three-wire 125-250-volt system.

METHOD OF PLANNING A WIRING INSTALLATION

The first step in planning a wiring installation, is to gather all the data which will affect either directly or indirectly the system of wiring and the manner in which the conductors are to be installed. These data will include: Kind of building; construction of building; space available for conductors; source and system of electric-current supply; and all details which will determine the method of wiring to be employed. These last items materially affect the cost of the work, and are usually determined by the character of the building and by commercial considerations.

Method of Wiring. In a modern fireproof building, the only system of wiring to be recommended is that in which the conductors are installed in rigid conduits; although, even in such cases, it may be desirable, and economy may be effected thereby, to install the larger feeder and main conductors exposed on insulators using weatherproof slow-burning wire. This latter method should be used, however, only where there is a convenient runway for the conductors, so that they will not be crowded and will not cross pipes, ducts, etc., and also will not have too many bends. Also, the local inspection authorities should be consulted before using this method.

For mills, factories, etc., wires exposed on cleats or insulators are usually to be recommended, although rigid conduit, flexible conduit, or armored cable may be desirable.

In finished buildings, and for extensions of existing outlets, where the wiring could not readily or conveniently be concealed, moulding is generally used, particularly where cleat wiring or other exposed methods of wiring would be objectionable. However, as has already been said, moulding should not be employed where there is any liability to dampness.

In finished buildings, particularly where they are of frame construction, flexible steel conduits or armored cable are to be recommended.

While in new buildings of frame construction, knob and tube wiring are frequently employed, this method should be used only where the question of first cost is of prime importance. While armored cable will cost approximately 50 to 100 per cent more than knob and

tube wiring, the former method is so much more permanent and is so much safer that it is strongly recommended.

Systems of Wiring. The system of wiring—that is, whether the two-wire or the three-wire system shall be used—is usually determined by the source of supply. If the source of supply is an isolated plant, with simple two-wire generators, and with little possibility of current being taken from the outside at some future time, the wiring in the building should be laid out on the two-wire system. If, on the other hand, the isolated plant is three-wire (having three-wire generators, or two-wire generators with balancer sets), or if the current is taken from an outside source, the wiring in the building should be laid out on a three-wire system.

It very seldom happens that current supply from a central station is arranged with other than the three-wire system inside of buildings, because, if the outside supply is alternating current, the transformers are usually adapted for a three-wire system. For small buildings, on the other hand, where there are only a few lights and where there would be only one feeder, the two-wire system is used. As a rule, however, when the current is taken from an outside source, it is best to consult the engineer of the central station supplying the current, and to conform with his wishes. As a matter of fact, this should be done in any event, in order to ascertain the proper voltage for the lamps and for the motors, and also to ascertain whether the central station will supply transformers, meters, and lamps—for, if these are not thus supplied, they should be included in the contract for the wiring.

Location of Outlets. It is not within the scope of this treatise to discuss the matter of *illumination*, but it is desirable, at this point, to outline briefly the method of procedure.

A set of plans, including elevation and details, if any, and showing decorative treatment of the various rooms, should be obtained from the Architect. A careful study should then be made by the Architect, the Owner, and the Engineer, or some other person qualified to make recommendations as to illumination. The location of the outlets will depend: *First*, upon the decorative treatment of the room, which determines the æsthetic and architectural effects; *second*, upon the type and general form of fixtures to be used, which should be previously decided on; *third*, upon the tastes of the owners or

occupants in regard to illumination in general, as it is found that tastes vary widely in regard to amount and kind of illumination.

The location of the outlets, and the number of lights required at each, having been determined, the outlets should be marked on the plans.

The Architect should then be consulted as to the location of the centers of distribution, the available points for the risers or feeders, and the available space for the branch circuit conductors.

In regard to the *rising points for the feeders and mains*, the following precautions should be used in selecting chases:

1. The space should be amply large to accommodate all the feeders and mains likely to rise at that given point. This seems trite and unnecessary, but it is the most usual trouble with chases for risers. Formerly architects and builders paid little attention to the requirements for chases for electrical work; but in these later days of 2-inch and 2½-inch conduit, they realize that these pipes are not so invisible and mysterious as the force they serve to distribute, particularly when twenty or more such conduits must be stowed away in a building where no special provision has been made for them.

2. If possible, the space should be devoted solely to electric wiring. Steam pipes are objectionable on account of their temperature; and these and all other pipes are objectionable in the same space occupied by the electrical conduits, for if the space proves too small, the electric conduits are the first to be crowded out.

The chase, if possible, should be continuous from the cellar to the roof, or as far as needed. This is necessary in order to avoid unnecessary bends or elbows, which are objectionable for many reasons.

In similar manner, the location of *cut-out cabinets or distributing centers* should fulfil the following requirements:

1. They should be accessible at all times.

2. They should be placed sufficiently close together to prevent the circuits from being too long.

3. Do not place them in too prominent a position, as that is objectionable from the Architect's point of view.

4. They should be placed as near as possible to the rising chases, in order to shorten the feeders and mains supplying them.

Having determined the system and method of wiring, the location of outlets and distributing centers, the next step is to lay out the *branch circuits* supplying the various outlets.

Before starting to lay out the branch circuits, a drawing showing the floor construction, and showing the space between the top of the beams and girders and the flooring, should be obtained from the Architect. In fire-proof buildings of iron or steel construction, it is almost the invariable practice, where the work is to be concealed, to run the

conduits over the beams, under the rough flooring, carrying them between the sleepers when running parallel to the sleepers, and notching the latter when the conduits run across them (see Fig. 31). In wooden frame buildings, the conduits run parallel to the beams and to the furring (see Fig. 32); they are also sometimes run below the



Fig. 31. Running Conductors Concealed under Floor in Fireproof Building.

beams. In the latter case the beams have to be notched, and this is allowable only in certain places, usually near the points where the beams are supported. The Architect's drawing is therefore necessary in order that the location and course of the conduits may be indicated on the plans.

The first consideration in laying out the branch circuit is the *number of outlets* and *number of lights* to be wired on any one branch circuit. The *Rules of the National Electric Code* (Rule 21-D) require that "no set of incandescent lamps requiring more than 660 watts, whether grouped on one fixture or on several fixtures or pendants, will be dependent on one cut-out." While it would be possible to have branch circuits supplying more than 660 watts, by placing various cut-outs at different points along the route of the branch circuit, so as to subdivide it into small sections to comply with the rule, this method is not recommended, except in certain cases, for exposed wiring in factories or mills. As a rule, the proper method is to have the cut-outs located at the center of distribution, and to limit each branch circuit to 660 watts, which corresponds to twelve or thirteen 50-watt lamps, twelve being the usual limit. Attention is called to the fact that the inspectors usually allow 50 watts for each socket connected to a branch circuit; and although 8-candle-power lamps may be placed at some of the outlets, the inspectors hold that the standard lamp is approximately 50 watts, and for that reason there is always the likelihood of a lamp of that capacity being used, and their inspec-

tion is based on that assumption. Therefore, to comply with the requirements, an allowance of not more than twelve lamps per branch circuit should be made.

In ordinary practice, however, it is best to reduce this number still further, so as to make allowance for future extensions or to increase the number of lamps that may be placed at any outlet. For this reason, it is wise to keep the number of the outlets on a circuit at the lowest point consistent with economical wiring. It has been proven by actual practice, that the best results are obtained by limiting the number to five or six outlets on a branch circuit. Of course, where all the outlets have a single light each, it is frequently necessary, for reasons of economy, to increase this number to eight, ten, and, in some cases, twelve outlets.

We have already referred to the location of the wires or conduits. This question is generally settled by the peculiarities of the construction of the building. It is necessary to know this, however, before laying out the circuit work, as it frequently determines the course of a circuit.

Now, as to the course of the circuit work, little need be said, as it is largely influenced by the relative position of the outlets, cut-



Fig. 32. Running Conductors Concealed under Floor in Wooden Frame Building.

outs, switches, etc. Between the cut-out box and the first outlet, and between the outlets, it will have to be decided, however, whether the circuits shall run at right angles to the walls of the building or room, or whether they shall run direct from one point to another, irrespective of the angle they make to the sleepers or beams. Of course, in the former case, the advantages are that the cost is somewhat less and the number of elbows and bends is reduced. If the

tubes are bent, however, instead of using elbows, the difference in cost is usually very slight, and probably does not compensate for the disadvantages that would result from running the tubes diagonally. As to the number of bends, if branch circuit work is properly laid out and installed, and a proper size of tube used, it rarely happens that there is any difference in "pulling" the branch circuit wires. It may happen, in the event of a very long run or one having a large number of bends, that it might be advisable to adopt a short and most direct route.

Up to this time, the location of the distribution centers has been made solely with reference to architectural considerations; but they must now be considered in conjunction with the branch circuit work.

It frequently happens that, after running the branch circuits on the plans, we find, in certain cases, that the position of centers of distribution may be changed to advantage, or sometimes certain groups may be dispensed with entirely and the circuits run to other points. We now see the wisdom of ascertaining from the Architect where cut-out groups may be located, rather than selecting particular points for their location.

As a rule, wherever possible, it is wise to limit the length of each branch circuit to 100 feet; and the number and location of the distributing centers should be determined accordingly.

It may be found that it is sometimes necessary and even desirable to increase the limit of length. One instance of this may be found in hall or corridor lights in large buildings. It is generally desirable, in such cases, to control the hall lights from one point; and, as the number of lights at each outlet is generally small, it would not be economical to run mains for sub-centers of distribution. Hence, in instances of this character, the length of runs will frequently exceed the limit named. In the great majority of cases, however, the best results are obtained by limiting the runs to 90 or 100 feet.

There are several good reasons for placing such a limit on the length of a branch circuit. To begin with, assuming that we are going to place a limit on the loss in voltage (drop) from the switchboard to the lamp, it may be easily proven that up to a certain reasonable limit it is more economical to have a larger number of distributing centers and shorter branch circuits, than to have fewer centers and longer circuits. It is usual, in the better class of work, to limit the

loss in voltage in any branch circuit to approximately one volt. Assuming this limit (one volt loss), it can readily be calculated that the number of lights at one outlet which may be connected on a branch circuit 100 feet long (using No. 14 B. & S. wire), is *four*; or in the case of outlets having a single light each, *five* outlets may be connected on the circuit, the first being 60 feet from the cut-out, the others being 10 feet apart.

These examples are selected simply to show that if the branch circuits are much longer than 100 feet, the loss must be increased to more than one volt, or else the number of lights that may be connected to one circuit must be reduced to a very small quantity, provided, of course, the size of the wire remains the same.

Either of these alternatives is objectionable—the first, on the score of regulation; and the second, from an economical standpoint. If, for instance, the loss in a branch circuit with all the lights turned on is four volts (assuming an extreme case), the voltage at which a lamp on that circuit burns will vary from four volts, depending on the number of lights burning at a time. This, of course, will cause the lamp to burn below candle-power when all the lamps are turned on, or else to diminish its life by burning above the proper voltage when it is the only lamp burning on the circuit. Then, too, if the drop in the branch circuits is increased, the sizes of the feeders and the mains must be correspondingly increased (if the total loss remains the same), thereby increasing their cost.

If the number of lights on the circuit is decreased, we do not use to good advantage the available carrying capacity of the wire.

Of course, one solution of the problem would be to increase the size of the wire for the branch circuits, thus reducing the drop. This, however, would not be desirable, except in certain cases where there were a few long circuits, such as for corridor lights or other special control circuits. In such instances as these, it would be better to increase the sizes of the branch circuit to No. 12 or even No. 10 B. & S. Gauge conductors, than to increase the number of centers of distribution for the sake of a few circuits only, in order to reduce the number of lamps (or loss) within the limit.

The method of calculating the loss in conductors has been given elsewhere; but it must be borne in mind, in calculating the loss of a branch circuit supplying more than one outlet, that separate calcu-

lations must be made for each portion of the circuit. That is, a calculation must be made for the loss to the first outlet, the length in this case being the distance from the center of distribution to the first outlet, and the load being the total number of lamps supplied by the circuit. The next step would be to obtain the loss between the first and second outlet, the length being the distance between the two outlets, and the load, in this case, being the total number of lamps supplied by the circuit, *minus* the number supplied by the first outlet; and so on. The loss for the total circuit would be the sum of these losses for the various portions of the circuit.

Feeders and Mains. If the building is more than one story, an elevation should be made showing the height and number of stories. On this elevation, the various distributing centers should be shown diagrammatically; and the current in amperes supplied through each center of distribution, should be indicated at each center. The next step is to lay out a tentative system of feeders and mains, and to ascertain the load in amperes supplied by each feeder and main. The estimated length of each feeder and main should then be determined, and calculation made for the loss from the switchboard to each center of distribution. It may be found that in some cases it will be necessary to change the arrangement of feeders or mains, or even the centers of distribution, in order to keep the total loss from the switchboard to the lamps within the limits previously determined. As a matter of fact, in important work, it is always best to lay out the entire work tentatively in a more or less crude fashion, according to the "cut and dried" method, in order to obtain the best results, because the entire layout may be modified after the first preliminary layout has been made. Of course, as one becomes more experienced and skilled in these matters, the final layout is often almost identical with the first preliminary arrangement.

TESTING

Where possible, two tests of the electric wiring equipment should be made, one after the wiring itself is entirely completed, and switches, cut-out panels, etc., are connected; and the second one after the fixtures have all been installed. The reason for this is that if a ground or short circuit is discovered before the fixtures are installed, it is more easily remedied; and secondly, because there is no division of

the responsibility, as there might be if the first test were made only after the fixtures were installed. If the test shows no grounds or short circuits before the fixtures are installed, and one does develop after they are installed, the trouble, of course, is that the short circuit or ground is one or more of the fixtures. As a matter of fact, it is a wise plan always to make a separate test of each fixture after it is delivered at the building and before it is installed.

While a *magneto* is largely used for the purpose of testing, it is at best a crude and unreliable method. In the first place, it does not give an indication, even approximately, of the total insulation resistance, but merely indicates whether there is a ground or short circuit, or not. In some instances, moreover, a magneto test has led to serious errors, for reasons that will be explained. If, as is nearly always the case, the magneto is an alternating-current instrument, it may sometimes happen—particularly in long cables, and especially where there is a lead sheathing on the cable—that the magneto will ring, indicating to the uninitiated that there is a ground or short circuit on the cable. This may be, and usually is, far from being the case; and the cause of the ringing of the magneto is not a ground or short circuit, but is due to the capacity of the cable, which acts as a condenser under certain conditions, since the magneto producing an alternating current repeatedly charges and discharges the cable in opposite directions, this changing of the current causing the magneto to ring. Of course, this defect in a magneto could be remedied by using a commutator and changing it to a direct-current machine; but as the method is faulty in itself, it is hardly worth while to do this.

A portable *galvanometer* with a resistance box and Wheatstone bridge, is sometimes employed; but this method is objectionable because it requires a special instrument which cannot be used for many other purposes. Furthermore, it requires more skill and time to use than the *voltmeter* method, which will now be described.

The advantage of the voltmeter method is that it requires merely a direct-current voltmeter, which can be used for many other purposes, and which all engineers or contractors should possess, together with a box of cells having a potential of preferably over 30 volts. The voltmeter should have a scale of not over 150 volts, for the reason that if the scale on which the battery is used covers too wide a range (say 1,000 volts) the readings might be so small as to make the test inac-

curate. A good arrangement would be to have a voltmeter having two scales—say, one of 60 and one of 600—which would make the voltmeter available for all practical potentials that are likely to be used inside of a building. If desired, a voltmeter could be obtained with three connections having three scales, the lowest scale of which would be used for testing insulation resistances.

Before starting a test, all of the fuses should be inserted and switches turned on, so that the complete test of the entire installation can be made. When this has been done, the voltmeter and battery should be connected, so as to obtain on the lowest scale of the voltmeter the electromotive force of the entire group of cells. This connection is shown in Fig. 33. Immediately after this has been done, the insulation resistance to be tested is placed in circuit, whether the insulation to be tested is a switchboard, slate panel-board, or the entire wiring installation; and the connections are made as shown in Fig. 34. A reading should then again be taken of the voltmeter; and the leakage is in proportion to the difference between the first and second readings of the voltmeter. The explanation given below will show how this resistance may be calculated: It is evident that the resistance in the first case was merely the resistance of the voltmeter and the internal resistance of the battery. As a rule, the internal resistance of the battery is so small in comparison with the resistance of the voltmeter and the external resistance, that it may be entirely neglected, and this will be done in the following calculation. In the second case, however, the total resistance in circuits is the resistance of the voltmeter and the battery, *plus* the entire insulation resistance on all the wires, etc., connected in circuit.



Fig. 33. Connections of Voltmeter and Battery for Testing Insulation Resistance.

To put this in mathematical form, the voltage of the cells may be indicated by the letter E; and the reading of the voltmeter when the insulation resistance is connected by the circuit, by the letter E'. Let R represent the resistance of the voltmeter and R_x represent the insulation resistance of the installation which we wish to measure.

It is a fact which the reader undoubtedly knows, that the E. M. F. as indicated by the voltmeter in Fig. 34 is inversely proportional to the resistance: that is, the greater the resistance, the lower will be the reading on the voltmeter, as this reading indicates the leakage or current passing through the resistance. Putting this in the shape of a formula, we have from the theory of proportion:

$$E : E' :: R + R_x : \mathrm{R};$$

or,

$$E' R + E' R_x = E R.$$

Transposing,

$$E' R_x = E R - E' R = R (E - E'),$$

and

$$R_x = \frac{R (E - E')}{E'}.$$

Or, expressed in words, the insulation resistance is equal to the resistance of the voltmeter *multiplied by* the difference between the first reading (or the voltage in the cells) and the second reading (or the reading of the voltmeter with the insulation resistance in series with the voltmeter), *divided by* this last reading of the voltmeter.



Fig. 34. Insulation Resistance Placed in Circuit, Ready for Testing.

Example. Assume a resistance of a voltmeter (R) of 20,000 ohms, and a voltage of the cells (E) of 30 volts; and suppose that the insulation resistance test of a wiring installation, including switchboard, feeders, branch circuits, panel-boards, etc., is to be made, the insulation resistance being represented by the letter R_x. By substituting in the formula

$$R_x = \frac{R (E - E')}{E'},$$

and assuming that the reading of the voltmeter with the insulation resistance connected is 5, we have:

$$R = \frac{20{,}000 \times (30 - 5)}{5} = 100{,}000 \text{ ohms.}$$

If the test shows an excessive amount of leakage, or a ground or

short circuit, the location of the trouble may be determined by the process of elimination—that is, by cutting out the various feeders until the ground or leakage disappears, and, when the feeder on which the trouble exists has been located, by following the same process with the branch circuits.

Of course, the larger the installation and the longer and more numerous the circuits, the greater the leakage will be; and the lower will be the insulation resistance, as there is a greater surface exposed for leakage. The *Rules of the National Electric Code* give a sliding scale for the requirements as to insulation resistance, depending upon the amount of current carried by the various feeders, branch circuits, etc. The rule of the *National Electric Code* (No. 66) covering this point, is as follows:

"The wiring in any building must test free from grounds; *i. e.*, the complete installation must have an insulation between conductors and between all conductors and the ground (not including attachments, sockets, receptacles, etc.) not less than that given in the following table:

Up to	5	amperes	4,000,000 ohms
"	10	"	2,000,000 "
"	25	"	800,000 "
"	50	"	400,000 "
"	100	"	200,000 "
"	200	"	100,000 "
"	400	"	50,000 "
"	800	"	25,000 "
"	1,600	"	12,500 "

"The test must be made with all cut-outs and safety devices in place. If the lamp sockets, receptacles, electroliers, etc., are also connected, only one-half of the resistances specified in the table will be required."

ALTERNATING-CURRENT CIRCUITS

It is not within the province of this chapter to treat the various alternating-current phenomena, but simply to outline the modifications which should be made in designing and calculating electric light wiring, in order to make proper allowance for these phenomena.

The most marked difference between alternating and direct current, so far as wiring is concerned, is the effect produced by self-induction, which is characteristic of all alternating-current circuits. This self-induction varies greatly with conditions depending upon the arrangement of the circuit, the medium surrounding the circuit, the devices or apparatus supplied by or connected in the circuit, etc.

For example, if a coil having a resistance of 100 ohms is included in the circuit, a current of one ampere can be passed through the coil with an electric pressure of 100 volts, if direct current is used; while it might require a potential of several hundred volts to pass a current of one ampere if alternating-current were used, depending upon the number of turns in the coil, whether it is wound on iron or some other non-magnetic material, etc.

It will be seen from this example, that greater allowance should be made for self-induction in laying out and calculating alternating-current wiring, if the conditions are such that the self-induction will be appreciable.

On account of self-induction, the two wires of an alternating-current circuit must never be installed in separate iron or steel conduits, for the reason that such a circuit would be virtually a *choke coil* consisting of a single turn of wire wound on an iron core, and the self-induction would not only reduce the current passing through the circuit, but also might produce heating of the iron pipe. It is for this reason that the *National Electric Code* requires conductors constituting a given circuit to be placed in the same conduit, if that conduit is iron or steel, whenever the said circuit is intended to carry, or is liable to carry at some future time, an alternating current. This does not mean, in the case of a two-phase circuit, that all four conductors need be placed in the same conduit, but that the two conductors of a given phase must be placed in the same conduit. If, however, the three-wire system be used for a two-phase system, all three conductors should be placed in the same conduit, as should also be the case in a three-wire three-phase system. Of course, in a single-phase two- or three-wire system, the conductors should all be placed in the same conduit.

In calculating circuits carrying alternating current, no allowance usually should be made for self-induction when the conductors of the same circuit are placed close together in an iron conduit. When, however, the conductors are run exposed, or are separated from each other, calculation should be made to determine if the effects of self-induction are great enough to cause an appreciable inductive drop. There are several methods of calculating this drop due to self-induction—one by formula, and one by a mathematical method which will be described.

Skin Effect. Skin effect in alternating-current circuits is caused by an incorrect distribution of the current in the wire, the current tending to flow through the outer portion of the wire, it being a well-known fact that in alternating currents, the current density decreases toward the center of the conductor, and that in large wires, the current density at the center of the conductor is relatively quite small.

The skin effect increases in proportion to the square of the diameter, and also in direct ratio to the frequency of the alternating current.

For conductors of No. 0000 B. & S. Gauge, and smaller, and for frequencies of 60 cycles per second, or less, the skin effect is negligible and is less than one-half of one per cent.

For very large cables and for frequencies above 60 cycles per second, the skin effect may be appreciable; and in certain cases, allowance for it should be made in making the calculation. In ordinary practice, however, it may be neglected. Table IX, taken from *Alternating-Current Wiring and Distribution*, by W. R. Emmet, gives the data necessary for calculating the skin effect. The figures given in the first and third columns are obtained by multiplying the size of the conductor (in circular mils) by the frequency (number of cycles per second); and the figures in the second and fourth columns show the factor to be used in multiplying the ohmic resistance, in order to obtain the combined resistance and skin effect.

TABLE IX

Data for Calculating Skin Effect

Product of Circular Mils × Cycles per Sec.	Factor	Product of Circular Mils × Cycles per Sec.	Factor
10,000,000	1.00	70,000,000	1.13
20,000,000	1.01	80,000,000	1.17
30,000,000	1.03	90,000,000	1.20
40,000,000	1.05	100,000,000	1.25
50,000,000	1.08	125,000,000	1.34
60,000,000	1.10	150,000,000	1.43

The factors given in this table, *multiplied by* the resistance to direct currents, will give the resistance to alternating currents for copper conductors of circular cross-section.

Mutual Induction. When two or more circuits are run in the same vicinity, there is a possibility of one circuit inducing an electromotive force in the conductors of an adjoining circuit. This effect may result in raising or lowering the E. M. F. in the circuit in which a

mutual induction takes place. The amount of this induced E. M. F. set up in one circuit by a parallel current, is dependent upon the current, the frequency, the lengths of the circuits running parallel to each other, and the relative positions of the conductors constituting the said circuits.

Under ordinary conditions, and except for long circuits carrying high potentials, the effect of mutual induction is so slight as to be negligible, unless the conductors are improperly arranged. In order to prevent mutual induction, the conductors constituting a given circuit should be grouped together. Figs. 35 to 39, inclusive, show



Fig. 35. 16,000 Alt. .035 Volts. 7,200 Alt. .016 Volts.

Fig. 36. 16,000 Alt. .015 Volts. 7,200 Alt. .0065 Volts.

Fig. 37. 16,000 Alt. .070 Volts. 7,200 Alt. .032 Volts.

Fig. 38. 16,000 Alt. .006 Volts. 7,200 Alt. .0027 Volts.

Fig. 39. 16,000 Alt. .112 Volts. 7,200 Alt. .050 Volts.

Various Groupings of Conductors in Two Two-Wire Circuits, Giving Various Effects of Induction.

five arrangements of two two-wire circuits; and show how relatively small the effect of first induction is when the conductors are properly arranged, as in Fig. 38, and how relatively large it may be when improperly arranged, as in Fig. 39. These diagrams are taken from a publication of Mr. Charles F. Scott, entitled *Polyphase Transmission*, issued by the Westinghouse Electric & Manufacturing Company.

Line Capacity. The effect of capacity is usually negligible, except in long transmission lines where high potentials are used; no calculations or allowance need be made for capacity, for ordinary circuits.

Calculation of Alternating-Current Circuits. In the instruction paper on "Power Stations and Transmission," a method is given for calculating alternating-current lines by means of formulæ, and data are given regarding power factor and the calculation of both single-phase and polyphase circuits. For short lines, secondary wiring, etc., however, it is probably more convenient to use the chart method devised by Mr. Ralph D. Mershon, described in the *American Electrician* of June, 1897, and partially reproduced as follows:

DROP IN ALTERNATING-CURRENT LINES

When alternating currents first came into use, when transmission distances were short and the only loads carried were lamps, the question of *drop* or *loss of voltage* in the transmitting line was a simple one, and the same methods as for direct current could without serious error be employed in dealing with it. The conditions existing in alternating practice to-day—longer distances, polyphase circuits, and loads made up partly or wholly of induction motors—render this question less simple; and direct-current methods applied to it do not lead to satisfactory results. Any treatment of this or of any engineering subject, if it is to benefit the majority of engineers, must not involve groping through long equations or complex diagrams in search of practical results. The results, if any, must be in available and convenient form. In what follows, the endeavor has been made to so treat the subject of drop in alternating-current lines that if the reader be grounded in the theory the brief space devoted to it will suffice; but if he do not comprehend or care to follow the simple theory involved, he may nevertheless turn the results to his practical advantage.

Calculation of Drop. Most of the matter heretofore published on the subject of drop treats only of the inter-relation of the E. M. F.'s involved, and, so far as the writer knows, there have not appeared in convenient form the data necessary for accurately calculating this quantity. Table X (page 47) and the chart (page 46) include, in a form suitable for the engineer's pocketbook, everything necessary for calculating the drop of alternating-current lines.

The chart is simply an extension of the vector diagram (Fig. 40), giving the relations of the E. M. F.'s of line, load and generator. In

Fig. 40, E is the generator E. M. F.; e, the E. M. F. impressed upon the load; c, that component of E which overcomes the back E. M. F. due to the impedance of the line. The component c is made up of two components at right angles to each other. One is a, the component overcoming the IR or back E. M. F. due to resistance of the line. The other is b, the component overcoming the reactance E. M. F. or back E. M. F. due to the alternating field set up around the wire by the current in the wire. The drop is the difference between E and e. It is d, the radial distance between two circular arcs, one of which is drawn with a radius e, and the other with a radius E.

The chart is made by striking a succession of circular arcs with O as a center. The radius of the smallest circle corresponds to e, the E. M. F. of the load, which is taken as 100 per cent. The radii of the succeeding circles increase by 1 per cent of that of the smallest circle; and, as the radius of the last or largest circle is 140 per cent of that of the smallest, the chart answers for drops up to 40 per cent of the E. M. F. delivered.



Fig. 40. Vector Diagram.

The terms *resistance volts, resistance E. M. F., reactance volts,* and *reactance E. M. F.*, refer, of course, to the voltages for overcoming the back E. M. F.'s due to resistance and reactance respectively. The figures given in the table under the heading "Resistance-Volts for One Ampere, etc." are simply the resistances of 2,000 feet of the various sizes of wire. The values given under the heading "Reactance-Volts, etc.," are, a part of them, calculated from tables published some time ago by Messrs. Houston and Kennelly. The remainder were obtained by using Maxwell's formula.

The explanation given in the table accompanying the chart



Chart for Calculating Drop in Alternating-Current Lines.

TABLE X

Data for Calculating Drop in Alternating-Current Lines

To be used in conjunction with Chart on opposite page.

By means of the table, calculate the *Resistance-Volts* and the *Reactance-Volts* in the line, and find what per cent each is of the E. M. F. delivered at the end of the line. Starting from the point on the chart where the vertical line corresponding with the power-factor of the load intersects the smallest circle, lay off in per cent the resistance E. M. F. horizontally and to the right; from the point thus obtained, lay off upward in per cent the reactance-E. M. F. The circle on which the last point falls gives the drop, in per cent, of the E. M. F. delivered at the end of the line. Every tenth circle arc is marked with the per cent drop to which it corresponds.

Size of wire—B. & S.	Upper figures are Weight in Lbs. per 1,000 ft. Single Wire	Upper figures are RESISTANCE-VOLTS in 1,000 ft. of Line (2,000 ft. of wire) for One Ampere	Throughout the table the lower figures in the squares give values for ONE MILE of line, corresponding to those of the upper figures for 1,000 feet of line. Upper figures are REACTANCE-VOLTS in 1,000 ft. of Line (= 2,000 ft. of Wire) for One Ampere at 7,200 Alternations per Minute (60 Cycles per Second) for the distance given between Centers of Conductors.										
			½"	1"	2"	3"	6"	9"	12"	18"	24"	30"	36"
0000	639 3,376	.098 .518	.046 .243	.079 .417	.111 .586	.130 .687	.161 .850	.180 .951	.193 1.02	.212 1.12	.225 1.19	.235 1.24	.244 1.29
000	507 2,677	.124 .653	.052 .275	.085 .449	.116 .613	.135 .713	.167 .882	.185 .977	.199 1.05	.217 1.15	.230 1.22	.241 1.27	.249 1.32
00	402 2,123	.156 .824	.057 .301	.090 .475	.121 .639	.140 .739	.172 .908	.190 1.00	.204 1.08	.222 1.17	.236 1.25	.246 1.30	.254 1.34
0	319 1,685	.197 1.04	.063 .332	.095 .502	.127 .671	.145 .766	.177 .935	.196 1.04	.209 1.10	.228 1.20	.241 1.27	.251 1.33	.259 1.37
1	253 1,335	.248 1.31	.068 .359	.101 .533	.132 .687	.151 .797	.183 .966	.201 1.06	.214 1.13	.233 1.23	.246 1.30	.256 1.35	.265 1.40
2	201 1,059	.313 1.65	.074 .391	.106 .560	.138 .728	.156 .824	.188 .993	.206 1.09	.220 1.16	.238 1.26	.252 1.33	.262 1.38	.270 1.43
3	159 840	.394 2.08	.079 .417	.112 .591	.143 .755	.162 .856	.193 1.02	.212 1.12	.225 1.19	.244 1.29	.257 1.36	.267 1.41	.275 1.45
4	126 666	.497 2.63	.085 .449	.117 .618	.149 .787	.167 .882	.199 1.05	.217 1.15	.230 1.22	.249 1.32	.262 1.38	.272 1.44	.281 1.48
5	100 528	.627 3.31	.090 .475	.121 .639	.154 .813	.172 .908	.204 1.08	.223 1.18	.236 1.25	.254 1.34	.268 1.42	.278 1.47	.286 1.51
6	79 419	.791 4.18	.095 .502	.127 .671	.158 .834	.178 .940	.209 1.10	.228 1.20	.241 1.27	.260 1.37	.272 1.44	.283 1.49	.291 1.54
7	63 332	.997 5.27	.101 .533	.132 .697	.164 .866	.183 .966	.214 1.13	.233 1.23	.246 1.30	.265 1.40	.278 1.47	.288 1.52	.296 1.56
8	50 263	1.260 6.64	.106 .560	.138 .729	.169 .893	.188 .993	.220 1.16	.238 1.26	.252 1.33	.270 1.43	.284 1.50	.293 1.55	.302 1.60

(Table X) is thought to be a sufficient guide to its use, but a few examples may be of value.

Problem. Power to be delivered, 250 K.W.; E. M. F. to be delivered, 2,000 volts; distance of transmission, 10,000 feet; size of wire, No. 0; distance between wires, 18 inches; power factor of load, .8; frequency, 7,200 alternations per minute. Find the line loss and drop.

Remembering that the power factor is that fraction by which the apparent power of volt-amperes must be multiplied to give the true power, the apparent power to be delivered is

$$\frac{250 \text{ K.W.}}{.8} = 312.5 \text{ apparent K.W.}$$

The current, therefore, at 2,000 volts will be

$$\frac{312{,}500}{2{,}000} = 156.25 \text{ amperes.}$$

From the table of reactances under the heading "18 inches," and corresponding to No. 0 wire, is obtained the constant .228. Bearing the instructions of the table in mind, the reactance-volts of this line are, 156.25 (amperes) × 10 (thousands of feet) × .228 = 356.3 volts, which is 17.8 per cent of the 2,000 volts to be delivered.

From the column headed "Resistance-Volts" and corresponding to No. 0 wire, is obtained the constant .197. The resistance-volts of the line are, therefore, 156.25 (amperes) × 10 (thousands of feet) × .197 = 307.8 volts, which is 15.4 per cent of the 2,000 volts to be delivered.

Starting, in accordance with the instructions of the table, from the point where the vertical line (which at the bottom of the chart is marked "Load Power Factor" .8) intersects the inner or smallest circle, lay off horizontally and to the right the resistance-E. M. F. in per cent (15.4); and *from the point thus obtained*, lay off vertically the reactance-E. M. F. in per cent (17.8). The last point falls at about 23 per cent, as given by the circular arcs. This, then, is the drop, in per cent, of *the E. M. F. delivered.* The drop, in per cent, of the *generator* E. M. F. is, of course,

$$\frac{23}{100+23} = 18.7 \text{ per cent.}$$

The percentage *loss of power* in the line has not, as with direct current, the same value as the percentage drop. This is due to the fact that the line has reactance, and also that the apparent power

delivered to the load is not identical with the true power—that is, the load power factor is less than unity. The loss must be obtained by calculating $I^2 R$ for the line, or, what amounts to the same thing, by multiplying the resistance-volts by the current.

The resistance-volts in this case are 307.8, and the current 156.25 amperes. The loss is $307.8 \times 156.25 = 48.1$ K. W. The percentage *loss* is

$$\frac{48.1}{250 + 48.1} = 16.1 \text{ per cent.}$$

Therefore, for the problem taken, the *drop* is 18.7 per cent, and the *loss* is 16.1 per cent. If the problem be to find the size wire for a given drop, it must be solved by trial. Assume a size of wire and calculate the drop; the result in connection with the table will show the direction and extent of the change necessary in the size of wire to give the required drop.

The effect of the line reactance in increasing the drop should be noted. If there were no reactance, the drop in the above example would be given by the point obtained in laying off on the chart the resistance-E. M. F. (15.4) only. This point falls at 12.4 per cent, and the drop in terms of the generator E. M. F. would be

$$\frac{12.4}{112.4} = 11 \text{ per cent, instead of } 18.7 \text{ per cent.}$$

Anything therefore which will reduce reactance is desirable.

Reactance can be reduced in two ways. One of these is to diminish the distance between wires. The extent to which this can be carried is limited, in the case of a pole line, to the least distance at which the wires are safe from swinging together in the middle of the span; in inside wiring, by the danger from fire. The other way of reducing reactance is to split the copper up into a greater number of circuits, and arrange these circuits so that there is no inductive interaction. For instance, suppose that in the example worked out above, two No. 3 wires were used instead of one No. 0 wire. The resistance-volts would be practically the same, but the reactance-volts would be less in the ratio $\frac{1}{2} \times \frac{.244}{.228} = .535$, since each circuit would bear half the current the No. 0 circuit does, and the constant for No. 3 wire is .244, instead of .228—that for No. 0. The effect of subdividing the copper is also shown if in the example given it is desired to reduce the drop

to, say, one-half. Increasing the copper from No. 0 to No. 0000 will not produce the required result, for, although the resistance-volts will be reduced one-half, the reactance-volts will be reduced only in the ratio $\frac{.212}{.228}$. If, however, *two* inductively independent circuits of No. 0 wire be used, the resistance- and reactance-volts will both be reduced one-half, and the drop will therefore be diminished the required amount.

The component of drop due to reactance is best diminished by subdividing the copper or by bringing the conductors closer together. It is little affected by change in size of conductors.

An idea of the manner in which changes of power factor affect drop is best gotten by an example. Assume distance of transmission, distance between conductors E. M. F., and frequency, the same as in the previous example. Assume the *apparent* power delivered the same as before, and let it be constant, but let the power factor be given several different values; the true power will therefore be a variable depending upon the value of the power factor. Let the size of wire be No. 0000. As the apparent power, and hence the current, is the same as before, and the line resistance is one-half, the resistance-E. M. F. will in this case be

$$\frac{15.4}{2}, \text{ or } 7.7 \text{ per cent of the E. M. F. delivered.}$$

Also, the reactance-E. M. F. will be

$$\frac{.212 \times 17.8}{.228} = 16.5 \text{ per cent.}$$

Combining these on the chart for a power factor of .4, and deducing the drop, in per cent, of the generator E. M. F., the value obtained is 15.3 per cent; with a power factor of .8, the drop is 14 per cent; with a power factor of unity, it is 8 per cent. If in this example the *true* power, instead of the *apparent* power, had been taken as constant, it is evident that the values of drop would have differed more widely, since the current, and hence the resistance- and reactance-volts, would have increased as the power factor diminished. The condition taken more nearly represents that of practice.

If the line had resistance and no reactance, the several values of drop, instead of 15.3, 14, and 8, would be 3.2, 5.7, and 7.2 per cent respectively, showing that for a load of lamps the drop will not

be much increased by reactance; but that with a load, such as induction motors, whose power factor is less than unity, care should be taken to keep the reactance as low as practicable. In all cases it is advisable to place conductors as close together as good practice will permit.

When there is a transformer in circuit, and it is desired to obtain the combined drop of transformer and line, it is necessary to know the resistance- and reactance-volts of the transformer. The resistance-volts of the combination of line and transformer are the sum of the resistance-volts of the line and the resistance-volts of the transformer. Similarly, the reactance-volts of the line and transformer are the sum of their respective reactance-volts. The resistance- and reactance-E. M. F.s of transformers may usually be obtained from the makers, and are ordinarily given in per cent.* These percentages express the values of the resistance- and reactance-E. M. F.'s when the transformer delivers its normal *full-load* current; and they express these values in terms of the normal *no-load* E. M. F. of the transformer.

Consider a transformer built for transformation between 1,000 and 100 volts. Suppose the resistance- and reactance-E. M. F.'s given are 2 per cent and 7 per cent respectively. Then the corresponding voltages when the transformer delivers full-load current, are 2 and 7 volts or 20 and 70 volts according as the line whose drop is required is connected to the low-voltage or high-voltage terminals. These values, 2—7 and 20—70, hold, no matter at what voltage the trans-

*When the required values cannot be obtained from the makers, they may be measured. Measure the resistance of both coils. If the line to be calculated is attached to the high-voltage terminals of the transformer, the equivalent resistance is that of the high-voltage coil, *plus* the resistance obtained by *increasing* in the square of the ratio of transformation the measured resistance of the low-voltage coil That is, if the ratio of transformation is 10, the equivalent resistance referred to the high-voltage circuit is the resistance of the high-voltage coil, *plus* 100 times that of the low-voltage coil. This equivalent resistance multiplied by the high-voltage current gives the transformer resistance-volts referred to the high-voltage circuit. Similarly, the equivalent resistance referred to the low-voltage circuit is the resistance of the low-voltage coil, *plus* that of the high-voltage coil *reduced* in the square of the ratio of transformation. It follows, of course, from this, that the values of the resistance-volts referred to the two circuits bear to each other the ratio of transformation. To obtain the reactance-volts, short-circuit one coil of the transformer and measure the voltage necessary to force through the other coil its normal current at normal frequency. The result is, nearly enough, the reactance-volts. It makes no difference which coil is short-circuited, as the results obtained in one case will bear to those in the other the ratio of transformation. If a close value is desired, subtract from the square of the voltage reading the square of the *resistance*-volts, and take the square root of the difference as the reactance-volts.

former is operated, since they depend only upon the strength of current, providing it is of the normal frequency. If any other than the full-load current is drawn from the transformer, the reactance- and resistance-volts will be such a proportion of the values given above as the current flowing is of the full-load current. It may be noted, in passing, that when the resistance- and reactance-volts of a transformer are known, its regulation may be determined by making use of the chart in the same way as for a line having resistance and reactance.

As an illustration of the method of calculating the drop in a line and transformer, and also of the use of table and chart in calculating low-voltage mains, the following example is given:

Problem. A single-phase induction motor is to be supplied with 20 amperes at 200 volts; alternations, 7,200 per minute; power factor, .78. The distance from transformer to motor is 150 feet, and the line is No. 5 wire, 6 inches between centers of conductors. The transformer reduces in the ratio $\frac{2,000}{200}$, has a capacity of 25 amperes at 200 volts, and, when delivering this current and voltage, its resistance-E. M. F. is 2.5 per cent, its reactance-E. M. F. 5 per cent. Find the drop.

The reactance of 1,000 feet of circuit consisting of two No. 5 wires, 6 inches apart, is .204. The reactance-volts therefore are

$$.204 \times \frac{150}{1,000} \times 20 = .61 \text{ volts.}$$

The resistance-volts are

$$.627 \times \frac{150}{1,000} \times 20 = 1.88 \text{ volts.}$$

At 25 amperes, the resistance-volts of the transformer are 2.5 per cent of 200, or 5 volts. At 20 amperes, they are $\frac{20}{25}$ of this, or 4 volts. Similarly, the transformer reactance-volts at 25 amperes are 10, and at 20 amperes are 8 volts. The combined reactance-volts of transformer and line are 8 + .61 = 8.61, which is 4.3 per cent of the 200 volts to be delivered. The combined resistance-volts are 1.88 +4, or 5.88, which is 2.94 per cent of the E. M. F. to be delivered. Combining these quantities on the chart with a power factor of .78, the drop is 5 per cent of the delivered E. M. F.,

$$\text{or } \frac{5}{105} = 4.8 \text{ per cent}$$

of the impressed E. M. F. The transformer must be supplied with

$$\frac{2{,}000}{.952} = 2{,}100 \text{ volts},$$

in order that 200 volts shall be delivered to the motor.

Table X (page 47) is made out for 7,200 alternations, but will answer for any other number if the values for reactance be changed in direct proportion to the change in alternations. For instance, for 16,000 alternations, multiply the reactances given by $\frac{16{,}000}{7{,}200}$. For other distances between centers of conductors, interpolate the values given in the table. As the reactance values for different sizes of wire change by a constant amount, the table can, if desired, be readily extended for larger or smaller conductors.

The table is based on the assumption of sine currents and E. M. F.'s. The best practice of to-day produces machines which so closely approximate this condition that results obtained by the above methods are well within the limits of practical requirements.

Polyphase Circuits. So far, single-phase circuits only have been dealt with. A simple extension of the methods given above adapts them to the calculation of polyphase circuits. A four-wire *quarter-phase* (two-phase) transmission may, so far as loss and regulation are concerned, be replaced by two single-phase circuits identical (as to size of wire, distance between wires, current, and E. M. F.) with the two circuits of the quarter-phase transmission, provided that in both cases there is no inductive interaction between circuits. Therefore, to calculate a four-wire, quarter-phase transmission, compute the single-phase circuit required to transmit one-half the power at the same voltage. The quarter-phase transmission will require two such circuits.

A three-wire, *three-phase* transmission, of which the conductors are symmetrically related, may, so far as loss and regulation are concerned, be replaced by two single-phase circuits having no inductive interaction, and identical with the three-phase line as to size, wire, and distance between wires. Therefore, to calculate a three-phase transmission, calculate a single-phase circuit to carry one-half the load at the same voltage. The three-phase transmission will require three wires of the size and distance between centers as obtained for the single-phase.

A three-wire, quarter-phase transmission may be calculated

exactly as regards loss, and *approximately* as regards drop, in the same way as for three-phase. It is possible to exactly calculate the drop, but this involves a more complicated method than the approximate one. The error by this approximate method is generally small. It is possible, also, to get a somewhat less drop and loss with the same copper by proportioning the cross-section of the middle and outside wires of a three-wire, quarter-phase circuit to the currents they carry, instead of using three wires of the same size. The advantage, of course, is not great, and it will not be considered here.

WIRING AN OFFICE BUILDING

The building selected as a typical sample of a wiring installation is that of an office building located in Washington, D. C. The figures shown are reproductions of the plans actually used in installing the work.

The building consists of a basement and ten stories. It is of fireproof construction, having steel beams with terra-cotta flat arches. The main walls are of brick and the partition walls of terra-cotta blocks, finished with plaster. There is a space of approximately five inches between the top of the iron beams and the top of the finished floor, of which space about three inches was available for running the electric conduits. The flooring is of wood in the offices, but of concrete, mosaic, or tile in the basement, halls, toilet-rooms, etc.

The electric current supply is derived from the mains of the local illuminating company, the mains being brought into the front of the building and extending to a switchboard located near the center of the basement.

As the building is a very substantial fireproof structure, the only method of wiring considered was that in which the circuits would be installed in iron conduits.

Electric Current Supply. The electric current supply is direct current, two-wire for power, and three-wire for lighting, having a potential of 236 volts between the outside conductors, and 118 volts between the neutral and either outside conductor.

Switchboard. On the switchboard in the basement are mounted wattmeters, provided by the local electric company, and the various switches required for the control and operation of the lighting and power feeders. There are a total of ten triple-pole switches for lighting, and eighteen for power. An indicating voltmeter and ampere meter are also placed in the switchboard. A voltmeter is provided with a double-throw switch, and so arranged as to measure the potential across the two outside conductors, or between the neutral conductor and either of the outside conductors. The ampere meter is arranged with two shunts, one being placed in each outside leg; the shunts are connected with a double-pole, double-throw switch, so that the ampere meter can be connected to either shunt and thus measure the current supplied on each side of the system.

Character of Load. The building is occupied partly as a newspaper office, and there are several large presses in addition to the usual linotype machines, trimmers, shavers, cutters, saws, etc. There are also electrically-driven exhaust fans, house pumps, air-compressors, etc. The upper portion of the building is almost entirely devoted to offices rented to outside parties. The total number of motors supplied was 55; and the total number of outlets, 1,100, supplying 2,400 incandescent lamps and 4 arc lamps.

Feeders and Mains. The arrangement of the various feeders and mains, the cut-out centers, mains, etc., which they supply, are shown diagrammatically in Fig. 41, which also gives in schedule the sizes of feeders, mains, and motor circuits, and the data relating to the cut-out panels.

Although the current supply was to be taken from an outside source, yet, inasmuch as there was a probability of a plant being installed in the building itself at some future time, the three-wire system of feeders and mains was designed, with a neutral conductor equal to the combined capacity of the two outside conductors, so that 120-volt two-wire generators could be utilized without any change in the feeders.

Basement. The plan of the basement, Fig. 42, shows the branch circuit wiring for the outlets in the basement, and the location of the main switchboard. It also shows the trunk cables for the interconnection system serving to provide the necessary wires for telephones,



Fig. 41. Wiring of an Office Building. Diagram Showing Arrangement of Feeders and Mains, Cut-Out Centers, etc.



Fig. 42. Wiring an Office Building. Basement Plan Showing Branch Circuit Wiring for Outlets in Basement, Location of Main Switchboard, and Trunk Cables of the Interconnection System Providing Wires for Telephone, Ticker, and Messenger Call Service, etc,

tickers, messenger calls, etc., in all the rooms throughout the building, as will be described later.

To avoid confusion, the feeders were not shown on the basement plan, but were described in detail in the specification, and installed in accordance with directions issued at the time of installation. The electric current supply enters the building at the front, and a service switch and cut-out are placed on the front wall. From this point, a two-wire feeder for power and a three-wire feeder for lighting, are run to the main switchboard located near the center of the basement. Owing to the size of the conduits required for these supply feeders, as well as the main feeders extending to the upper floors of the building, the said conduits are run exposed on substantial hangers suspended from the basement ceiling.

First Floor. The rear portion of the building from the basement through the first floor, Fig. 43, and including the mezzanine floor, between the first and second floors, at the rear portion of the building only, is utilized as a press room for several large and heavy, modern newspaper presses. The motors and controllers for these presses are located on the first floor. A separate feeder for each of these press motors is run directly from the main switchboard to the motor controller in each case. Empty conduits were provided, extending from the controllers to the motor in each case, intended for the various control wires installed by the contractor for the press equipments.

One-half of the front portion of the first floor is utilized as a newspaper office; the remaining half, as a bank.

Second Floor. The rear portion of the second floor, Fig. 44, is occupied as a composing and linotype room, and is illuminated chiefly by means of drop-cords from outlets located over the linotype machines and over the compositors' cases. Separate $\frac{1}{8}$-horse-power motors are provided for each linotype machine, the circuits for the same being run underneath the floor.

Upper Floors. A typical plan (Fig. 45) is shown of the upper floors, as they are similar in all respects with the exception of certain changes in partitions, which are not material for the purpose of illustration or for practical example. The circuit work is sufficiently intelligible from the plan to require no further explanation.

Interconnection System. Fig. 46 is a diagram of the interconnection system, showing the main interconnection box located in the


SCHEDULE OF CIRCUITS
NO.
SUPPLIED BY CUTOUT
SUPPLIED BY MAIN
No. of BRANCHES
OUTLETS SUPPLIED
TOTAL OUTLETS
TOTAL LIGHTS
AT WHAT POINT CONTROLLED
I B 1 a 1 8 Sat B
II " " 1 bcde 4 8 " "
III " " 1 f 1 8 " "
IV " " 1 g 1 10 " "
V " " 1 h 1 10 " "
VI " " 1 i 1 10 " "
VII " " 1 j 1 10 " "
VIII " " 1 klm 3 6 " "
IX " " 1 nop 3 6 " "
16 76
X C C-1 1 qrst 4 8 Sat C
11 " " 1 u 1 10 " "
12 " " 1 vwx 3 6 " "
13 " " 1 y 1 10 " "
14 " " 1 z 1 10 " "
15 " " 1 a' 1 10 " "
16 " " 1 b' 1 8 " "
17 " " 1 c'd'e'f' 4 8 " "
16 70
19 D D-1 1 8 Receptacles 8 8
20 " " 1 8 8
21 " " 1 8 8
22 " " 1 q h' i' 3 6 Sat D
23 " " 1 j k' l' 3 6 " "
24
25
26 SEE MEZZ. PLAN
27
28
29
30 E E-1 1 y z' 2 3 Sat E
31 " " 1 a'' 1 8 " "
32 " " 1 b'' 1 8 " "
33 " " 1 c'' 1 8 " "
34 " " 1 d'' e'' f' g' 4 4 " "
35
36
37 SEE MEZZ. PLAN
38
39
40 F 1 o'' 1 8 Sat F
41 " " 1 p'' 1 2 " "
42 " " 1 q'' r'' 2 10 " "
43 " " 1 s'' 1 4 " "
44 " " 1 t'' u'' 2 6 " "
45 " " 1 v'' 1 1 " "
8 31
RISE TO CONTROLLER 7'-0" FROM FL.
SEE SKETCH BELOW
EMPTY CONDUIT
PRESS ROOM
MAIN E-1
PAPER STORAGE
INT. BOX 14 TO BE LOCATED OVER PANEL E
TERMINATE AT RECEPTACLES ON PRESS, AS DIRECTED
RISE TO OUTLET
CABLE NO. 35 UNDER FLOOR
RISING POINT X
2 WIRES 1" CONDUIT
MAIN B-1
MAIN C-1
NEWSPAPER COUNTING ROOM
STORE
NOTE: THE CLOCKS IN STORE AND COUNTING ROOM ARE TO BE LOCATED AS DIRECTED BY ARCHITECT.
WALL BETWEEN PRESS ROOM & PAPER STORAGE
CONTROLLER PLATFORM
EMPTY CONDUIT
PRESS RM. FLOOR
SKETCH SHOWING ROUTE OF EMPTY CONDUITS RISING TO CONTROLLER PLATFORM IN PRESS ROOM.
NOTE: ALL CONDUITS FOR THE PRESSES MUST COME THROUGH THE CONTROLLER PLATFORM 21" FROM THE WALL.
ALL CONDUITS ARE TO TERMINATE IN PRESS AS DIRECTED.

Fig. 43. Wiring of an Office Building.

First-Floor Plan, Showing Press Room in Rear, Containing Motors and Controllers for Newspaper Presses, Fed Directly from Main Switchboard in Basement; also, in front, Newspaper Counting Room and Bank Offices.



SCHEDULE OF CIRCUITS

NO.	CUT-OUT	MAIN	No. of BRANCHES	OUTLETS SUPPLIED	TOTAL OUTLETS	LIGHTS	AT WHAT POINT CONTROLLED
1	A	A-2	1	a	1	2	Sat A
2	"	"	1	b c	2	7	
3	"	"	1	d e f	3	3	
4	"	"	1	g h i j	4	8	
5	"	"	1	k l	2	4	
6	"	"	1	m	1	1	
7	"	"	1	n	"	"	
8	"	"	1	o	"	"	
9	"	"	1	p q r s	4	4	
10	"	"	1	t u	2	8	
11	"	"	1	v	1	3	
12	"	"	1	w & 6 Drop Cds	7	"	
13	"	"	1	x y z a' b'	4	4	
14	"	"	1	c' d'	2	2	
					30	76	
15	B	B-2	1	Drop Cords	6	6	
16	"	"	1	" "	"	"	
17	"	"	1	" "	"	"	
18	"	"	1	" "	"	"	
19	"	"	1	" "	"	"	
20	"	"	1	" "	"	"	
21	"	"	1	" "	10	10	
22	"	"	1	" "	6	6	
23	"	"	1	" "	"	"	
24	"	"	1	" "	"	"	
25	"	"	1	" "	"	"	
26	"	"	1	" "	"	"	
27	"	"	1	" "	"	"	
28	"	"	1	" "	9	9	
29	"	"	1	" "	"	"	
30	"	"	1	" "	"	"	
31	"	"	1	" "	"	"	
32	"	"	1	" "	7	7	
33	"	"	1	" "	6	6	
34	"	"	1	" "	7	7	
35	"	"	1	" "	6	6	
36	"	"	1	e'	1	8	Sat B
37	"	"	1	Drop Cords	7	7	
38	"	"	1	" "	9	9	
39	"	"	1	f'	1	8	Sat B
40	"	"	1	g' h' i' j' k'	5	5	
41	"	"	1	l' m'	2	3	Sat B
42	"	"	1	Drop Cords	7	7	
43	"	"	1	" "	7	7	
44	"	"	1	" "	8	8	
45	C	C-2	1	n' o'	2	8	Sat C
46	"	"	1	p'	1	8	" "

TERMINATE ALL MOTOR CIRCUITS AT MOTOR CONTROLLER AS DIRECTED

MOTOR CIRCUITS

NO.	SUPPLIED BY: FEEDER NO	CUT-OUT	FLOOR	H.P. SUPPLIED	CURRENT IN AMPERES	LENGTH IN FT. (ONE WAY)	SIZE OF WIRE	INSIDE DIA. OF CONDUIT ALLOWED *
12	9	D	2ND	* *		98	10	
13	"	"	"	"		90	"	"
14	"	"	"	"		82	"	"
15	"	"	"	"		76	"	"
16	"	"	"	"		66	"	"
17	"	"	"	"		60	"	"
18	"	"	"	"		52	"	"
19	"	"	"	"		46	"	"
20	"	"	"	"		38	"	"
21	"	"	"	"		28	"	"
22	"	"	"	"		94	"	"
23	"	"	"	"		86	"	"
24	"	"	"	"		78	"	"
25	"	"	"	"		70	"	"
26	"	"	"	"		62	"	"
27	"	"	"	"		54	"	"
28	"	"	"	"		46	"	"
29	"	"	"	"		38	"	"
30	"	"	"	"		30	"	"
31	"	"	"	"		90	"	"
32	"	"	"	"		"	"	"
33	"	"	"	"		"	"	"
34	"	E	"	3/4		22	"	"
35	"	"	"	"		32	"	"
36	"	"	"	"		36	"	"
37	"	"	"	"		34	"	"
38	"	"	"	1		46	12	"
39	"	"	"	"		46	10	"
40	"	"	"	"		36	"	"
41	"	"	"	"		28	"	"
42	"	"	"	3		18	"	"

* BOTH CONDUCTORS IN ONE CONDUIT
* * ½ H.P. REDUCED TO ¼ H.P.

Fig. 44. Wiring of an Office Building. Plan of Second Floor. Rear Portion Occupied as a Composing and Linotype Room.



SCHEDULE OF CIRCUITS

NO.	SUPPLIED by CUTOUT	SUPPLIED by MAIN	No. of BRANCHES	OUTLETS SUPPLIED	TOTAL OUTLETS	TOTAL LIGHTS	AT WHAT POINT CONTROLLED
I	A		1	a b c d	4	8	
II	"	"	1	e f g h i j k	7	7	
III	"	"	1	l m	2	8	
IV	"	"	1	n	1	6	
V	"	"	1	o	1	6	
VI	"	"	1	p q r s t u	6	6	
VII	"	"	1	v w x y	4	8	
VIII	"	"	1	z a'	2	8	
IX	"	"	1	b' c'	2	8	
X	"	"	1	d' e' f'	3	6	
11	"	"	1	g' h' i' j'	4	4	
12	"	"	1	k'	1	8	
13	"	"	1	l' m' n' o' p' q' r'	7	7	
14	"	"	1	s' t'	2	8	
15	"	"	1	u' v'	2	8	
16	"	"	1	w' x'	2	8	
17	"	"	1	y' z'	2	8	
18	"	"	1	a" b"	2	8	
19	"	"	1	c"	1	4	
20	"	"	1	d" e" f" g" h" i"	6	6	
21	"	"	1	j" k"	2	2	
22	"	"	1	l"	1	2	Sat A
					64	146	
23	B		1	m" n"	2	8	Sat B
24	"	"	1	o"	1	8	S " "
25	"	"	1	p" q" r"	3	12	S " "
					6	28	

Fig. 45. Wiring of an Office Building.

Typical Plan of Upper Floors, Showing Circuit Work, Schedule, etc. All the Floors above the Second are Similar to One Another in Plan, Differing Only in Comparatively Unimportant Details of Partitions.



— CABLES. —

NO.	START AT BOX NO.	START AT FLOOR	END AT BOX NO.	END AT FLOOR	NO. OF WIRES	LENGTH IN FEET	INSIDE DIA. OF CONDUIT ALLOWED
1	1	BASMT	3	1 ST	50	172	1"
2	"	"	4	2 ND	"	176	"
3	"	"	4	2 ND	"	188	"
4	"	"	5	3 RD	"	184	"
5	"	"	6	4 TH	"	180	"
6	"	"	7	5 TH	"	184	"
7	"	"	8	6 TH	"	188	"
8	"	"	9	7 TH	"	192	"
9	"	"	10	8 TH	"	196	"
10	"	"	11	9 TH	"	200	"
11	"	"	12	10 TH	"	204	"
12	"	"	2	1 ST	10	172	¾
13	"	"	3	2 ND	"	176	"
14	"	"	4	3 RD	"	184	"
15	"	"	5	4 TH	"	180	"
16	"	"	6	5 TH	"	184	"
17	"	"	7	6 TH	"	188	"
18	"	"	8	7 TH	"	192	"
19	"	"	9	8 TH	"	196	"
20	"	"	10	9 TH	"	200	"
21	"	"	11	10 TH	"	204	"
22	2	1 ST	12	1 ST	"	172	1"
23	"	"	13	"	"	176	"
24	"	"	14	"	"	184	"
25	"	"	15	"	"	180	"
26	"	"	16	"	"	184	"
27	"	"	17	"	"	188	"
28	"	"	18	"	"	192	"
29	"	"	19	"	"	196	"
30	"	"	20	"	"	200	"
31	"	"	21	"	"	204	"
32	3	2 ND	22	2 ND	"	176	"
33	"	"	23	"	"	184	"
34	"	"	24	"	"	180	"
35	"	"	25	"	"	184	"
36	"	"	26	"	"	188	"
37	"	"	27	"	"	192	"
38	"	"	28	"	"	196	"
39	"	"	29	"	"	200	"
40	"	"	30	"	"	204	"
41	"	"	31	"	"	208	"
42	4	3 RD	32	3 RD	"	184	"
43	"	"	33	"	"	180	"
44	"	"	34	"	"	184	"
45	"	"	35	"	"	188	"
46	"	"	36	"	"	192	"
47	"	"	37	"	"	196	"
48	"	"	38	"	"	200	"
49	"	"	39	"	"	204	"
50	"	"	40	"	"	208	"
51	"	"	41	"	"	212	"
52	"	"	42	"	"	216	"
53	"	"	43	"	"	220	"
54	"	"	44	"	"	224	"
55	"	"	45	"	"	228	"
56	"	"	46	"	"	232	"
57	"	"	47	"	"	236	"
58	"	"	48	"	"	240	"
59	"	"	49	"	"	244	"
60	"	"	50	"	"	248	"
61	5	4 TH	51	4 TH	"	184	"
62	"	"	52	"	"	180	"
63	"	"	53	"	"	184	"
64	"	"	54	"	"	188	"
65	"	"	55	"	"	192	"
66	"	"	56	"	"	196	"
67	"	"	57	"	"	200	"
68	"	"	58	"	"	204	"
69	"	"	59	"	"	208	"
70	"	"	60	"	"	212	"
71	6	5 TH	61	5 TH	"	188	"
72	"	"	62	"	"	184	"
73	"	"	63	"	"	188	"
74	"	"	64	"	"	192	"
75	"	"	65	"	"	196	"
76	"	"	66	"	"	200	"
77	"	"	67	"	"	204	"
78	"	"	68	"	"	208	"

* EMPTY CONDUIT ONLY

— BOXES. —

NO.	FLOOR	NO. REQUIRED OF VARIOUS SIZES 60 F	1-A	14-B	16-B	20-B	2-D	3-A			
1	BASMT	1									
2	1 ST		1	1							
3	2 ND		1	1							
4	3 RD		1	1							
5	4 TH		1	1							
6	5 TH		1	1							
7	6 TH		1	1							
8	7 TH		1	1							
9	8 TH		1	1							
10	9 TH		1	1							
11	10 TH		1	1							
12	1 ST				1						
13	"				1						
14	"				1						
15	2 ND				1						
16	"				1						
17	"				1						
18	3 RD				1						
19	"				1						
20	"				1						
21	4 TH				1						
22	"				1						
23	"				1						
24	5 TH				1						
25	"				1						
26	"				1						
27	6 TH				1						
28	"				1						
29	"				1						
30	7 TH				1						
31	"				1						
32	"				1						
33	8 TH				1						
34	"				1						
35	"				1						
36	9 TH				1						
37	"				1						
38	"				1						
39	10 TH				1						
40	"				1						
41	"				1						
42	"				1						
43	"				1						
44	"				1						
45	"				1						
46	"				1						
47	"				1						
48	"				1						
TOTALS		1	9	6	31	1	2	1			

— FIXTURES. —

LOCATION	BATTERIES	BATTERY CABINET	CLOCKS	MASTER CLOCK							
BASEMENT	28	1									
1 ST F.											
2 ND "											
3 RD "											
4 TH "											
5 TH "											
6 TH "											
7 TH "											
8 TH "											
9 TH "											
10 TH "											
ATTIC			3								
TOTALS	28	1	15	1							

SECTION OF INTERCONNECTION BOX FOR TICKERS, MESSENGER CALLS, ETC.

SECTION OF INTERCONNECTION BOX FOR TELEPHONES, BELL CALLS, ETC.

Fig. 46. Wiring of an Office Building. Diagram of the Interconnection System.

basement; adjoining this main box is located the terminal box of the local telephone company. A separate system of feeders is provided for the ticker system, as these conductors require somewhat heavier insulation, and it was thought inadvisable to place them in the same conduits with the telephone wires, owing to the higher potential of ticker circuits. A separate interconnection cable runs to each floor, for telephone and messenger call purposes; and a central box is placed near the rising point at each floor, from which run subsidiary cables to several points symmetrically located on the various floors. From these subsidiary boxes, wires can be run to the various offices requiring telephone or other service. Small pipes are provided to serve as raceways from office to office, so as to avoid cutting partitions. In this way, wires can be quickly provided for any office in the building without damaging the building in any way whatever; and, as provision is made for a special wooden moulding near the ceiling to accommodate these wires, they can be run around the room without disfiguring the walls. All the main cables and subsidiary wires are connected with special interconnection blocks numbered serially; and a schedule is provided in the main interconnection box in the basement, which enables any wire originating thereat, to be readily and conveniently traced throughout the building. All the main cables and subsidiary cables are run in iron conduits.

OUTLET-BOXES, CUT-OUT PANELS, AND OTHER ACCESSORIES

Outlet-Boxes. Before the introduction of iron conduits, outlet-boxes were considered unnecessary, and with a few exceptions were not used, the conduits being brought to the outlet and cut off after the walls and ceilings were plastered. With the introduction of iron conduits, however, the necessity for outlet-boxes was realized; and the *Rules* of the Fire Underwriters were modified so as to require their use. The *Rules of the National Electric Code* now require outlet-boxes to be used with rigid iron and flexible steel conduits, and with armored cables. A portion of the rule requiring their use is as follows:

All interior conduits and armored cables "must be equipped at every outlet with an approved outlet-box or plate.

"Outlet-plates must not be used where it is practicable to install outlet-boxes.

"In buildings already constructed, where the conditions are such that neither outlet-box nor plate can be installed, these appliances may be omitted by special permission of the inspection department having jurisdiction, providing the conduit ends are bushed and secured."

Fig. 47 shows a typical form of outlet-box for bracket or ceiling outlets of the *universal type.* When it is desired to make an opening for the conduits, a blow from a hammer will remove any of the weakened portion of the wall of the outlet-box, as may be required. This form of outlet-box is frequently referred to as the *knock-out type.* Other forms of outlet-boxes are made with the openings cast in the box at the required points, this class being usually stronger and better made than the universal type. The advantages of the universal type of outlet-box are that one form of box will serve for any ordinary conditions, the openings being made according to the number of conduits and the directions in which they enter the box.



Fig. 47. Universal and Knock-Out Type of Outlet Box.

Fig. 48 shows a waterproof form of outlet-box used out of doors, or in other places where the conditions require the use of a water-tight and waterproof outlet-box.

It will be seen in this case, that the box is threaded for the conduits, and that the cover is screwed on tightly and a flange provided for a rubber gasket.



Fig. 48. Water-Tight Outlet Box.
Courtesy of H. Krantz Manufacturing Co., Brooklyn, N. Y.

Figs. 49 and 50 show water-tight floor boxes which are for outlets located in the floor. While the rules do not require that the floor outlet-box shall be water-tight, it is strongly recommended that a water-tight outlet be used in all cases for floor connections. In this case also, the conduit opening is threaded, as well as the stem cover through which the extension is made in the conduit to the desk or table. When the floor outlet connection is not required, the stem cover may be removed and a flat, blank cover be used to replace the same.

A form of outlet-box used for flexible steel cables and steel armored cable, has already been shown (see Fig. 5).

There is hardly any limit to the number and variety of makes of outlet-boxes on the market, adapted for ordinary and for special con-



Fig. 49.



Fig. 50.

Types of Floor Outlet-Boxes.

ditions; but the types illustrated in these pages are characteristic and typical forms.

Bushings. The *Rules of the National Electric Code* require that conduits entering junction-boxes, outlet-boxes, or cut-out cabinets shall be provided with approved *bushings*, fitted to protect the wire from abrasion.

Fig. 51 shows a typical form of conduit bushing. This bushing is screwed on the end of the conduit after the latter has been introduced into the outlet-box, cut-out cabinet, etc., thereby forming an insulated orifice to protect the wire at the point where it leaves the conduits, and to prevent abrasion, grounds, short circuits, etc. A lock-nut (Fig. 52) is screwed on the threaded end of the conduit before the conduit is placed in the outlet-box or cut-out cabinet, and this lock-nut and bushing clamp the conduit securely in position. Fig.

53 shows a terminal bushing for panel-boxes used for flexible steel conduit or armored cable.

The *Rules of the National Electric Code* require that the metal of conduits shall be permanently and effectually grounded, so as to insure a positive connection for grounds or leaking currents, and in order to provide a path of least resistance to prevent the current from finding a path through any source which might cause a fire. At outlet-boxes, the conduits and gaspipes must be fastened in such a manner as to insure good electrical connection; and at centers of distribution, the conduits should be joined by suitable bond wires, preferably of copper, the said bond wires being connected to the metal structure of the building, or, in case of a building not having an iron or steel structure, being grounded in a permanent manner to water or gas piping.



Fig. 51. Conduit Bushing.



Fig. 52. Lock-Nut.

Fuse-Boxes, Cut-Out Panels, etc. From the very outset, the necessity was apparent of having a protective device in circuit with the conductor to protect it from overload, short circuits, etc. For this purpose, a fusible metal having a low melting point was employed. The form of this fuse has varied greatly. Fig. 54 shows a characteristic form of what is known as the *link fuse* with copper terminals, on which are stamped the capacity of the fuse.



Fig. 53. Panel-Box Terminal Bushing.
Courtesy of Sprague Electric Co., New York, N. Y.

The form of fuse used probably to a greater extent than any other, although it is now being superseded by other more modern forms,

is that known as the *Edison fuse-plug*, shown in Fig. 55. A porcelain *cut-out block* used with the Edison fuse is shown in Fig. 56.

Within the last four or five years, a new form of fuse, known as the *enclosed fuse*, has been introduced and used to a considerable



Fig. 54. Copper-Tipped Fuse Link.

Fig. 55. Edison Fuse-Plug,
Courtesy of General Electric Co., Schenectady, N. Y.

extent. A fuse of this type is shown in Fig. 57. Fig. 58 gives a sectional view of this fuse, showing the porous filling surrounding the fuse-strips, and also the device for indicating when the fuse has blown. This form of fuse is made with various kinds of terminals; it can be used with spring clips in small sizes, and with a post screw contact in larger sizes. For ordinary low potentials this fuse is desirable for currents up to 25 amperes; but it is a debatable question whether it is desirable to use an enclosed fuse for heavier currents. Fig. 59 shows a *cut-out box* with Edison plug fuse-blocks used with knob and tube wiring. It will be seen that there is no connection compartment in this fuse-box, as the circuits enter directly opposite the terminals with which they connect.



Fig. 56. Porcelain Cut-Out Block.
Courtesy of General Electric Co., Schenectady, N. Y.

Fig. 60 shows a *cut-out panel* adapted for enclosed fuses, and installed in a cabinet having a connection compartment. As will be seen from the cut, the tablet itself is surrounded on the four sides by slate, which is secured in the corners by angle-irons. The outer box may be of wood lined with sheet iron, or it may be of iron. Fig. 61 shows a door and trim for a cabinet of this type. It will be seen that



Fig. 57. Enclosed or "Cartridge" Fuse.



Fig. 58. Section of Enclosed Fuse.

the door opens only on the center panel, and that the trim covers and conceals the connection compartment. The inner side of the door should be lined with slate, and the inner side of the trim should be lined with sheet iron. Fig. 62 shows a sectional view of the cabinet and panel. In this type of cabinet, the conduits may enter at any point, the wires being run to the proper connectors in the connection compartment.



Fig. 59. Porcelain Cut-Outs in Wooden Box.
Courtesy of H. T. Paiste Co., Philadelphia, Pa.

Figs. 63 and 64 illustrate a type of panelboard and cabinet having a push-button switch connected with each branch circuit and so arranged that the cut-out panel itself may be enclosed by locked doors, and access to the switches may be obtained through two separate doors provided with latches only. This type of panel was arranged and designed by the author of this instruction paper.

OVERHEAD LINEWORK

The advantages of overhead linework as compared with underground linework are that it is much less expensive; it is more readily and more quickly installed; and it can be more readily inspected and repaired.

Its principal disadvantages are that it is not so permanent as underground linework; it is more easily deranged; and it is more unsightly.

For large cities, and in congested districts, overhead linework should not be used. However, the question of first cost, the question of permanence, and the municipal regulations, are usually the factors which determine whether overhead or underground linework shall be used.

The principal factors to be considered in overhead linework will be briefly outlined.

Placing of Poles. As a general rule, the poles should be set from 100 to 125 feet apart, which is equivalent to 53 to 42 poles per mile. Under certain conditions, these spacings given will have to be modified; but if the poles are spaced too far apart, there is danger of too great a strain on the poles themselves, and on the cross-arms, pins, and



Fig. 60. Plan View, Cover, and Section of Double Cut-Out Box.



Fig. 61.



Fig. 62.

conductors. If, on the other hand, they are placed too close together, the cost is unnecessarily increased. The size and number of conductors, and the potential of the linework, determine to a great extent the distance between the poles; the smaller the size, the less the number of conductors; and the lower the potential, the greater the distance between the poles may be made. Of course, the exact location of the poles is subject to variation because of trees, buildings, or other obstructions. The usual method employed in locating poles, is first to make a map on a fairly large scale, showing the course of the linework, and then to locate the poles on the ground according to the actual conditions.

Poles. Poles should be of selected quality of chestnut or cedar, and should be sound and free from cracks, knots, or other flaws. Experience has proven that chestnut and cedar poles are the most durable and best fitted for linework. If neither chestnut nor cedar poles can be obtained, northern pine may be used, and even other timber in localities where these poles cannot be obtained; but it is found that the other woods do not last so long as those mentioned,



Fig. 68. Cut-Out Panel with Push-Button Switches. Cover Removed.

and some of the other woods are not only less strong initially, but are apt to rot much quicker at the "wind and water line"—that is, just above and below the surface of the ground.

The proper height of pole to be used depends upon conditions. In country and suburban districts, a pole of 25 to 30 feet is usually of sufficient height, unless there are more than two or three cross-arms required. In more densely populated districts and in cities where a great number of cross-arms are required, the poles may have to be

40 to 60 feet, or even longer. Of course, the longer the pole, the greater the possibility of its breaking or bending; and as the length increases, the diameter of the butt end of pole should also increase. Table X gives the average diameters required for various heights of poles, and the depth the poles should be placed in the ground. These data have been compiled from a number of standard specifications.

TABLE X

Pole Data

Length of Pole	Diameter 6 In. from Butt	Diameter at Top	Depth Pole should be Placed in Ground
25 feet	9 to 10 in.	6 to 8 in.	5 feet
30 "	11 "	"	5½ "
35 "	12 "	"	5½ "
40 "	13 "	"	6 "
45 "	14 "	"	6½ "
50 "	15 "	"	7 "
55 "	16 to 17 "	"	7½ "
60 "	18 "	"	7½ "
65 "	19 "	"	8 "
70 "	20 "	"	8 "
75 "	21 "	"	8½ "
80 "	22 "	"	9 "

As it is somewhat difficult, because of irregularities in size, to measure the diameter of some poles, the circumference may be measured instead: then, by multiplying the diameters given in the above table, by 3.1416, the measurements may be reduced to the circumference in inches.

The minimum diameters of the pole at the top, which should be allowed, will depend largely on the size of the conductors used, and on the potential carried by the circuits; the larger the conductors and the higher the potentials, the greater should be the diameter at the top of the pole.

Poles should be shaved, housed, and gained, also cleaned and ready for painting, before erection.

Poles should usually be painted, not only for the sake of appearance, but also in order to preserve them from the weather. It is particularly important that they should be protected at their butt end, not only where they are surrounded by the ground, but for a foot or two above the ground, as it is at this point that poles usually deteriorate most rapidly. Painting is not so satisfactory at this point as the use of tar, pitch, or creosote. The life of the pole can be increased considerably by treating it with one or another of these preservatives.

Before any poles are erected, they should be closely inspected for flaws and for crookedness or too great departure from a straight line.

Where appearance is of considerable importance, octagonal poles may be used, although these cost considerably more than round poles. *Gains* or notches for the cross-arms should be cut in the poles before they are erected, and should be cut square with the axis of the pole, and so that the cross-arms will fit snugly and tightly within the space thus provided. These gains should be not less than 4½ inches wide,



Fig. 64. Cut-Out Panel with Push-Button Switches. With Cover.

nor less than ½ inch deep. Gains should not be placed closer than 24 inches between centers, and the top gains should be at least 9 inches from the apex of the pole.

Pole Guying. Where poles are subject to peculiar strains due to unusual stress of the wires, such as at corners, etc., *guys* should be employed to counteract the strain and to prevent the pole from being bent and finally broken, or from being pulled from its proper position.

Where there are a considerable number of wires on the poles, or in case of unusually long poles, or where the linework is subject to severe storms, it is frequently necessary to guy the poles even on straight linework. In such cases, the guys should extend from a point near the top of the pole to a point near the butt of the adjacent pole. Straight guying should also be employed at the terminal pole, the guy extending to a stub beyond the last pole, to counteract the strain of the wires pulling in the opposite direction. On particularly heavy lines, it is sometimes necessary to use straight guys for the second and even the third pole from the terminal pole, to prevent undue strain on the terminal pole itself, as shown in Fig. 65.



Fig. 65. Use of Straight Guys on Poles at Terminus of Heavy Line.

Where there are three or more cross-arms, either two sets of guys should be employed, or else a "Y" form of guy should be used. If a single guy is used on a long pole or on a pole carrying a number of cross-arms, or on which there is unusual strain, the pole is apt to break where the guy is attached. Figs. 66 and 67 show respectively a proper and an improper method of guying, and their effect.

At corners, or wherever the direction of the linework changes, guys should be provided to counteract the strain due to the change in direction. Guys are also necessary at points where poles are set in other than a vertical position.

Where the soil is not firm or solid, or where poles are subject to unusual stress, it is sometimes necessary to obtain additional stiffness by what is known as *crib-bracing*, as may be seen from Fig. 68. This consists of placing two short logs at the butt of the pole. These logs need not be more than 4 to 5 feet long, or more than 8 to 9 inches



Fig. 66. Proper Method of Guying where there are Three or More Cross-Arms. A Y-form of Guy is Used at Left; Double Guy at Right.

in diameter. This crib-bracing is sometimes also necessary to give greater stability to stubs or short poles to which guys are fastened.

While, as a rule, it is not advisable to use trees for guy supports, it is sometimes necessary to do this, but the trees should be sound and should be protected in a proper manner from injury. On private property, permission should first be obtained from the owner to use the tree for such purpose.

The guy itself should be of standard cable, consisting of 7 strands of No. 12 B. & S. Gauge iron or steel wire. This is the standard *guy cable*, and should be used in all cases, except for very light poles and light linework, where a smaller cable having a minimum diameter of $\frac{1}{4}$ inch may be used. The guy wires should be fastened at the ends by means of suitable clamps. All guy cables and clamps should be heavily galvanized, to prevent rusting.

Corners. In cases of heavy linework where there are a considerable number of wires and cross-arms, the turns should be made,



Fig. 67. Improper Method of Guying where there are Three or More Cross-Arms. Strain is Concentrated at one Point, Causing Rupture of Pole.

if possible, by the use of two poles. In cases where there are only a few wires, a double cross-arm may be employed, using a single pole. The two methods are illustrated in Figs. 69 and 70.



Fig. 68. Additional Stiffness Secured by Use of Crib-Bracing.

Cross-Arms. Cross-arms, where possible, should be of long leaf yellow pine, or of Oregon or Washington fir, of sound wood,

thoroughly seasoned and free from sap, cracks, or large knots. They should be not less than 3½ inches thick by 4½ inches deep, the length depending upon the number of pins required.

Cross-arms, after being properly seasoned, should be painted with two coats of lead paint before erection. They should then be snugly fitted into the gain of the pole, and securely fastened with a bolt not less than ⅝ inch in diameter driven through a hole of slightly less diameter previously bored in the pole. A galvanized-iron washer not less than 2 inches in diameter should be placed under the head and nut of each bolt. The cross-arms should be at right angles to the pole, and should be parallel to one another where two or more arms are used on the same pole.



Fig. 69. Two-Poles Used in Making Turn on Heavy Line.

The cross-arms should be braced with galvanized-iron *braces* approximately 1¼ inches wide, ¼ inch thick, and from 18 to 30 inches in length. The braces should be fastened to the cross-arm by means of ⅜-inch galvanized-iron bolts passing through the brace and the cross-arm, washers being used under the nut and head of each bolt. Guys should be provided for the cross-arms in case of unusual strain. The dimensions of cross-arms required for various numbers of pins, are given very completely in a

paper read by Mr. Paul Spencer before the Atlantic City Convention of the National Electric Light Association in 1906, and reprinted in a number of the technical journals.

Wherever practicable, cross-arms should be placed on the poles before the poles are erected, as not only can they be more securely fastened when the poles are on the ground, but the cost of erection is thereby considerably reduced.

Pins. Pins should be of selected locust, not less than $1\frac{1}{2}$ inches in diameter at the shank portion, and not less than $\frac{3}{4}$ inch in diameter at the point where they rest upon the cross-arm. For potentials of 20,000 volts or over, the pins should be of metal, to avoid carbonization of the wood due to static leakage. The top portion of the pin (if of wood) should be not less than one inch in diameter. The length of both the shank and the upper portion should be each approximately $4\frac{1}{2}$ inches, making the total length approximately 9 inches. The pin should be threaded and tapered, and accurately cut. The pin should fit the hole in the cross-arm snugly, and should be nailed to the cross-arm with a sixpenny galvanized-iron wire nail driven straight through the center of the shank of the pin.



Fig. 70. Double Cross-Arm Used on Single Pole to Make Turn in Heavy Line Carrying Only a Few Wires.

Insulators. For potentials of 3,000 volts or less, insulators should be of flint glass, of double-petticoat, deep-grooved type. For potentials of over 3,000 volts, they should be of the triple-petticoat type, and preferably of porcelain, and should be of special pattern adapted for the potential.

Service Mains, Pole Wiring, etc. For service connections—

that is, for the mains run to service switches in consumers' residences or other buildings, conductors of not less than No. 8 B. & S. Gauge should be used in order to obtain the necessary tensile strength. Where possible, the circuits should be arranged in such a manner as to have the service main connect with the line on the lowest cross-arm, in order to prevent crossing of wires. The transformers should be installed either on poles or in vaults outside of the building, or, where this is impracticable, in a fireproof vault or other enclosed space inside of the building itself. Small transformers may be fastened to a pair of cross-arms secured to the pole itself. For transformers of 25 K.W. and over, it is usually best to provide special poles. It is inadvisable to place transformers on building walls.

Where appearance is of importance, when the transformer is placed underground, or when the wires enter the lower portion of a building, the conductors must be run underground. In such cases, a splice should be made between the weatherproof conductors and rubber-insulated lead-sheathed conductors, at a height of about 15 to 20 feet above the ground, and the mains run in iron pipe down the pole to a point underground, where they may be continued either in iron pipe or in vitrified or fiber conduits underground to the point of entrance.

All circuit wiring on poles should be so arranged as to leave one side free for the linemen to climb the poles without injuring the conductors. As a rule, all poles on which transformers, lightning arresters, or fuse-boxes are located, should be provided with steps.

In order to limit the area of disturbance of a short circuit or overload, fuses should be inserted in each leg of a primary circuit in making connections to transformers, or where tap or branch connections are made. The fuses should have a capacity of approximately 50 per cent greater than the transformer or conductor which they protect. Of course, it would be undesirable to have an excessive number of fuses, and for short branch lines they might frequently be undesirable; but for important branch lines, they should be employed in order to prevent the fuse on the main feeder from being *blown* in case of disturbance on the branch line.

Lightning arresters should be placed on the linework in places particularly exposed to lightning discharges, and at all points where connections are made to enter a building. The location and number

of lightning arresters will depend upon local conditions, the likelihood and frequency of thunderstorms, etc. Where lightning arresters are provided, it is essential that a good ground connection be obtained. The ground connection should be made by a fairly good-sized insulated rubber conductor, not less than No. 6 B. & S. Gauge, connecting either with a water pipe to which it should be clamped, or fastened in such a manner as to obtain a good electric contact, or else to a ground-plate of copper embedded in crushed charcoal or coke.



Fig. 71. Method of Wiring to and Supporting Lamp on Pole.

The neutral wire of a three-wire of both secondary alternating-current systems and direct-current systems, should be properly grounded as required by the *National Electric Code* (see Rules 12, 13, and 13-A).

Lamps on Poles. Fig. 71 shows the method of wiring to and supporting a lamp located on a pole.

UNDERGROUND LINEWORK

In large cities, or in congested districts, or where the appearance of overhead linework is objectionable, it is generally necessary to place the conductors underground instead of overhead.

The advantages of underground linework are—*first*, that of appearance; *second*, it is more permanent and less liable to interruption than overhead work.

The principal disadvantage of underground work is the greater first cost. In overhead linework, conductors having weatherproof insulators consisting of cotton dipped in a special compound similar to pitch, are used, the cost of which is relatively small. For underground linework, however, the conductors must not only have rubber insulation, but also a lead sheathing for mechanical protection.

Furthermore, the cost of the ducts, trenching, concrete work, laying the ducts, etc., is much greater than the cost of poles, cross-arms, etc.

As in the case of inside wiring, underground linework should be so arranged that the conductors may be readily removed and replaced without disturbing the underground conduits or ducts. The system should be arranged with *manholes*, and in such a manner that changes or additions or branches may be readily and conveniently made. In order to provide for the removal and replacing of conductors, and also for growth in the system, the method formerly in vogue, of embedding the conductors in wooden boxes, or in trenches underground, has been abandoned; and the conductors are now placed in *conduits* or *ducts*. A number of different forms of ducts and conduits have been introduced, some of which have been dropped as cheaper and better forms have been introduced. The forms of conduits or ducts now most generally employed include *iron pipe*, *vitrified conduits*, and *fibre conduit*. As all three of these forms of conduit are very generally employed, they will now be described, as well as the method of installing them.

Iron Pipe. Three-inch iron conduit is frequently used for underground linework, particularly for short runs or where there are not more than two or three ducts required, or where the soil is bad and where the longer lengths and more stable joints of the iron conduit would make it more desirable than vitrified duct or fibre conduit. This conduit, however, is generally undesirable on account of its greater first cost, and also on account of its liability to deterioration from rust or corrosion. Where iron conduit is used, and where it is subject to corrosion, it should be coated with asphaltum or other similar protective composition. While it is not necessary to have a concrete bed under iron pipe, it is better to provide such a bed, especially where the soil is shifting or not solid.

Vitrified Tile Conduit. This type of conduit in both the single- and multiple-duct form, is used more extensively than any other form of conduit for underground work. It is made in lengths of 18 inches for the single-duct form, and in considerably greater lengths in the multiple-duct form. Fig. 72 shows the single-duct conduit, and Fig. 73 shows a multiple-duct form of conduit.

Vitrified conduit requires less space for the same number of ducts than any other form, and is particularly desirable where a great

number of ducts are required in a small space. The advantages of this form of conduit are that it is cheap in first cost; after being laid, it is practically indestructible; it is not subject to corrosion or

Fig. 72. Self-Centering Duct, Vitrified Conduit.
Courtesy of Standard Vitrified Conduit Co., New York, N. Y.



Fig. 73. Multiple Duct, Vitrified Conduit.
Courtesy of Standard Vitrified Conduit Co., New York, N. Y.

deterioration; it is not combustible; it is fairly strong mechanically; and it does not require skilled labor to install.

Table XI gives the principal data of one of the well-known makes of vitrified conduit.

TABLE XI

Standard Vitrified Conduit

Style of Conduit	Dimension of Square Duct (Inches)	Dimension of Round Duct (Inches)	Outside Dimensions of End Section (In.)	Reg. Stock Lengths (Inches)	Short Lengths (Inches)	Approx. Weight per Duct (Foot)
2-duct multiple...	3⅜ sq.	3¼	5 x 9	24	6, 9, 12	8 lbs.
3-duct multiple...	3⅜ sq.	3¼	5 x 13	24	6, 9, 12	8 "
4-duct multiple...	3⅜ sq.	3¼	9 x 9	36	6, 9, 12	8 "
6-duct multiple...	3⅜ sq.	3¼	9 x 13	36	6, 9, 12	8 "
9-duct multiple...	3⅜ sq.	3¼	13 x 13	36	6, 9, 12	8 "
Common single duct		3⅜	5 x 5	18	6, 9, 12	8 "
Single duct, self-centering.....		3⅜	5 x 5	18	6, 9, 12	10 "
Round single duct, self-centering...		3¼	5 in. round	18	6, 9, 12	10 "

In installing vitrified conduit, a trench following as straight lines as possible should be dug to such a depth that there will be a space of at least 18 inches from the top layer of the duct to the street surface. The bottom of the trench should be level; and a bed of good cement concrete not less than 3 inches thick should be laid. The following instructions* for installing vitrified conduit may be considered as typical of the best up-to-date practice:

*From the Catalogue of the Standard Underground Conduit Company.

Laying of Conduit. When the trench has been properly prepared and the concrete foundation set, the laying of conduit should be begun. The ends of the conduit should be butted against the shoulder of the conduit terminal brick; short length should be used for the breaking of joints.

Care should be taken, when each length of conduit is laid, that the duct hole is perfectly clear and the conduit level. The work may then proceed; and if the following instructions are carried out, no difficulty will be encountered after the duct are laid.

When the first piece of conduit is laid and the keys inserted, one on the top and one on the side of the duct, the burlap for joints should be slipped partly under the conduit, and the next piece brought up and connected. The burlap is then brought up and wrapped around the conduit. After this operation is completed, a thin layer of cement mortar is plastered around the burlap, extending over the edges, so as to cover the scarified portion of the conduit so that it may adhere to it, thus making the joint practically water-tight.

The burlap should be first prepared in strips of not less than 6 inches in width, and of suitable length to wrap around the conduit, overlapping about 6 inches. If possible, the burlap should be saturated in asphaltum or pitch; but if this is not convenient, it may be dipped in water so as to stick to the conduit until the joint has been cemented. The engineer or foreman in charge should personally oversee the making of the joint, and especially see that the keys are inserted, as in many instances they are left out by the workmen, causing considerable trouble and expense. Sufficient time should be allowed for the joints to harden.

After the duct are laid, the sides are filled in with either concrete or dirt, as specified, care being taken that the conduit are not forced out of alignment by the careless filling-in of the sides. The top layer of concrete may then be laid and leveled.

After this the trench is ready for filling in.

In the laying of our self-centering single-duct conduit, no dowel-pins are used, the ducts being self-centering—one piece of conduit socketing into the other. Burlaping and cementing of joint is not necessary. Otherwise the instructions for the laying of multiple-duct should be followed. The use of a mandrel in laying self-centering conduit is superfluous.

As each section of the system—that is, from manhole to manhole—is completed, it should be rodded to insure the duct being clear. For this purpose wooden rods are employed, the rods being from 3 to 4 feet long by one inch in diameter and provided with brass couplings on the ends. The first rod is pushed into the duct chamber, the second one is then attached, and then the third and so on, until the first rod appears in the manhole at the opposite end.

A wooden mandrel about 10 inches long, made to conform to the shape of the duct, but about $\frac{1}{4}$ inch smaller in diameter, is attached to the last rod, and a galvanized-iron wire is then attached to the other end of the mandrel. The rods are drawn through the duct and uncoupled, until the mandrel has passed through the ducts. The wire is left remaining in the chamber, and secured in the manhole to prevent its being pulled out. The same operation is repeated until all the ducts are tested and wired. Should obstructions be met with and the mandrel bind, the location of the obstructions can readily be ascertained from the length of rod yet remaining in the duct, and can easily be removed. This method is far better than pulling the mandrel through as the ducts are laid, as in many cases the duct is obstructed or thrown out of alignment by the filling-in of the concrete or trench, and this would not be noticed until an attempt was made to draw the cable. The wire left in the duct is used in drawing the cables.

Fibre Conduit. This type of conduit consists of wood fibre formed into a tube over a mandrel under pressure. After the tube

Fig. 74. Socket-Joint Fibre Conduit.

is formed on the mandrel, it is removed, and, after being dried in air, is placed in a tank of preservative and insulating compound.

Fibre conduits are made in three different styles—namely, the *socket-joint*, *sleeve-joint*, and *screw-joint* types, shown respectively in Figs. 74, 75, and 76. The forms of conduit here shown are made by the Fibre Conduit Company, of Orangeburg, New York.

In the socket-joint type, the connections between the lengths

of conduit are made by means of male and female joints turned on the ends of the conduit so that it is necessary only to push one length within the other to secure alignment without the use of a sleeve-coupling or other device. While this is the cheapest and simplest

Fig. 75. Sleeve-Joint Fibre Conduit.

form of fibre conduit, the joint is not so secure as in either of the other two types.

The sleeve-joint fibre conduit has the ends of each joint turned so that a sleeve may be slipped over the turned portion and butted up against the shoulder on the tubes. These sleeves are about 4 inches long and $\frac{3}{8}$ inch thick. While this form of joint is more secure than the socket type, it is not so secure as the screw-joint type.

The screw-joint type of fibre conduit is manufactured with a slightly thicker wall than the socket-joint type, in order to obtain the necessary thickness for getting the thread on the end of the pipe. The sleeve in this case is threaded; and, instead of being slipped on the conduit, as in the case of the sleeve-joint type, it is screwed on, and the thread may be filled with compound and a water-tight joint thereby obtained. Various special forms of elbows, bends, junction-boxes, tees, etc., are provided for this conduit, for special connections. Couplings are also made so that joints can be made between fibre conduit and iron pipe, where it is desirable to make such a connection.

The advantages of fibre conduit are—*first*, that it is lighter than any of the other forms of conduit, which reduces the cost of trans-

Fig. 76. Screw-Joint Fibre Conduit.

portation, carting, and handling; and *second*, that the cost of labor for installing it is less than in the case of iron pipe, and less than that of the single-duct tile pipe. Table XII gives the principal data relating to fibre conduit.

TABLE XII
Fibre Conduit

Inside Diameter (Inches)	Type of Conduit	Length (Feet)	Thickness of Wall (Inches)	Approx. Weight per Foot (lbs.)
1	Socket-joint	2-½	¼	0.50
1½	" "	5	¼	0.70
2	" "	5	¼	0.85
2½	" "	5	¼	1.02
3	" "	5	¼	1.20
3½	" "	5	¼	1.40
4	" "	5	¼	1.60
1½	Sleeve-joint	5	¼	0.80
2	" "	5	¼	0.95
2½	" "	5	¼	1.15
3	" "	5	7/16	2.40
3½	" "	5	7/16	2.90
4	" "	5	½	3.33
1½	Screw-joint	5	5/16	1.00
2	" "	5	⅜	1.45
2½	" "	5	⅜	1.75
3	" "	5	7/16	2.40
3½	" "	5	7/16	2.90
4	" "	5	½	3.33

Fig. 77 shows the method of laying fibre conduit in a trench.

A concrete bed should be provided for all three types of fibre conduit. Where the ground is moist or where there is likelihood of water getting in the joints, it is advisable to make a complete envelope around the conduit.

The joints should be carefully dipped in or coated with a special liquid compound provided for this purpose, so as to insure water-tightness. The cables should be spaced about 1½ inches apart, by means of wooden separators; and the spaces between the ducts, and between the walls of the trench and the outer ducts, should be filled with a thin grouting of cement and sand. If more than one horizontal row of ducts are installed, the grouting of each row should be smoothed over so as to prepare a base for the next row of ducts.

To fish the conductors in fibre conduit, it is not necessary to follow the method of rodding usually required with vitrified conduits; but it is found that by utilizing a solid No. 6 iron wire, and fishing from one manhole to the next, the mandrels and brush can be attached to the end of the wire and pulled through the conduits, thus insuring that the joints are smooth and that there are no obstructions in the conduit. To prevent accidental clogging of the ends of the con-

duit, wooden plugs should be installed in the openings of all unfinished conduit work, or in all unoccupied cable ducts at manholes.

Drawing In the Cables. After the conduits have been tested by means of the mandrel to ascertain that they are continuous and that the joints are smooth, the work of installing the cables may be started. Special precaution should be taken to prevent sharp bending of the cables, and thus to prevent injury to the lead sheathing of the rubber insulation. If the cable is light and of small diameter, the distance not over 300 feet, and the run fairly straight, the cable can usually be pulled in by hand; but often other means must be provided so as to secure sufficient power. Precautions should be taken, however, to avoid placing too great a strain on the cables, as it is liable to injure them, and the injuries may not show up immediately, but may cause trouble later. The remedy is to avoid placing the manholes too far apart, and to have the runs as straight as possible; also to properly test the conduits for continuity and smoothness before starting to install the cables. Enough slack should be left in each manhole to allow the cables to pass close to the side walls of the manhole, and to have the centers free and accessible for a man to enter the manhole. Where there are a great number of cables in a manhole, shelves or other supports should be



Fig. 77. Method of Laying Fibre Conduit in Trench.

provided for holding the cables apart and in position. Where two or more conductors are placed in the same duct, they should always be pulled in at the same time, for otherwise the cables last pulled in are apt to injure those already installed.

Manholes. Manholes should be provided about every 300 feet, in order to facilitate the installation of the conductors in the duct. The exact distance between manholes should be determined by conditions; in some cases they should be placed even closer together than the figure given, while in other cases their distance apart might be slightly greater.



Fig. 78. Plan and Sectional Elevation of Standard Form of Manhole Used in New York City.

Manholes are built of concrete or brick, and provided with a cast-iron frame or cover. The manholes may be of square, round, rectangular, or oval section, the last-mentioned form of manhole being probably the best, as it avoids the liability to sharp bends or kinks being made in the cable. The manhole cover may be of the same form as the manhole itself, or it may be of different form; but round or square covers are usually used. Fig. 78 shows a standard form of manhole used in New York City. This manhole is substantially built, and adapted for heavy traffic passing over the cover. For suburban or country work, manholes may be made of lighter construction.

REVIEW QUESTIONS.

PRACTICAL TEST QUESTIONS.

In the foregoing sections of this Cyclopedia numerous illustrative examples are worked out in detail in order to show the application of the various methods and principles. Accompanying these are examples for practice which will aid the reader in fixing the principles in mind.

In the following pages are given a large number of test questions and problems which afford a valuable means of testing the reader's knowledge of the subjects treated. They will be found excellent practice for those preparing for Civil Service Examinations. In some cases numerical answers are given as a further aid in this work.

REVIEW QUESTIONS

ON THE SUBJECT OF

HEATING AND VENTILATION.

PART I.

---

1. What advantage does indirect steam heating have over direct heating? What advantages over furnace heating?

2. What are the causes of heat loss from a building?

3. Why is hot water especially adapted to the warming of dwellings?

4. What proportion of carbonic acid gas is found in outdoor air under ordinary conditions?

5. A room in the N. E. corner of a building of fairly good construction is 18 feet square and 10 feet high; there are 5 single windows, each 3 by 10 feet in size. The walls are of brick 12 inches in thickness. With an inside temperature of 70 degrees, what will be the heat loss per hour in zero weather?

6. State four important points to be noted in the care of a furnace.

7. A grammar school building, constructed in the most thorough manner, has 4 rooms, one in each corner, each being 30 ft. by 30 ft. and 14 ft. high, and seating 50 pupils. The walls are of wooden construction, and the windows make up $\frac{1}{3}$ of the total exposed surface. The basement and attic are warm. How many pounds of coal will be required per hour for both heating and ventilation in zero weather, if 8,000 B. T. U. are utilized from each pound of coal?

8. What two distinct types of furnaces are used? What are the distinguishing features?

9. What is meant by the efficiency of a furnace? What efficiencies are obtained in ordinary practice?

REVIEW QUESTIONS

ON THE SUBJECT OF

HEATING AND VENTILATION.

PART II.

---

1. How would you obtain the sizes of the cold-air and warm-air pipes connecting with indirect heaters in dwelling-house work?

2. What is an aspirating coil, and what is its use?

3. What efficiencies may be allowed for indirect heaters in schoolhouse work? How would you compute the size of an indirect heater for a room in a dwelling-house?

4. How is the size of a direct-indirect radiator computed?

5. A schoolroom on the third floor is to be supplied with 2,400 cubic feet of air per minute. What should be the area of the warm-air supply flue?

6. What is the chief objection to a mixing damper, and how may this be overcome?

7. How many square feet of indirect radiation will be required to warm and ventilate a schoolroom when it is 10 degrees below zero, if the heat loss through walls and windows is 42,000 B. T. U., and the air-supply 120,000 cubic feet per hour?

8. What is the difference in construction oetween a steam radiator and one designed for hot water? Can the steam radiator be used for hot water? State reasons for answer.

9. How may the piping in a hot-water system be arranged so that no air-valves will be required on the radiators?

10. What efficiency is commonly obtained from a direct hot-water radiator? How is this computed?

11. How should the pipes be graded in making the connections with indirect hot-water heaters? Where should the air-valve be placed?

REVIEW QUESTIONS

ON THE SUBJECT OF

HEATING AND VENTILATION.

PART III.

---

1. A main heater contains 1,040 square feet of heating surface made up of wrought-iron pipe, and is used in connection with a fan which delivers 528,000 cubic feet of air per hour. The heater is 20 pipes deep, and has a free area, between the pipes, of 11 square feet. If air is taken at zero, to what temperature will it be raised with steam at 5 pounds' pressure.

2. An 8-foot fan used for schoolhouse ventilation runs at a speed of 124 r. p. m. What horse-power of engine is required? What horse-power would be required if the fan were speeded up to 134.6 r. p. m.?

3. What precaution must be taken in connecting the radiators in tall buildings?

4. Give the size of heater from Table XXXI which will be required to raise 672,000 cubic feet of air per hour, from 10° below zero to 95°, with a steam pressure of 20 pounds. If the air-quantity is raised to 840,000 cubic feet per hour through the same heater, what will be the resulting temperature with all other conditions the same?

5. A fan running at 150 revolutions produces a pressure of $\frac{1}{2}$ ounce. If the speed is increased to 210 revolutions, what will be the resulting pressure?

6. A certain fan is delivering 12,000 cubic feet of air per minute, at a speed of 200 revolutions. It is desired to increase the amount to 18,000 cubic feet. What will be the required speed? If the original power required to run the fan was 4 H. P., what will be the final power due to the increased speed?

7. What size fan will be required to supply a schoolhouse

having 300 pupils, if each is to be provided with 3,000 cubic feet of air per hour? What speed of fan will be required, and what H. P. of engine?

8. What advantages has the plenum method of ventilation over the exhaust method?

9. A church is to be warmed and ventilated by means of a fan and heater. The air-supply is to be 300,000 cubic feet per hour. The heat loss through walls and windows is 200,000 B. T. U., when it is zero. How many square feet of heating surface will be required, and how many rows of pipe deep must the heater be, with steam at 5 pounds' pressure?

10. A schoolhouse requiring 600,000 cubic feet of air per hour is to be supplied with a cast-iron sectional heater of the pin type. How many square feet of radiating surface will be required to raise the air from 10° below zero to 70° above, with a steam pressure of 10 pounds?

11. What velocities of air-flow in the main duct and branches are commonly used in connection with a fan system?

12. A main heater is to be designed for use in connection with a fan. How many square feet of radiation will be required to warm 1,000,000 cubic feet of air per hour, from a temperature of 10° below zero to 70° above, with a steam pressure of 5 pounds and a velocity of 800 feet per minute between the pipes of the heater? How many rows of pipe deep must the heater be?

13. State in a brief manner the essential parts of a system of automatic temperature control.

14. What advantage does an indirect steam-heating system have over furnace heating in schoolhouse work?

15. The air in a restaurant kitchen is to be changed every 10 minutes by means of a disc fan. The room is 60 by 30 by 10 feet. Give size and speed of fan, and H. P. of motor.

16. What forms of heating are best adapted to the warming of apartment houses?

17. Give an approximate method for finding the heating surface required for greenhouses, both for steam and hot water.

18. How does the cost of electric heating compare with that by steam and hot water?

19. Describe briefly the construction of an electric heater, and the principle upon which it works.

REVIEW QUESTIONS

ON THE SUBJECT OF

STEAM AND HOT WATER FITTING.

1. What points should be borne in mind when selecting a heating boiler for a given service?

2. Explain by an example how to check the catalogue rating of a boiler.

3. Point out the difference between (a) direct, (b) direct-indirect, and (c) indirect radiation.

4. State the advantages of each type.

5. What advantages do overhead coils possess over other classes of direct radiation?

6. (a) With overhead coil heating, how should the coils be placed with reference to walls and floor to secure the best results? (b) Why?

7. In what two ways is heat given off by a radiator?

8. What advantages has a wet return system over one with dry returns?

9. (a) In what classes of buildings, as a rule, may the overhead feed system be used and why? (b) What advantages are possessed over the up-feed system?

10. When should a two-pipe system be used in preference to a one-pipe?

11. Explain the action of a siphon trap in balancing a low pressure steam heating system.

12. When is it advisable to establish an artificial water line?

13. Explain in detail how to compute the radiating surface for low pressure steam in a corner room 18 ft. square, 10 ft. high, the exposed wall to be 16 in. thick, exposed toward the north and west, and having glass surface equal to one-fourth the total exposed surface of wall and glass combined.

REVIEW QUESTIONS

ON THE SUBJECT OF

ELECTRIC WIRING

1. Explain the three-wire system of wiring.

2. In case a test shows excessive leakage, or a ground or short circuit, how would you locate the trouble and remedy it?

3. Describe the construction and use of outlet-boxes.

4. What is the principal difference between alternating and direct-current circuits, so far as concerns the wiring system?

5. Compare the advantages of the two-wire and three-wire systems of wiring.

6. Under what general heads are approved methods of wiring classified?

7. A single-phase induction motor is to be supplied with 25 amperes at 220 volts; alternations 12,000 per minute; power factor .8. The transformer is 200 feet from the motor, the line consisting of No. 4 wire, 9 inches between centers of conductors. The transformer reduces in the ratio $\frac{2,500}{250}$, has a capacity of 30 amperes at 220 volts, and, when delivering this current and voltage, has a resistance-E. M. F. of 2.5 per cent, and a reactance E. M. F. of 5 per cent. Calculate the drop. (Use table and chart.)

8. What are the distinctive features of the different kinds of metal conduit?

9. Suppose power to be delivered, 300 K. W.; E. M. F. to be delivered, 2,200 volts; distance of transmission, 15,000 feet; size of wire, No. 00; distance between wires, 24 inches; power factor of load, .7; frequency, 100 cycles per second. Calculate line loss and drop in per cent of E. M. F. delivered. (Use table and chart.)

10. In installing A. C. circuits, what requirements are insisted on as to the placing of conductors in conduits?

INDEX

The page numbers of this volume will be found at the bottom of the pages; the numbers at the top refer only to the section.

	Page
A	
Adjustable tongs	274
Air	
analysis of	18
force for moving	21
measurement of velocity of	21
required for ventilation	19
Air-compressor	199
Air distribution	22
Air-filters and air-washers	204
Air-valves	68, 119, 269
Air-venting	115
Alternating-current circuits	330
calculation of	334
line capacity	333
mutual induction	332
skin effect	332
Armored cable	296
Artificial water line	244
Aspirating heaters and coils	255
Atmosphere, composition of	17
Auto-valve	261
Automatic return-pumps	140
B	
Back-pressure valve	138, 258
Balance pipe	141
Blow-off tank	78
Boiler	
cast-iron	225
coke	229
foundations	229
selection of	227
setting	229
for soft coal	228
Boiler capacity	232
Boiler connections	230
Boiler fittings	232
Boiler foundations	229
Boiler horse-power	46
Boiler setting	229
Breast drill	276
Brick setting for boilers	229
British thermal unit	23
Bullhead tee	267
Bushings	355
By-pass	259
C	
Cast-iron boilers	225
Centrifugal fan	170
theory of	173
Centrifugal pumps	130
Chimney flues	38
Circuit system of steam piping	240
Circulation coils	55
Coal consumption	233
Coils	
miter	237
return-bend	237
wall	236
Coke boilers	229
Coke fitter attached to heater	256
Cold-air ducts	92
Composition of atmosphere	
carbonic acid gas	17
nitrogen	17
oxygen	17
Computing radiation	252
Concealed knob and tube wiring	303
Concealed radiators	235

Note.—For page numbers see foot of pages.

	Page
Conductors, calculation of sizes of	315
Conduit bushing	355
Connections for boilers	230
Crib-bracing	364
Cross-arms	365
Cut-out panel	357
D	
Damper regulators	144
Dampers	87, 202
Diaphragm motors	202
Direct hot-water heating	114, 107
air-venting	115
circulation systems	108
combination systems	117
expansion tank	113
fittings	120
overhead distribution	113
pipe connections	115
piping systems	111
radiating surface, types of	109
radiators, efficiency	110
valves	119
Direct-indirect radiation, computing	254
Direct-indirect radiators	14, 238
Direct radiation, computing	252
Direct radiators	234
Direct steam heating	12, 52
blow-off tank	78
boiler connections	77
cast-iron radiators	53
circulation coils	55
pipe radiators	55
pipe sizes	70
pipes, expansion of	66
piping systems	
one-pipe circuit	64
one-pipe relief	62
two-pipe	59
radiators	
connections of	65
efficiency of	57
location of	59
returns	76
valves	68
Disc or propeller fans	182
Draining mains and risers	243
Drills	275
Drop in A. C. lines	334
Dry return system of steam piping	240
Ducts and flues, areas of	255
E	
Edison fuse-plug	357
Efficiency of	
heaters	84
pipe heaters	162
radiators	57, 110
Electric heat and energy	196
Electric heaters	
calculation of	197
connections for	197
construction of	196
Electric heating	16, 196
cost of	198
heaters	197
Electric motors	187
Electric wiring	291–377
Exhaust head	140
Exhaust method of forced blast	157
Exhaust-steam heating	15, 134, 256
automatic return-pumps	140
back-pressure valve	138, 258
coke fitter	257
damper-regulators	144
exhaust head	140
float trap	260
grease extractor	137
pipe connections	145
pressure-reducing valve	257
reducing valves	136
return traps	142, 260
Expansion	
amount of	249
of pipes	66
provision for	250
radiator connections	251
of risers	250
Expansion tank	113
F	
Fan engines	185
Fans	169
centrifugal	170
disc or propeller	181

Note.—For page numbers see foot of pages.

	Page
Fans	
electric motors for	187
engines for	185
Fiber conduit	373
Fibrous tubing	305
Firepot	33
Fittings for boilers	232
Fittings for heating systems	266
Flat jaw vise	267
Flexible metal conduit	294
Float trap	260
Flue velocities	255
Forced blast	157
cast-iron heaters, efficiency of	167
double-duct system	193
ducts and flues, area of	188
exhaust method	157
for factory heating	189
fan engines	185
fans	169
heating surface, forms of	158
pipe heaters, efficiency of	162
plenum method	158
Forced blast heating	16
Forced hot-water circulation	127
heaters	132
mains and branches, sizes of	128
piping systems	127
pumps	130
Foundations for boilers	229
Furnace heating	29
chimney flues	38
cold-air box	38
combination systems	43
combustion chamber	34
efficiency	35
firepots	33
furnaces	
care and management	44
location of	37
types of	30
grates	32
heating capacity	36
heating surface	35
radiators	34
registers	43
return duct	39

	Page
Furnace heating	
smoke-pipes	37
warm-air pipes	40
Furnaces	11
care and management of	44
types of	30
Fuse-boxes	356
G	
Galvanometer	327
Guy cable	364
Gate-valves	119
Globe valve	68
Grates	32
Grease extractor	137
Grate surface	233
Grates, arrangement of	227
H	
Heat given off by steam radiators	239
Heat loss from buildings	
by air-leakage	24
by ventilation	28
per walls and windows	23
Heaters, hot-water	276
Heating capacity of boilers	233
Heating systems, pipe for	263
Heating and ventilation of	
apartment houses	219
churches	214
greenhouse and conservatories	219
halls	216
hospitals	212
office buildings	217
school buildings	206
theaters	216
Heating and ventilation systems, care and management of	221
Horse-power for ventilation	52
Hot-water heaters	104
care and management of	126
Hot-water heating	276
ducts and flues	286
forced circulation system	285
heaters	276
open-tank vs. pressure system	284
piping for	280
connections	280

Note.—For page numbers see foot of pages.

	Page
Hot-water heating	
piping for	
expansion-tank connections	283
overhead-feed system	282
radiator connections	283
single-main system	280
two-pipe up-feed system	281
radiation of, computing	285
radiators and valves	278
Humidostat	203
I	
Indirect hot-water heating	15, 123
flues and casings	125
pipe connections	125
pipe sizes	126
radiators, types of	124
stacks, size of	124
Indirect radiation, computing	254
Indirect radiators	238
Indirect steam heating	13, 81
cold-air ducts	92
dampers	87
direct-indirect radiators	101
heaters	
efficiency of	84
types of	82
pipe connections	99
pipe sizes	100
registers	97
stacks and casings	87
vent flues	93
warm-air flues	91
Insulators	367
wires run exposed on	
accessibility	307
cheapness	306
durability	306
K	
Key-pattern air-valves	279
Knob and tube wiring	304
L	
Lightning arresters	368
Line capacity	333
Linework	
overhead	358
underground	369
M	
Magneto	327
Mains and risers, draining	243
Manholes	377
Mercury seal vacuum systems of steam heating	262
Miter coils	237
Monkey wrench	275
Moulding, wires run in	299
tual induction	332
O	
One-pipe system of steam piping	243
Outlet-boxes	353
Overhead feed system of steam piping	241
Overhead linework	358
corners	365
cross-arms	365
insulators	367
lamps on poles	369
lightning arresters	368
pins	367
pole guying	362
poles for	360
poles, placing of	359
service mains	367
P	
Paul vacuum heating system	155
Pipe cutters	271
Pipe and fittings for heating systems	263
Pipe tongs	273
Pipe vise	267
Pipe wrenches	274
Pipe-fitting tools	271
Plenum method of forced blast	158
Pliers	275
Pole guying	362
Poles for overhead linework	360
Polyphase circuits	343
Porcelain insulators	308
Pressure-reducing valve	257
R	
Radiation	
direct, computing	252
direct-indirect, computing	254
indirect, computing	254

Note.—For page numbers see foot of pages.

	Page
Radiation of hot-water heating, computing	285
Radiator valves	268
Radiators	
efficiency of	57
hot-water	278
steam	234
Ratchet drill	276
Reamers	275
Reducing valves	136
Registers	43
area of	255
Return-bend coils	237
Return-bend wrench	275
Return traps	142, 260
Rigid conduit	291
S	
Screw-joint fiber conduit	374
Sectional boilers	49
Setting, boiler	229
Siphon trap	244
Skin effect in A. C. circuits	332
Sleeve-joint fiber conduit	374
Sleeves for pipes	267
Soft coal boilers	228
Spud wrench	275
Stacks and casings	87
Steam boilers	46
cast-iron, with vertical sections	226
coal consumption	233
connections	230
fittings	232
foundation	229
grates	227
grate surface	233
heating capacity	233
non-conducting coverings	234
sectional	49
selection of	227
setting	229
small cast-iron	225
for soft coal	228
tubular	46
Steam heating	
mercury seal vacuum systems	262
pipe for	263
thermograde system	261
vapor system	261

	Page
Steam-heating boilers, care and management of	102
Steam and hot-water fitting	225–288
Steam piping	
artificial water line	244
circuit systems	240
draining mains and risers	243
dry return system	240
one-pipe system	243
overhead feed system	241
pipe sizes	245
two-pipe system	243
wet return system	241
Steam pressures and temperatures	248
Steam radiators	
concealed	235
direct	234
direct-indirect	238
heat given off by	239
indirect	238
Steel armored cable	296
Stocks and dies	272
Stoves	11
Swinging-check valve	269
T	
Table	
air, number of changes in, required in various rooms	21
air, power required for moving under different pressures	180
air, quantity of, required per person	20
air required for ventilation of various classes of buildings	20
air-flow per flues of various heights under varying conditions of temperature	96
armored conductors, types, dimensions, etc.	298
boiler, size of, for different conditions	48
circuit mains, sizes of	240
conductors, size of, in fibrous conduits	305
conduit, single wire in	292
conduit, two wires in one	293
conduit, three wires in one	293
direct radiating surface supplied by mains of different sizes and lengths of run	121

Note.—For page numbers see foot of pages.

Table	Page
disc fans, capacity, speed, etc.	185
drop in A. C. lines, data for calculating	337
expansion tanks, radiation capacities of	285
fan speeds, pressures and velocities of air-flow	175
fans, effective area of	177
fiber conduit	375
firepot dimensions	37
flexible steel conduit, Greenfield	295
flow of steam in pipes of other lengths than 100 ft., factors for calculating	72
flow of steam in pipes under initial pressure above 5 lbs., factors for calculating	71
flow of steam in pipes of various sizes, etc.	71
grate area per H. P. for different rates of evaporation and combustion	47
heat loss, factor for calculating, for other than southern exposures	25
heat losses in B. T. U. per square foot of surface per hour, southern exposure	24
heat units emitted from radiators and coils	239
heaters, forced blast, dimensions of	165
heating surface supplied by pipes of various sizes	74
heating system, relative cost of	14
indirect radiating surface supplied by pipes of various sizes	101
indirect radiators, sizes of supply connections for	247
mains, sizes of, for different conditions	131
mouldings, sizes of, required for various sizes of conductors	302
one-pipe risers, capacities of	246
oval pipe dimensions	42
pipe dimensions and data, standard weight	264
pipe heater data	164
pipe sizes	169
pipe sizes from boiler to main header	77
pipe sizes for radiator connections	76
pipes, proper distance to screw into fittings	272
pole data	361
radiating surface on different floors supplied by pipes of different sizes	121
radiating surface supplied by pipes of various sizes, indirect hot-water system	126
radiating surface supplied by steam risers	75
radiators, coils, etc., efficiency of	57
registers, sizes of for different sizes of pipes	43
return, blow-off, and feed pipes, sizes of	78
rigid, enameled conduit, size, dimensions, etc.	292
skin effect, data for calculating	332
steam pipes, size of returns for	76
supply mains, gravity return system, capacity of, etc.	246
temperature of steam at various pressures	248
two-pipe risers, capacities of	247
vitrified conduit, standard	371
warm-air pipe dimensions	40
Telethermometer	203
Temperature regulators	299
air-compressor	199
dampers	202
diaphragm motors	202
diaphragm valve	201
humidostat	203
telethermometer	203
thermostat	200
Temperature of steam at various pressures	248
Testing electric wiring equipment	
magneto method	327
portable galvanometer method	327
voltmeter method	327
Thermograde system of steam heating	261
Thermostat	152, 200
Three-wire system of electric wiring, details of	312

Note.—For page numbers see foot of pages.

690 03/05 9
42529

	Page
Tubular boilers	46
Two-pipe system of steam piping	243
Two-wire system of electric wiring	310
U	
Underground linework	369
conduit, laying of	372
drawing in the cables	376
fiber conduit	373
iron pipe	370
manholes	377
vitrified tile conduit	370
V	
Vacuum heating systems	
Paul	155
Webster	151
Vacuum valve	70
Valves	68, 268
Vapor system of steam heating	261
Vector diagram	334
Vent flues	93
Ventilation	
air required for	19
horse-power for	52
principles of	17
Vitrified tile conduit	370
Voltmeter	327
W	
Wall coils	236
Wall radiators	235
Warm-air flues	91
Warming, systems of	
direct hot water	14
direct-indirect radiators	14
direct steam	12
electric heating	16
Warming, systems of	
exhaust steam	15
forced blast	16
furnaces	11
indirect hot water	15
indirect steam	13
stoves	11
Water-seal motor	152
Water-tube boilers	49
Webster vacuum heating system	151
Wet return system of steam piping	241
Wiring, methods of	291
concealed knob and tube	303
wires run concealed in conduits	29
armored cable	296
in flexible metal conduits	294
in rigid conduits	291
wires run exposed on insulators	306
wires run in moulding	299
Wiring, systems of	310
Wiring an office building	
basement, plan of	345
character of load	345
electric current supply	344
feeders and mains	345
first floor plan	348
interconnection system	348
second floor plan	348
switchboard	345
upper floor plan	348
Wiring installation, method of planning	
feeders and mains	326
outlets, location of	320
testing	326
wiring, method of	319
wiring, systems of	320
Wrought-iron pipe, notes on	265

Note.—For page numbers see foot of pages.